BBMP (Ward No 06)

BRUHAT BANGALORE MAHANAGARA PALIKE

NAME OF WORK:- Improvements to Roads and Drains at Mariyannapalya, Munikempanna Layout, Bhuvaneshwarinagra, Dasarahalli Balance Roads and Surrounding Area in Ward No.06 Byatarayanapura Sub Division

MODIFIED ESTIMATE

Chainage From	Chainage To	Description of Item	Unit	No	Length (m)	Breadth B1	Breadth B2	Breadth Avg B	Depth (m)	Quantity	Rate in RS.	Amount in RS.
Item no.01		Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0.00	2.50		Cum	1	2.50	0.90	0.90	0.90	0.90	2.03		
2.50	15.00		Cum	1	12.50	0.90	0.90	0.90	0.90	10.13		
15.00	18.40		Cum	1	3.40	0.90	0.90	0.90	0.90	2.75		
18.40	24.40		Cum	1	6.00	0.90	0.90	0.90	0.90	4.86		
24.40	35.00		Cum	1	10.60	0.90	0.90	0.90	0.90	8.59		
35.00	50.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
50.00	64.10		Cum	1	14.10	0.90	0.90	0.90	0.90	11.42		
64.10	75.00		Cum	1	10.90	0.90	0.90	0.90	0.90	8.83		
75.00	87.80		Cum	1	12.80	0.90	0.90	0.90	0.90	10.37		
87.80	91.80		Cum	1	4.00	0.90	0.90	0.90	0.90	3.24		
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	19.40		Cum	1	4.40	0.90	0.90	0.90	0.90	3.56		
19.40	28.20		Cum	1	8.80	0.90	0.90	0.90	0.90	7.13		
28.20	33.50		Cum	1	5.30	0.90	0.90	0.90	0.90	4.29		
33.50	42.50		Cum	1	9.00	0.90	0.90	0.90	0.90	7.29		
42.50	54.90		Cum	1	12.40	0.90	0.90	0.90	0.90	10.04		
54.90	65.70		Cum	1	10.80	0.90	0.90	0.90	0.90	8.75		
65.70	74.10		Cum	1	8.40	0.90	0.90	0.90	0.90	6.80		
74.10	85.00		Cum	1	10.90	0.90	0.90	0.90	0.90	8.83		
85.00	92.80		Cum	1	7.80	0.90	0.90	0.90	0.90	6.32		
		Joseph House Road (W0884)										
		LHS										
		East to West										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	36.40		Cum	1	6.40	0.90	0.90	0.90	0.90	5.18		
36.40	48.80		Cum	1	12.40	0.90	0.90	0.90	0.90	10.04		
		RHS										
		West to East										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	27.60		Cum	1	12.60	0.90	0.90	0.90	0.90	10.21		
		1st Main Road (W1307)										
		LHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	22.70		Cum	1	7.70	0.90	0.90	0.90	0.90	6.24		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	17.60		Cum	1	2.60	0.90	0.90	0.90	0.90	2.11		
17.60	23.40	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00		
23.40	30.00		Cum	1	6.60	0.90	0.90	0.90	0.90	5.35		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	55.20		Cum	1	10.20	0.90	0.90	0.90	0.90	8.26		
55.20	60.30	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00		
60.30	75.00		Cum	1	14.70	0.90	0.90	0.90	0.90	11.91		
75.00	86.30		Cum	1	11.30	0.90	0.90	0.90	0.90	9.15		
86.30	91.50	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00		
91.50	105.00		Cum	1	13.50	0.90	0.90	0.90	0.90	10.94		
105.00	120.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
120.00	131.50		Cum	1	11.50	0.90	0.90	0.90	0.90	9.32		

Scanned by CamScanner

		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	19.20		Cum	1	4.20	0.90	0.90	0.90	0.90	3.40		
19.20	25.50		Cum	1	6.30	0.90	0.90	0.90	0.90	5.10		
25.50	30.00		Cum	1	4.50	0.90	0.90	0.90	0.90	3.65		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	75.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
75.00	90.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
90.00	105.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
105.00	120.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
120.00	125.90		Cum	1	5.90	0.90	0.90	0.90	0.90	4.78		
		Cross Road 1 (W0870)										
		East to West										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	26.10		Cum	1	11.10	0.90	0.90	0.90	0.90	8.99		
		Cross Road 2 (W0862)										
		East to West										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	33.80		Cum	1	3.80	0.90	0.90	0.90	0.90	3.08		
		Cross Road 3										
		East to West										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	37.50		Cum	1	7.50	0.90	0.90	0.90	0.90	6.08		
		Cross Road (W1297)										
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	106.70		Cum	1	1.70	1.10	1.10	1.10	0.90	1.68		
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	107.20		Cum	1	2.20	1.10	1.10	1.10	0.90	2.18		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	29.80		Cum	1	14.80	0.90	0.90	0.90	0.90	11.99		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		

Scanned by CamScanner

45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	61.80		Cum	1	1.80	0.90	0.90	0.90	0.90	1.46		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	66.90		Cum	1	6.90	0.90	0.90	0.90	0.90	5.59		
		Dead END										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	16.80		Cum	1	1.80	0.90	0.90	0.90	0.90	1.46		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	63.10		Cum	1	3.10	0.90	0.90	0.90	0.90	2.51		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	66.30		Cum	1	6.30	0.90	0.90	0.90	0.90	5.10		
		Dead END										
0.00	5.80		Cum	1	5.80	0.90	0.90	0.90	0.90	4.70		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	45.80		Cum	1	0.80	0.90	0.90	0.90	0.90	0.65		
45.80	59.20		Cum	1	13.40	0.90	0.90	0.90	0.90	10.85		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	27.00		Cum	1	12.00	0.90	0.90	0.90	0.90	9.72		
27.00	41.80		Cum	1	14.80	0.90	0.90	0.90	0.90	11.99		
41.80	55.00		Cum	1	13.20	0.90	0.90	0.90	0.90	10.69		
55.00	60.20		Cum	1	5.20	0.90	0.90	0.90	0.90	4.21		
		Dead END										
0.00	7.30		Cum	1	7.30	0.90	0.90	0.90	0.90	5.91		
		1st Main Road (W0612)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	36.60		Cum	1	6.60	0.90	0.90	0.90	0.90	5.35		
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	53.30		Cum	1	8.30	1.10	1.10	1.10	0.90	8.22		
53.30	61.10	Road Break	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
61.10	70.70		Cum	1	9.60	1.10	1.10	1.10	0.90	9.50		
70.70	85.00		Cum	1	14.30	1.10	1.10	1.10	0.90	14.16		
85.00	100.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
100.00	115.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
115.00	125.80		Cum	1	10.80	1.10	1.10	1.10	0.90	10.69		

Scanned by CamScanner

		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	18.40		Cum	1	3.40	1.10	1.10	1.10	0.90	3.37		
18.40	30.00		Cum	1	11.60	1.10	1.10	1.10	0.90	11.48		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	49.10		Cum	1	4.10	1.10	1.10	1.10	0.90	4.06		
49.10	55.00		Cum	1	5.90	1.10	1.10	1.10	0.90	5.84		
55.00	64.80		Cum	1	9.80	1.10	1.10	1.10	0.90	9.70		
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	30.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
30.00	45.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	74.20		Cum	1	14.20	1.10	1.10	1.10	0.90	14.06		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	20.20		Cum	1	5.20	1.10	1.10	1.10	0.90	5.15		
20.20	33.00	No Work	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
33.00	45.00		Cum	1	12.00	1.10	1.10	1.10	0.90	11.88		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	68.40		Cum	1	8.40	1.10	1.10	1.10	0.90	8.32		
68.40	74.60		Cum	1	6.20	1.10	1.10	1.10	0.90	6.14		
74.60	85.00		Cum	1	10.40	1.10	1.10	1.10	0.90	10.30		
85.00	100.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
100.00	115.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
115.00	128.50		Cum	1	13.50	1.10	1.10	1.10	0.90	13.37		
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	17.60		Cum	1	2.60	1.10	1.10	1.10	0.90	2.57		
17.60	21.80		Cum	1	4.20	1.10	1.10	1.10	0.90	4.16		
21.80	26.50		Cum	1	4.70	1.10	1.10	1.10	0.90	4.65		
26.50	36.40		Cum	1	9.90	1.10	1.10	1.10	0.90	9.80		
36.40	46.80		Cum	1	10.40	1.10	1.10	1.10	0.90	10.30		
46.80	57.20		Cum	1	10.40	1.10	1.10	1.10	0.90	10.30		
57.20	70.00		Cum	1	12.80	1.10	1.10	1.10	0.90	12.67		
70.00	78.40		Cum	1	8.40	1.10	1.10	1.10	0.90	8.32		
78.40	82.50	No Work	Cum	1	0.00	1.10	1.10	1.10	0.90	0.00		
82.50	91.00		Cum	1	8.50	1.10	1.10	1.10	0.90	8.42		
91.00	95.30		Cum	1	4.30	1.10	1.10	1.10	0.90	4.26		
95.30	104.20		Cum	1	8.90	1.10	1.10	1.10	0.90	8.81		
104.20	113.40		Cum	1	9.20	1.10	1.10	1.10	0.90	9.11		
113.40	128.20		Cum	1	14.80	1.10	1.10	1.10	0.90	14.65		
		Connecting Road 1 (W0608)										
		RHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	23.80		Cum	1	8.80	0.90	0.90	0.90	0.90	7.13		
		LHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	25.40		Cum	1	10.40	0.90	0.90	0.90	0.90	8.42		
		Dead END (W0965)										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	17.70		Cum	1	2.70	0.90	0.90	0.90	0.90	2.19		
		Connecting Road 2										
		RHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	21.60		Cum	1	6.60	0.90	0.90	0.90	0.90	5.35		
		LHS										

Scanned by CamScanner

0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	23.90		Cum	1	8.90	0.90	0.90	0.90	0.90	7.21		
		1st Main, 1st A Cross (W0975)										
0.00	15.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
15.00	20.50		Cum	1	5.50	1.10	1.10	1.10	0.90	5.45		
20.50	30.30		Cum	1	9.80	1.10	1.10	1.10	0.90	9.70		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	60.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
60.00	74.40		Cum	1	14.40	0.90	0.90	0.90	0.90	11.66		
0.00	10.70		Cum	1	10.70	1.10	1.10	1.10	0.90	10.59		
10.70	25.00		Cum	1	14.30	1.10	1.10	1.10	0.90	14.16		
25.00	32.50		Cum	1	7.50	1.10	1.10	1.10	0.90	7.43		
32.50	45.00		Cum	1	12.50	1.10	1.10	1.10	0.90	12.38		
45.00	60.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
60.00	75.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
75.00	90.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
90.00	105.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
105.00	120.00		Cum	1	15.00	1.10	1.10	1.10	0.90	14.85		
120.00	121.20		Cum	1	1.20	1.10	1.10	1.10	0.90	1.19		
		LHS										
		South to North										
0.00	14.20		Cum	1	14.20	0.85	0.85	0.85	0.90	10.86		
14.20	25.00		Cum	1	10.80	0.85	0.85	0.85	0.90	8.26		
25.00	40.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
40.00	65.00		Cum	1	25.00	0.85	0.85	0.85	0.90	19.13		
65.00	76.60		Cum	1	11.60	0.85	0.85	0.85	0.90	8.87		
		2nd A Main Road (W0616)										
		RHS										
0.00	15.00		Cum	1	15.00	1.00	1.00	1.00	0.90	13.50		
15.00	26.50		Cum	1	11.50	1.00	1.00	1.00	0.90	10.35		
26.50	35.70		Cum	1	9.20	1.00	1.00	1.00	0.90	8.28		
35.70	46.40		Cum	1	10.70	1.00	1.00	1.00	0.90	9.63		
46.40	58.00		Cum	1	11.60	1.00	1.00	1.00	0.90	10.44		
58.00	70.60		Cum	1	12.60	1.00	1.00	1.00	0.90	11.34		
70.60	83.30		Cum	1	12.70	1.00	1.00	1.00	0.90	11.43		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	27.20		Cum	1	12.20	0.90	0.90	0.90	0.90	9.88		
27.20	36.90		Cum	1	9.70	0.90	0.90	0.90	0.90	7.86		
36.90	44.40		Cum	1	7.50	0.90	0.90	0.90	0.90	6.08		
44.40	50.00		Cum	1	5.60	0.90	0.90	0.90	0.90	4.54		
50.00	65.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
65.00	75.00		Cum	1	10.00	0.90	0.90	0.90	0.90	8.10		
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	25.10		Cum	1	10.10	0.90	0.90	0.90	0.90	8.18		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0.00	15.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
15.00	30.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
30.00	45.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
45.00	60.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
60.00	75.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
75.00	85.60		Cum	1	10.60	0.85	0.85	0.85	0.90	8.11		
		Dead END (W0965)										
0.00	15.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		

Scanned by CamScanner

15.00	30.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
30.00	35.70		Cum	1	5.70	0.85	0.85	0.85	0.90	4.36		
		Dasarahalli Main Road (M0022)										
		RHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	59.10		Cum	1	14.10	0.90	0.90	0.90	0.90	11.42		
		20th R Cross Road (W0961)										
		RHS										
0.00	15.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
15.00	30.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
30.00	45.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
45.00	47.50		Cum	1	2.50	0.90	0.90	0.90	0.90	2.03		
47.50	53.00	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.90	0.00		
53.00	65.00		Cum	1	12.00	0.90	0.90	0.90	0.90	9.72		
65.00	80.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
80.00	95.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
95.00	99.70		Cum	1	4.70	0.90	0.90	0.90	0.90	3.81		
99.70	112.00		Cum	1	12.30	0.90	0.90	0.90	0.90	9.96		
112.00	125.00		Cum	1	13.00	0.90	0.90	0.90	0.90	10.53		
125.00	140.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
140.00	155.00		Cum	1	15.00	0.90	0.90	0.90	0.90	12.15		
155.00	159.90		Cum	1	4.90	0.90	0.90	0.90	0.90	3.97		
		LHS										
0.00	15.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
15.00	30.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
30.00	40.50		Cum	1	10.50	0.85	0.85	0.85	0.90	8.03		
40.50	55.00		Cum	1	14.50	0.85	0.85	0.85	0.90	11.09		
55.00	65.50		Cum	1	10.50	0.85	0.85	0.85	0.90	8.03		
65.50	70.70	Culvert	Cum	1	0.00	0.85	0.85	0.85	0.90	0.00		
70.70	85.00		Cum	1	14.30	0.85	0.85	0.85	0.90	10.94		
85.00	100.00		Cum	1	15.00	0.85	0.85	0.85	0.90	11.48		
100.00	111.80		Cum	1	11.80	0.85	0.85	0.85	0.90	9.03		
111.80	116.90	No Work	Cum	1	0.00	0.85	0.85	0.85	0.90	0.00		
116.90	130.00		Cum	1	13.10	0.85	0.85	0.85	0.90	10.02		
130.00	144.50		Cum	1	14.50	0.85	0.85	0.85	0.90	11.09		
144.50	148.70	No Work	Cum	1	0.00	0.85	0.85	0.85	0.90	0.00		
148.70	164.30		Cum	1	15.60	0.85	0.85	0.85	0.90	11.93		
		2nd Cross (W0983) Dead End										
0.00	13.20		Cum	1	13.20	0.90	0.90	0.90	0.90	10.69		
		Dasarahalli Circle										
0.00	15.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
15.00	30.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
30.00	45.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
45.00	60.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
60.00	75.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
75.00	90.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
90.00	105.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
105.00	120.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
120.00	135.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
135.00	150.00		Cum	1	15.00	1.35	1.35	1.35	1.25	25.31		
150.00	159.00		Cum	1	9.00	1.35	1.35	1.35	1.25	15.19		
		For Culvert										
		Kuvempu Layout										
		2nd Main Road (W0616)	Cum	1	5.75	1.40	1.40	1.40	0.85	6.84		
		1st Main 1st Cross Road (W0973)	Cum	1	8.20	1.40	1.40	1.40	0.85	9.76		
		21st Cross Road (W0969)	Cum	1	6.20	1.40	1.40	1.40	0.85	7.38		
			Cum	1	10.40	1.40	1.40	1.40	0.85	12.38		
		Dead End Road (W0965)	Cum	1	8.10	1.40	1.40	1.40	0.85	9.64		
		21st Cross Road (W0969)	Cum	1	7.40	1.40	1.40	1.40	0.85	8.81		
		Dasarahalli Main Road (M0022)	Cum	1	7.00	1.40	1.40	1.40	0.85	8.33		
		1st Main Road (W0612)	Cum	1	7.70	1.40	1.40	1.40	0.85	9.16		
			Cum	1	4.70	1.40	1.40	1.40	0.85	5.59		
			Cum	1	9.50	1.40	1.40	1.40	0.85	11.31		

Scanned by CamScanner

		20th R Cross Road (W0961)	Cum	1	7.00	1.40	1.40	1.40	0.85	8.33		
		18th A Cross Road (W0618)	Cum	1	6.30	1.40	1.40	1.40	0.85	7.50		
		1st Main Road (W0612)	Cum	1	5.50	1.40	1.40	1.40	0.85	6.55		
		Mariyanna Palya										
		Joseph House Road (W0884)	Cum	1	5.60	1.70	1.70	1.70	0.85	8.09		
		Moto Works Oppo. (W1299)	Cum	1	6.10	1.70	1.70	1.70	0.85	8.81		
			Cum	1	5.80	1.70	1.70	1.70	0.85	8.38		
			Cum	1	5.10	1.70	1.70	1.70	0.85	7.37		
			Cum	1	5.20	1.70	1.70	1.70	0.85	7.51		
		Desilt										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0.00	15.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
15.00	30.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
30.00	37.50	Culvert	Cum	0	0.00	0.75	0.75	0.75	0.75	0.00		
37.50	50.00		Cum	1	12.50	0.75	0.75	0.75	0.75	7.03		
50.00	65.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
65.00	80.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
80.00	94.80		Cum	1	14.80	0.75	0.75	0.75	0.75	8.33		
94.80	103.80	Culvert	Cum	0	0.00	0.75	0.75	0.00	0.75	0.00		
103.80	115.00		Cum	1	11.20	0.75	0.75	0.75	0.75	6.30		
115.00	128.10		Cum	1	13.10	0.75	0.75	0.75	0.75	7.37		
128.10	135.00	Culvert	Cum	0	0.00	0.75	0.75	0.75	0.75	0.00		
135.00	147.30		Cum	1	12.30	0.75	0.75	0.75	0.75	6.92		
147.30	152.50		Cum	1	5.20	0.75	0.75	0.75	0.75	2.92		
152.50	162.00		Cum	1	9.50	0.75	0.75	0.75	0.75	5.34		
162.00	177.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
177.00	191.50		Cum	1	14.50	0.75	0.75	0.75	0.75	8.16		
191.50	200.00		Cum	1	8.50	0.75	0.75	0.75	0.75	4.78		
200.00	215.00		Cum	1	15.00	0.75	0.75	0.75	0.75	8.44		
215.00	228.00		Cum	1	13.00	0.75	0.75	0.75	0.75	7.31		
228.00	240.00		Cum	1	12.00	0.75	0.75	0.75	0.75	6.75		
240.00	244.50		Cum	1	4.50	0.75	0.75	0.75	0.75	2.53		
		Deduction										
		Dasarahalli Circle										
0.00	15.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
15.00	30.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
30.00	45.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
45.00	60.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
60.00	75.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
75.00	90.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
90.00	105.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
105.00	120.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
120.00	135.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
135.00	150.00		Cum	-1	15.00	0.75	0.75	0.75	0.60	-6.75		
150.00	159.00		Cum	-1	9.00	0.75	0.75	0.75	0.60	-4.05		
										Total Executed Quantity	**2995.64**	
										Tender Quantity	**2854.05**	
										Quantity upto 125%	**2995.64**	**215.00**	**644063.00**
Item no.02		Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications and directions of the Engineer in charge.										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
3	10		Cum	2	7.00	0.50	0.50	0.50	0.90	6.30		
16	28		Cum	1	12.00	0.50	0.50	0.50	0.90	5.40		
30	37.5	Culvert	Cum	0	0.00	0.50	0.50	0.50	0.90	0.00		
42	46.3		Cum	2	4.30	0.50	0.50	0.50	0.90	3.87		
55	61		Cum	2	6.00	0.50	0.50	0.50	0.90	5.40		
70	75		Cum	2	5.00	0.50	0.50	0.50	0.90	4.50		
94.8	103.8	Culvert	Cum	0	0.00	0.50	0.50	0.50	0.90	0.00		
105	113		Cum	2	8.00	0.50	0.50	0.50	0.90	7.20		
120	128.1		Cum	2	8.10	0.50	0.50	0.50	0.90	7.29		
128.1	135	Culvert	Cum	0	0.00	0.50	0.50	0.50	0.90	0.00		
141	145		Cum	2	4.00	0.50	0.50	0.50	0.90	3.60		
147.3	152.5		Cum	2	5.20	0.50	0.50	0.50	0.90	4.68		

Scanned by CamScanner

155	162		Cum	2	7.00	0.50	0.50	0.50	0.90	6.30		
169	177		Cum	2	8.00	0.50	0.50	0.50	0.90	7.20		
182	189		Cum	2	7.00	0.50	0.50	0.50	0.90	6.30		
									Total Executed Quantity	**68.04**	**5500.00**	**374220.00**
									Tender Quantity	**68.04**		
Item no.03		Providing and Filling in foundation with granite / trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift. complete as per specifications. and directions of the Engineer in charge.										
		Dasarahalli Circle										
0	15		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
15	30		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
30	45		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
45	60		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
60	75		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
75	90		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
90	105		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
105	120		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
120	135		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
135	150		Cum	1	15.00	1.35	1.35	1.35	0.25	5.06		
150	159		Cum	1	9.00	1.35	1.35	1.35	0.25	3.04		
									Total Executed Quantity	**53.66**	**2700.00**	**144882.00**
									Tender Quantity	**53.66**		
Item no.04		Providing and laying Plain cement concrete of mix1:3:6 with OPC cement @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days Including cost of materials,labour, HOM curing form work, Scaffolding and Centering complete as per specifications and as per the directions of the Engineer-in-charge of the work										
		Drain PCC										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0	2.5		Cum	1	2.50	0.90	0.90	0.90	0.15	0.34		
2.5	15		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
15	18.4		Cum	1	3.40	0.90	0.90	0.90	0.15	0.46		
18.4	24.4		Cum	1	6.00	0.90	0.90	0.90	0.15	0.81		
24.4	35		Cum	1	10.60	0.90	0.90	0.90	0.15	1.43		
35	50		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
50	64.1		Cum	1	14.10	0.90	0.90	0.90	0.15	1.90		
64.1	75		Cum	1	10.90	0.90	0.90	0.90	0.15	1.47		
75	87.8		Cum	1	12.80	0.90	0.90	0.90	0.15	1.73		
87.8	91.8		Cum	1	4.00	0.90	0.90	0.90	0.15	0.54		
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	19.4		Cum	1	4.40	0.90	0.90	0.90	0.15	0.59		
19.4	28.2		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
28.2	33.5		Cum	1	5.30	0.90	0.90	0.90	0.15	0.72		
33.5	42.5		Cum	1	9.00	0.90	0.90	0.90	0.15	1.22		
42.5	54.9		Cum	1	12.40	0.90	0.90	0.90	0.15	1.67		
54.9	65.7		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46		
65.7	74.1		Cum	1	8.40	0.90	0.90	0.90	0.15	1.13		
74.1	85		Cum	1	10.90	0.90	0.90	0.90	0.15	1.47		
85	92.8		Cum	1	7.80	0.90	0.90	0.90	0.15	1.05		
		Joseph House Road (W0884)										
		LHS										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	36.4		Cum	1	6.40	0.90	0.90	0.90	0.15	0.86		
36.4	48.8		Cum	1	12.40	0.90	0.90	0.90	0.15	1.67		
		RHS										
		West to East										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27.6		Cum	1	12.60	0.90	0.90	0.90	0.15	1.70		
		1st Main Road (W1307)										
		LHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Scanned by CamScanner

15	22.7		Cum	1	7.70	0.90	0.90	0.90	0.15	1.04		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	17.6		Cum	1	2.60	0.90	0.90	0.90	0.15	0.35		
17.6	23.4	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
23.4	30		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	55.2		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
55.2	60.3	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
60.3	75		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98		
75	86.3		Cum	1	11.30	0.90	0.90	0.90	0.15	1.53		
86.3	91.5	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
91.5	105		Cum	1	13.50	0.90	0.90	0.90	0.15	1.82		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	131.5		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	19.2		Cum	1	4.20	0.90	0.90	0.90	0.15	0.57		
19.2	25.5		Cum	1	6.30	0.90	0.90	0.90	0.15	0.85		
25.5	30		Cum	1	4.50	0.90	0.90	0.90	0.15	0.61		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	125.9		Cum	1	5.90	0.90	0.90	0.90	0.15	0.80		
		Cross Road 1 (W0870)										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	26.1		Cum	1	11.10	0.90	0.90	0.90	0.15	1.50		
		Cross Road 2 (W0862)										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	33.8		Cum	1	3.80	0.90	0.90	0.90	0.15	0.51		
		Cross Road 3										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	37.5		Cum	1	7.50	0.90	0.90	0.90	0.15	1.01		
		Cross Road (W1297)										
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	106.7		Cum	1	1.70	1.10	1.10	1.10	0.15	0.28		
		RHS										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	107.2		Cum	1	2.20	1.10	1.10	1.10	0.15	0.36		

Scanned by CamScanner

		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	29.8		Cum	1	14.80	0.90	0.90	0.90	0.15	2.00		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	61.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	66.9		Cum	1	6.90	0.90	0.90	0.90	0.15	0.93		
		Dead END										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	16.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	63.1		Cum	1	3.10	0.90	0.90	0.90	0.15	0.42		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	66.3		Cum	1	6.30	0.90	0.90	0.90	0.15	0.85		
		Dead END										
0	5.8		Cum	1	5.80	0.90	0.90	0.90	0.15	0.78		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	45.8		Cum	1	0.80	0.90	0.90	0.90	0.15	0.11		
45.8	59.2		Cum	1	13.40	0.90	0.90	0.90	0.15	1.81		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
27	41.8		Cum	1	14.80	0.90	0.90	0.90	0.15	2.00		
41.8	55		Cum	1	13.20	0.90	0.90	0.90	0.15	1.78		
55	60.2		Cum	1	5.20	0.90	0.90	0.90	0.15	0.70		
		Dead END										
0	7.3		Cum	1	7.30	0.90	0.90	0.90	0.15	0.99		

Scanned by CamScanner

		1st Main Road (W0612)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	36.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	53.3		Cum	1	8.30	1.10	1.10	1.10	0.15	1.37		
53.3	61.1	Road Break	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
61.1	70.7		Cum	1	9.60	1.10	1.10	1.10	0.15	1.58		
70.7	85		Cum	1	14.30	1.10	1.10	1.10	0.15	2.36		
85	100		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	125.8		Cum	1	10.80	1.10	1.10	1.10	0.15	1.78		
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	18.4		Cum	1	3.40	1.10	1.10	1.10	0.15	0.56		
18.4	30		Cum	1	11.60	1.10	1.10	1.10	0.15	1.91		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	49.1		Cum	1	4.10	1.10	1.10	1.10	0.15	0.68		
49.1	55		Cum	1	5.90	1.10	1.10	1.10	0.15	0.97		
55	64.8		Cum	1	9.80	1.10	1.10	1.10	0.15	1.62		
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	74.2		Cum	1	14.20	1.10	1.10	1.10	0.15	2.34		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	20.2		Cum	1	5.20	1.10	1.10	1.10	0.15	0.86		
20.2	33	No Work	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
33	45		Cum	1	12.00	1.10	1.10	1.10	0.15	1.98		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	68.4		Cum	1	8.40	1.10	1.10	1.10	0.15	1.39		
68.4	74.6		Cum	1	6.20	1.10	1.10	1.10	0.15	1.02		
74.6	85		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
85	100		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	128.5		Cum	1	13.50	1.10	1.10	1.10	0.15	2.23		
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	17.6		Cum	1	2.60	1.10	1.10	1.10	0.15	0.43		
17.6	21.8		Cum	1	4.20	1.10	1.10	1.10	0.15	0.69		
21.8	26.5		Cum	1	4.70	1.10	1.10	1.10	0.15	0.78		
26.5	36.4		Cum	1	9.90	1.10	1.10	1.10	0.15	1.63		
36.4	46.8		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
46.8	57.2		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
57.2	70		Cum	1	12.80	1.10	1.10	1.10	0.15	2.11		
70	78.4		Cum	1	8.40	1.10	1.10	1.10	0.15	1.39		
78.4	82.5	No Work	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
82.5	91		Cum	1	8.50	1.10	1.10	1.10	0.15	1.40		
91	95.3		Cum	1	4.30	1.10	1.10	1.10	0.15	0.71		
95.3	104.2		Cum	1	8.90	1.10	1.10	1.10	0.15	1.47		
104.2	113.4		Cum	1	9.20	1.10	1.10	1.10	0.15	1.52		
113.4	128.2		Cum	1	14.80	1.10	1.10	1.10	0.15	2.44		
		Connecting Road 1 (W0608)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.8		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		

Scanned by CamScanner

		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.4		Cum	1	10.40	0.90	0.90	0.90	0.15	1.40		
		Dead END (W0965)										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	17.7		Cum	1	2.70	0.90	0.90	0.90	0.15	0.36		
		Connecting Road 2										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	21.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.9		Cum	1	8.90	0.90	0.90	0.90	0.15	1.20		
		1st Main, 1st A Cross (W0975)										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	20.5		Cum	1	5.50	1.10	1.10	1.10	0.15	0.91		
20.5	30.3		Cum	1	9.80	1.10	1.10	1.10	0.15	1.62		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	74.4		Cum	1	14.40	0.90	0.90	0.90	0.15	1.94		
0	10.7		Cum	1	10.70	1.10	1.10	1.10	0.15	1.77		
10.7	25		Cum	1	14.30	1.10	1.10	1.10	0.15	2.36		
25	32.5		Cum	1	7.50	1.10	1.10	1.10	0.15	1.24		
32.5	45		Cum	1	12.50	1.10	1.10	1.10	0.15	2.06		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	120		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120	121.2		Cum	1	1.20	1.10	1.10	1.10	0.15	0.20		
		LHS										
		South to North										
0	14.2		Cum	1	14.20	0.85	0.85	0.85	0.15	1.81		
14.2	25		Cum	1	10.80	0.85	0.85	0.85	0.15	1.38		
25	40		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
40	65		Cum	1	25.00	0.85	0.85	0.85	0.15	3.19		
65	76.6		Cum	1	11.60	0.85	0.85	0.85	0.15	1.48		
		2nd A Main Road (W0616)										
		RHS										
0	15		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15	26.5		Cum	1	11.50	1.00	1.00	1.00	0.15	1.73		
26.5	35.7		Cum	1	9.20	1.00	1.00	1.00	0.15	1.38		
35.7	46.4		Cum	1	10.70	1.00	1.00	1.00	0.15	1.61		
46.4	58		Cum	1	11.60	1.00	1.00	1.00	0.15	1.74		
58	70.6		Cum	1	12.60	1.00	1.00	1.00	0.15	1.89		
70.6	83.3		Cum	1	12.70	1.00	1.00	1.00	0.15	1.91		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27.2		Cum	1	12.20	0.90	0.90	0.90	0.15	1.65		
27.2	36.9		Cum	1	9.70	0.90	0.90	0.90	0.15	1.31		
36.9	44.4		Cum	1	7.50	0.90	0.90	0.90	0.15	1.01		
44.4	50		Cum	1	5.60	0.90	0.90	0.90	0.15	0.76		
50	65		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Scanned by CamScanner

65	75		Cum	1	10.00	0.90	0.90	0.90	0.15	1.35		
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.1		Cum	1	10.10	0.90	0.90	0.90	0.15	1.36		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	45		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
45	60		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
60	75		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
75	85.6		Cum	1	10.60	0.85	0.85	0.85	0.15	1.35		
		Dead END (W0965)										
0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	35.7		Cum	1	5.70	0.85	0.85	0.85	0.15	0.73		
		Dasarahalli Main Road (M0022)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	59.1		Cum	1	14.10	0.90	0.90	0.90	0.15	1.90		
		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	47.5		Cum	1	2.50	0.90	0.90	0.90	0.15	0.34		
47.5	53	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
53	65		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
65	80		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
80	95		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
95	99.7		Cum	1	4.70	0.90	0.90	0.90	0.15	0.63		
99.7	112		Cum	1	12.30	0.90	0.90	0.90	0.15	1.66		
112	125		Cum	1	13.00	0.90	0.90	0.90	0.15	1.76		
125	140		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
140	155		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
155	159.9		Cum	1	4.90	0.90	0.90	0.90	0.15	0.66		
		LHS										
0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	40.5		Cum	1	10.50	0.85	0.85	0.85	0.15	1.34		
40.5	55		Cum	1	14.50	0.85	0.85	0.85	0.15	1.85		
55	65.5		Cum	1	10.50	0.85	0.85	0.85	0.15	1.34		
65.5	70.7	Culvert	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
70.7	85		Cum	1	14.30	0.85	0.85	0.85	0.15	1.82		
85	100		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
100	111.8		Cum	1	11.80	0.85	0.85	0.85	0.15	1.50		
111.8	116.9	No Work	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
116.9	130		Cum	1	13.10	0.85	0.85	0.85	0.15	1.67		
130	144.5		Cum	1	14.50	0.85	0.85	0.85	0.15	1.85		
144.5	148.7	No Work	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
148.7	164.3		Cum	1	15.60	0.85	0.85	0.85	0.15	1.99		
		2nd Cross (W0983) Dead End										
0	13.2		Cum	1	13.20	0.90	0.90	0.90	0.15	1.78		
		Dasarahalli Circle										
0	15		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
15	30		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
30	45		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
45	60		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
60	75		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
75	90		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
90	105		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		

Scanned by CamScanner

105	120		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
120	135		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
135	150		Cum	1	15.00	1.35	1.35	1.35	0.15	3.04		
150	159		Cum	1	9.00	1.35	1.35	1.35	0.15	1.82		
		For Culvert										
		Kuvempu Layout										
		2nd Main Road (W0616)	Cum	1	5.75	1.40	1.40	1.40	0.15	1.21		
		1st Main 1st Cross Road (W0973)	Cum	1	8.20	1.40	1.40	1.40	0.15	1.72		
		21st Cross Road (W0969)	Cum	1	6.20	1.40	1.40	1.40	0.15	1.30		
			Cum	1	10.40	1.40	1.40	1.40	0.15	2.18		
		Dead End Road (W0965)	Cum	1	8.10	1.40	1.40	1.40	0.15	1.70		
		21st Cross Road (W0969)	Cum	1	7.40	1.40	1.40	1.40	0.15	1.55		
		Dasarahalli Main Road (M0022)	Cum	1	7.00	1.40	1.40	1.40	0.15	1.47		
		1st Main Road (W0612)	Cum	1	7.70	1.40	1.40	1.40	0.15	1.62		
			Cum	1	4.70	1.40	1.40	1.40	0.15	0.99		
			Cum	1	9.50	1.40	1.40	1.40	0.15	2.00		
		20th R Cross Road (W0961)	Cum	1	7.00	1.40	1.40	1.40	0.15	1.47		
		18th A Cross Road (W0618)	Cum	1	6.30	1.40	1.40	1.40	0.15	1.32		
		1st Main Road (W0612)	Cum	1	5.50	1.40	1.40	1.40	0.15	1.16		
		Mariyanna Palya										
		Joseph House Road (W0884)	Cum	1	5.60	1.70	1.70	1.70	0.15	1.43		
		Moto Works Oppo. (W1299)	Cum	1	6.10	1.70	1.70	1.70	0.15	1.56		
			Cum	1	5.80	1.70	1.70	1.70	0.15	1.48		
			Cum	1	5.10	1.70	1.70	1.70	0.15	1.30		
			Cum	1	5.20	1.70	1.70	1.70	0.15	1.33		
		For Kerb										
		Mariyanna Palya										
		1st Main Road (W1307)										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	22.7		Cum	1	7.70	0.20	0.20	0.20	0.10	0.15		
		Moto Works Oppo. (W1299)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60	75		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
75	90		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
90	105		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
105	120		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
120	125.9		Cum	1	5.90	0.20	0.20	0.20	0.10	0.12		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	17.6		Cum	1	2.60	0.20	0.20	0.20	0.10	0.05		
17.6	23.4	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
23.4	35		Cum	1	11.60	0.20	0.20	0.20	0.10	0.23		
35	50		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
50	55.2		Cum	1	5.20	0.20	0.20	0.20	0.10	0.10		
55.2	60.3	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
60.3	74		Cum	1	13.70	0.20	0.20	0.20	0.10	0.27		
74	77.3	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
77.3	86.3		Cum	1	9.00	0.20	0.20	0.20	0.10	0.18		
86.3	91.5	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
91.5	105		Cum	1	13.50	0.20	0.20	0.20	0.10	0.27		
105	117.2		Cum	1	12.20	0.20	0.20	0.20	0.10	0.24		
117.2	120.4	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
120.4	131.5		Cum	1	11.10	0.20	0.20	0.20	0.10	0.22		
		Kuvempu Layout										
		2nd Main road 2nd Cross Road (W0616)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	29.8		Cum	1	14.80	0.20	0.20	0.20	0.10	0.30		

Scanned by CamScanner

		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
		1st main 2nd Cross Road (W0983)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	63.1		Cum	1	18.10	0.20	0.20	0.20	0.10	0.36		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60	66.3		Cum	1	6.30	0.20	0.20	0.20	0.10	0.13		
		1st main 1st Cross Road (W0973)										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	24.6		Cum	1	9.60	0.20	0.20	0.20	0.10	0.19		
24.6	27.8	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
27.8	45		Cum	1	17.20	0.20	0.20	0.20	0.10	0.34		
45	58.2		Cum	1	13.20	0.20	0.20	0.20	0.10	0.26		
		LHS										
0	15	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
15	25.6	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
25.6	41.4		Cum	1	15.80	0.20	0.20	0.20	0.10	0.32		
41.4	60.2		Cum	1	18.80	0.20	0.20	0.20	0.10	0.38		
		1st main Road (W0612)										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	40.2		Cum	1	10.20	0.20	0.20	0.20	0.10	0.20		
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	54.3		Cum	1	9.30	0.20	0.20	0.20	0.10	0.19		
54.3	62.1	Road Break										
62.1	77.1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
77.1	92.1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
92.1	107.1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
107.1	122.1		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
122.1	126.8		Cum	1	4.70	0.20	0.20	0.20	0.10	0.09		
		1st main Road (W0612)										
		LHS										
0	15	No work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
15	30	No work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
30	45	No work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
45	50	No work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
50	65		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
65	80		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
80	95		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
95	110		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
110	125		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
125	128.4		Cum	1	3.40	0.20	0.20	0.20	0.10	0.07		
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45.4		Cum	1	15.40	0.20	0.20	0.20	0.10	0.31		
45.4	50.3	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
50.3	65.3		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
65.3	74.8		Cum	1	9.50	0.20	0.20	0.20	0.10	0.19		

vssIFMS - ifms220

Work Order -> View

Scanned by CamScanner

		1st Main 3rd Cross Road (W0989)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	61.8		Cum	1	16.80	0.20	0.20	0.20	0.10	0.34		
		2nd Main Road (W0616)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	21.2		Cum	1	6.20	0.20	0.20	0.20	0.10	0.12		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60	74		Cum	1	14.00	0.20	0.20	0.20	0.10	0.28		
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60	75		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
75	90		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
90	105		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
105	120.8		Cum	1	15.80	0.20	0.20	0.20	0.10	0.32		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	60		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
60	75		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
75	85.6		Cum	1	10.60	0.20	0.20	0.20	0.10	0.21		
		21th Cross Road (W0969)										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	20.2		Cum	1	5.20	0.20	0.20	0.20	0.10	0.10		
20.2	33	No Work										
33	48		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
48	63		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
63	68.4		Cum	1	5.40	0.20	0.20	0.20	0.10	0.11		
68.4	74.6	No Work										
74.6	89.6		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
89.6	104.6		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
104.6	119.6		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
119.6	129.5		Cum	1	9.90	0.20	0.20	0.20	0.10	0.20		
0	0	LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	46.8		Cum	1	16.80	0.20	0.20	0.20	0.10	0.34		
46.8	57.2	old Culvert										
57.2	72.2		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
72.2	87.2		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
87.2	102.2		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
102.2	117.2		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
117.2	128.2		Cum	1	11.00	0.20	0.20	0.20	0.10	0.22		
		Connecting Road-1 (W0608)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	25.4		Cum	1	10.40	0.20	0.20	0.20	0.10	0.21		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	23.8		Cum	1	8.80	0.20	0.20	0.20	0.10	0.18		

Scanned by CamScanner

BBMP (Ward No 06)

		Dead End Road (W0965)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	17		Cum	1	2.00	0.20	0.20	0.20	0.10	0.04		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	23.1		Cum	1	8.10	0.20	0.20	0.20	0.10	0.16		
23.1	35.7	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		Connecting Road -2										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	20.5		Cum	1	5.50	0.20	0.20	0.20	0.10	0.11		
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	23.9		Cum	1	8.90	0.20	0.20	0.20	0.10	0.18		
		1st A Cross Road (W0975)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30.3		Cum	1	15.30	0.20	0.20	0.20	0.10	0.31		
		2nd Main Road (W0616)										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	24.8		Cum	1	9.80	0.20	0.20	0.20	0.10	0.20		
		18th A Cross Road (W0618)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	25		Cum	1	10.00	0.20	0.20	0.20	0.10	0.20		
25	34.8	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
34.8	49.8		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
49.8	54		Cum	1	4.20	0.20	0.20	0.20	0.10	0.08		
54	69	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
69	72.3	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		2nd A Cross Road (W0616)										
		LHS										
0	7.4	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
7.4	25.1		Cum	1	17.70	0.20	0.20	0.20	0.10	0.35		
25.1	40.5	Ramp	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
40.5	55.5		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
55.5	69.9		Cum	1	14.40	0.20	0.20	0.20	0.10	0.29		
69.9	83.1	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
		2nd Main Road (W0616)										
		LHS										
0	8		Cum	1	8.00	0.20	0.20	0.20	0.10	0.16		
8	9.8		Cum	1	1.80	0.20	0.20	0.20	0.10	0.04		
9.8	24.8		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
24.8	36.1		Cum	1	11.30	0.20	0.20	0.20	0.10	0.23		
		Mariyannana Palya										
		1st Main Road (W0973)										
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	29.8		Cum	1	14.80	0.20	0.20	0.20	0.10	0.30		
29.8	37.4	Culvert	Cum	1	7.60	0.20	0.20	0.20	0.10	0.15		
37.4	52.4		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
52.4	67.4		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
67.4	82.4		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
82.4	94.8		Cum	1	12.40	0.20	0.20	0.20	0.10	0.25		
94.8	103.8	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
103.8	118.8		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
118.8	128		Cum	1	9.20	0.20	0.20	0.20	0.10	0.18		
128	135	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
135	147.4		Cum	1	12.40	0.20	0.20	0.20	0.10	0.25		
147.4	152.6	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
152.6	161.5		Cum	1	8.90	0.20	0.20	0.20	0.10	0.18		
161.5	177	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
177	191.7		Cum	1	14.70	0.20	0.20	0.20	0.10	0.29		

VssIFMS - ifms220
Work Order ->View
Scanned by CamScanner

		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	45		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
45	47.5		Cum	1	2.50	0.20	0.20	0.20	0.10	0.05		
47.5	53	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
53	65		Cum	1	12.00	0.20	0.20	0.20	0.10	0.24		
65	80		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
80	95		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
95	99.7		Cum	1	4.70	0.20	0.20	0.20	0.10	0.09		
99.7	112		Cum	1	12.30	0.20	0.20	0.20	0.10	0.25		
112	125		Cum	1	13.00	0.20	0.20	0.20	0.10	0.26		
125	140		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
140	155		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
155	159.9		Cum	1	4.90	0.20	0.20	0.20	0.10	0.10		
		LHS										
0	15		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
15	30		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
30	40.5		Cum	1	10.50	0.20	0.20	0.20	0.10	0.21		
40.5	55		Cum	1	14.50	0.20	0.20	0.20	0.10	0.29		
55	65.5		Cum	1	10.50	0.20	0.20	0.20	0.10	0.21		
65.5	70.7	Culvert	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
70.7	85		Cum	1	14.30	0.20	0.20	0.20	0.10	0.29		
85	100		Cum	1	15.00	0.20	0.20	0.20	0.10	0.30		
100	111.8		Cum	1	11.80	0.20	0.20	0.20	0.10	0.24		
111.8	116.9	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
116.9	130		Cum	1	13.10	0.20	0.20	0.20	0.10	0.26		
130	144.5		Cum	1	14.50	0.20	0.20	0.20	0.10	0.29		
144.5	148.7	No Work	Cum	1	0.00	0.20	0.20	0.20	0.10	0.00		
148.7	164.3		Cum	1	15.60	0.20	0.20	0.20	0.10	0.31		
		For Flagging Coarse										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0	15		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
15	30		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
30	37.5	Culvert	Cum	0	0.00	0.20	0.20	0.20	0.10	0.00		
37.5	50		Cum	2	12.50	0.20	0.20	0.20	0.10	0.50		
50	65		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
65	80		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
80	94.8		Cum	2	14.80	0.20	0.20	0.20	0.10	0.59		
94.8	103.8	Culvert	Cum	0	0.00	0.20	0.20	0.20	0.10	0.00		
103.8	115		Cum	2	11.20	0.20	0.20	0.20	0.10	0.45		
115	128.1		Cum	2	13.10	0.20	0.20	0.20	0.10	0.52		
128.1	135	Culvert	Cum	0	0.00	0.20	0.20	0.20	0.10	0.00		
135	147.3		Cum	2	12.30	0.20	0.20	0.20	0.10	0.49		
147.3	152.5		Cum	2	5.20	0.20	0.20	0.20	0.10	0.21		
152.5	162		Cum	2	9.50	0.20	0.20	0.20	0.10	0.38		
162	177		Cum	2	15.00	0.20	0.20	0.20	0.10	0.60		
177	191.5		Cum	2	14.50	0.20	0.20	0.20	0.10	0.58		
191.5	200	Desilt Only	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
200	215	Desilt Only	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
215	228	Desilt Only	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
228	240	Desilt Only	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
240	244.5	Desilt Only	Cum	2	0.00	0.20	0.20	0.20	0.10	0.00		
										Total Executed Quantity	**530.38**	
										Tender Quantity	**519.33**	
										Quantity upto 125%	**530.38**	**6500.00**	**3447462.00**
Item no.05		Providing laying plain/ reinforced cement concrete for side Drains Using M20 nominal mix Concrete with OPC at 300kgs.With 20mm and Down size granite metal coarse aggregate at 0.69cum and fine aggregate at 0.43cum Machne mixed, well compacted for wall and Bottom including centering shuttering,cost of materials,HOM of Machinery,Curing Etc.,Complete Excluding cost of Steel as per morth MORTH specification and as per the directions of the Engineer-in-charge of the work										
		Bottom Raft										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0	2.5		Cum	1	2.50	0.90	0.90	0.90	0.15	0.34		

Scanned by CamScanner

2.5	15		Cum	1	12.50	0.90	0.90	0.90	0.15	1.69		
15	18.4		Cum	1	3.40	0.90	0.90	0.90	0.15	0.46		
18.4	24.4		Cum	1	6.00	0.90	0.90	0.90	0.15	0.81		
24.4	35		Cum	1	10.60	0.90	0.90	0.90	0.15	1.43		
35	50		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
50	64.1		Cum	1	14.10	0.90	0.90	0.90	0.15	1.90		
64.1	75		Cum	1	10.90	0.90	0.90	0.90	0.15	1.47		
75	87.8		Cum	1	12.80	0.90	0.90	0.90	0.15	1.73		
87.8	91.8		Cum	1	4.00	0.90	0.90	0.90	0.15	0.54		
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	19.4		Cum	1	4.40	0.90	0.90	0.90	0.15	0.59		
19.4	28.2		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
28.2	33.5		Cum	1	5.30	0.90	0.90	0.90	0.15	0.72		
33.5	42.5		Cum	1	9.00	0.90	0.90	0.90	0.15	1.22		
42.5	54.9		Cum	1	12.40	0.90	0.90	0.90	0.15	1.67		
54.9	65.7		Cum	1	10.80	0.90	0.90	0.90	0.15	1.46		
65.7	74.1		Cum	1	8.40	0.90	0.90	0.90	0.15	1.13		
74.1	85		Cum	1	10.90	0.90	0.90	0.90	0.15	1.47		
85	92.8		Cum	1	7.80	0.90	0.90	0.90	0.15	1.05		
		Joseph House Road (W0884)										
		LHS										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	36.4		Cum	1	6.40	0.90	0.90	0.90	0.15	0.86		
36.4	48.8		Cum	1	12.40	0.90	0.90	0.90	0.15	1.67		
		RHS										
		West to East										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27.6		Cum	1	12.60	0.90	0.90	0.90	0.15	1.70		
		1st Main Road (W1307)										
		LHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	22.7		Cum	1	7.70	0.90	0.90	0.90	0.15	1.04		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	17.6		Cum	1	2.60	0.90	0.90	0.90	0.15	0.35		
17.6	23.4	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
23.4	30		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	55.2		Cum	1	10.20	0.90	0.90	0.90	0.15	1.38		
55.2	60.3	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
60.3	75		Cum	1	14.70	0.90	0.90	0.90	0.15	1.98		
75	86.3		Cum	1	11.30	0.90	0.90	0.90	0.15	1.53		
86.3	91.5	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
91.5	105		Cum	1	13.50	0.90	0.90	0.90	0.15	1.82		
105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	131.5		Cum	1	11.50	0.90	0.90	0.90	0.15	1.55		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	19.2		Cum	1	4.20	0.90	0.90	0.90	0.15	0.57		
19.2	25.5		Cum	1	6.30	0.90	0.90	0.90	0.15	0.85		
25.5	30		Cum	1	4.50	0.90	0.90	0.90	0.15	0.61		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	75		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
75	90		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
90	105		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Scanned by CamScanner

105	120		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
120	125.9		Cum	1	5.90	0.90	0.90	0.90	0.15	0.80		
		Cross Road 1 (W0870)										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	26.1		Cum	1	11.10	0.90	0.90	0.90	0.15	1.50		
		Cross Road 2 (W0862)										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	33.8		Cum	1	3.80	0.90	0.90	0.90	0.15	0.51		
		Cross Road 3										
		East to West										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	37.5		Cum	1	7.50	0.90	0.90	0.90	0.15	1.01		
		Cross Road (W1297)										
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	106.7		Cum	1	1.70	1.10	1.10	1.10	0.15	0.28		
		RHS										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	107.2		Cum	1	2.20	1.10	1.10	1.10	0.15	0.36		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	29.8		Cum	1	14.80	0.90	0.90	0.90	0.15	2.00		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	61.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		

Scanned by CamScanner

60	66.9		Cum	1	6.90	0.90	0.90	0.90	0.15	0.93		
		Dead END										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	16.8		Cum	1	1.80	0.90	0.90	0.90	0.15	0.24		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	63.1		Cum	1	3.10	0.90	0.90	0.90	0.15	0.42		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	66.3		Cum	1	6.30	0.90	0.90	0.90	0.15	0.85		
		Dead END										
0	5.8		Cum	1	5.80	0.90	0.90	0.90	0.15	0.78		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	45.8		Cum	1	0.80	0.90	0.90	0.90	0.15	0.11		
45.8	59.2		Cum	1	13.40	0.90	0.90	0.90	0.15	1.81		
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
27	41.8		Cum	1	14.80	0.90	0.90	0.90	0.15	2.00		
41.8	55		Cum	1	13.20	0.90	0.90	0.90	0.15	1.78		
55	60.2		Cum	1	5.20	0.90	0.90	0.90	0.15	0.70		
		Dead END										
0	7.3		Cum	1	7.30	0.90	0.90	0.90	0.15	0.99		
		1st Main Road (W0612)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	36.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	53.3		Cum	1	8.30	1.10	1.10	1.10	0.15	1.37		
53.3	61.1	Road Break	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
61.1	70.7		Cum	1	9.60	1.10	1.10	1.10	0.15	1.58		
70.7	85		Cum	1	14.30	1.10	1.10	1.10	0.15	2.36		
85	100		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	125.8		Cum	1	10.80	1.10	1.10	1.10	0.15	1.78		
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	18.4		Cum	1	3.40	1.10	1.10	1.10	0.15	0.56		
18.4	30		Cum	1	11.60	1.10	1.10	1.10	0.15	1.91		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		

Scanned by CamScanner

45	49.1		Cum	1	4.10	1.10	1.10	1.10	0.15	0.68		
49.1	55		Cum	1	5.90	1.10	1.10	1.10	0.15	0.97		
55	64.8		Cum	1	9.80	1.10	1.10	1.10	0.15	1.62		
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	30		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
30	45		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	74.2		Cum	1	14.20	1.10	1.10	1.10	0.15	2.34		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	20.2		Cum	1	5.20	1.10	1.10	1.10	0.15	0.86		
20.2	33	No Work	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
33	45		Cum	1	12.00	1.10	1.10	1.10	0.15	1.98		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	68.4		Cum	1	8.40	1.10	1.10	1.10	0.15	1.39		
68.4	74.6		Cum	1	6.20	1.10	1.10	1.10	0.15	1.02		
74.6	85		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
85	100		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
100	115		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
115	128.5		Cum	1	13.50	1.10	1.10	1.10	0.15	2.23		
		LHS										
		South to North										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	17.6		Cum	1	2.60	1.10	1.10	1.10	0.15	0.43		
17.6	21.8		Cum	1	4.20	1.10	1.10	1.10	0.15	0.69		
21.8	26.5		Cum	1	4.70	1.10	1.10	1.10	0.15	0.78		
26.5	36.4		Cum	1	9.90	1.10	1.10	1.10	0.15	1.63		
36.4	46.8		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
46.8	57.2		Cum	1	10.40	1.10	1.10	1.10	0.15	1.72		
57.2	70		Cum	1	12.80	1.10	1.10	1.10	0.15	2.11		
70	78.4		Cum	1	8.40	1.10	1.10	1.10	0.15	1.39		
78.4	82.5	No Work	Cum	1	0.00	1.10	1.10	1.10	0.15	0.00		
82.5	91		Cum	1	8.50	1.10	1.10	1.10	0.15	1.40		
91	95.3		Cum	1	4.30	1.10	1.10	1.10	0.15	0.71		
95.3	104.2		Cum	1	8.90	1.10	1.10	1.10	0.15	1.47		
104.2	113.4		Cum	1	9.20	1.10	1.10	1.10	0.15	1.52		
113.4	128.2		Cum	1	14.80	1.10	1.10	1.10	0.15	2.44		
		Connecting Road 1 (W0608)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.8		Cum	1	8.80	0.90	0.90	0.90	0.15	1.19		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.4		Cum	1	10.40	0.90	0.90	0.90	0.15	1.40		
		Dead END (W0965)										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	17.7		Cum	1	2.70	0.90	0.90	0.90	0.15	0.36		
		Connecting Road 2										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	21.6		Cum	1	6.60	0.90	0.90	0.90	0.15	0.89		
		LHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	23.9		Cum	1	8.90	0.90	0.90	0.90	0.15	1.20		

Scanned by CamScanner

		1st Main, 1st A Cross (W0975)										
0	15		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
15	20.5		Cum	1	5.50	1.10	1.10	1.10	0.15	0.91		
20.5	30.3		Cum	1	9.80	1.10	1.10	1.10	0.15	1.62		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	60		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
60	74.4		Cum	1	14.40	0.90	0.90	0.90	0.15	1.94		
0	10.7		Cum	1	10.70	1.10	1.10	1.10	0.15	1.77		
10.7	25		Cum	1	14.30	1.10	1.10	1.10	0.15	2.36		
25	32.5		Cum	1	7.50	1.10	1.10	1.10	0.15	1.24		
32.5	45		Cum	1	12.50	1.10	1.10	1.10	0.15	2.06		
45	60		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
60	75		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
75	90		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
90	105		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
105	120		Cum	1	15.00	1.10	1.10	1.10	0.15	2.48		
120	121.2		Cum	1	1.20	1.10	1.10	1.10	0.15	0.20		
		LHS										
		South to North										
0	14.2		Cum	1	14.20	0.85	0.85	0.85	0.15	1.81		
14.2	25		Cum	1	10.80	0.85	0.85	0.85	0.15	1.38		
25	40		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
40	65		Cum	1	25.00	0.85	0.85	0.85	0.15	3.19		
65	76.6		Cum	1	11.60	0.85	0.85	0.85	0.15	1.48		
		2nd A Main Road (W0616)										
		RHS										
0	15		Cum	1	15.00	1.00	1.00	1.00	0.15	2.25		
15	26.5		Cum	1	11.50	1.00	1.00	1.00	0.15	1.73		
26.5	35.7		Cum	1	9.20	1.00	1.00	1.00	0.15	1.38		
35.7	46.4		Cum	1	10.70	1.00	1.00	1.00	0.15	1.61		
46.4	58		Cum	1	11.60	1.00	1.00	1.00	0.15	1.74		
58	70.6		Cum	1	12.60	1.00	1.00	1.00	0.15	1.89		
70.6	83.3		Cum	1	12.70	1.00	1.00	1.00	0.15	1.91		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	27.2		Cum	1	12.20	0.90	0.90	0.90	0.15	1.65		
27.2	36.9		Cum	1	9.70	0.90	0.90	0.90	0.15	1.31		
36.9	44.4		Cum	1	7.50	0.90	0.90	0.90	0.15	1.01		
44.4	50		Cum	1	5.60	0.90	0.90	0.90	0.15	0.76		
50	65		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
65	75		Cum	1	10.00	0.90	0.90	0.90	0.15	1.35		
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	25.1		Cum	1	10.10	0.90	0.90	0.90	0.15	1.36		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	45		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
45	60		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
60	75		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
75	85.6		Cum	1	10.60	0.85	0.85	0.85	0.15	1.35		
		Dead END (W0965)										

vssIFMS - ifms220

Scanned by CamScanner

0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	35.7		Cum	1	5.70	0.85	0.85	0.85	0.15	0.73		
		Dasarahalli Main Road (M0022)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	59.1		Cum	1	14.10	0.90	0.90	0.90	0.15	1.90		
		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
15	30		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
30	45		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
45	47.5		Cum	1	2.50	0.90	0.90	0.90	0.15	0.34		
47.5	53	Culvert	Cum	1	0.00	0.90	0.90	0.90	0.15	0.00		
53	65		Cum	1	12.00	0.90	0.90	0.90	0.15	1.62		
65	80		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
80	95		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
95	99.7		Cum	1	4.70	0.90	0.90	0.90	0.15	0.63		
99.7	112		Cum	1	12.30	0.90	0.90	0.90	0.15	1.66		
112	125		Cum	1	13.00	0.90	0.90	0.90	0.15	1.76		
125	140		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
140	155		Cum	1	15.00	0.90	0.90	0.90	0.15	2.03		
155	159.9		Cum	1	4.90	0.90	0.90	0.90	0.15	0.66		
		LHS										
0	15		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
15	30		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
30	40.5		Cum	1	10.50	0.85	0.85	0.85	0.15	1.34		
40.5	55		Cum	1	14.50	0.85	0.85	0.85	0.15	1.85		
55	65.5		Cum	1	10.50	0.85	0.85	0.85	0.15	1.34		
65.5	70.7	Culvert	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
70.7	85		Cum	1	14.30	0.85	0.85	0.85	0.15	1.82		
85	100		Cum	1	15.00	0.85	0.85	0.85	0.15	1.91		
100	111.8		Cum	1	11.80	0.85	0.85	0.85	0.15	1.50		
111.8	116.9	No Work	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
116.9	130		Cum	1	13.10	0.85	0.85	0.85	0.15	1.67		
130	144.5		Cum	1	14.50	0.85	0.85	0.85	0.15	1.85		
144.5	148.7	No Work	Cum	1	0.00	0.85	0.85	0.85	0.15	0.00		
148.7	164.3		Cum	1	15.60	0.85	0.85	0.85	0.15	1.99		
		2nd Cross (W0983) Dead End										
0	13.2		Cum	1	13.20	0.90	0.90	0.90	0.15	1.78		
		Dasarahalli Circle										
0	15		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
15	30		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
30	45		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
45	60		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
60	75		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
75	90		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
90	105		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
105	120		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
120	135		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
135	150		Cum	1	15.00	1.35	1.35	1.35	0.20	4.05		
150	159		Cum	1	9.00	1.35	1.35	1.35	0.20	2.43		
		Side Wall										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0	2.5		Cum	2	2.50	0.15	0.15	0.15	0.60	0.45		
2.5	15		Cum	2	12.50	0.15	0.15	0.15	0.60	2.25		
15	18.4		Cum	2	3.40	0.15	0.15	0.15	0.60	0.61		
18.4	24.4		Cum	2	6.00	0.15	0.15	0.15	0.60	1.08		
24.4	35		Cum	2	10.60	0.15	0.15	0.15	0.60	1.91		

Scanned by CamScanner

35	50		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
50	64.1		Cum	2	14.10	0.15	0.15	0.15	0.60	2.54		
64.1	75		Cum	2	10.90	0.15	0.15	0.15	0.60	1.96		
75	87.8		Cum	2	12.80	0.15	0.15	0.15	0.60	2.30		
87.8	91.8		Cum	2	4.00	0.15	0.15	0.15	0.60	0.72		
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	19.4		Cum	2	4.40	0.15	0.15	0.15	0.60	0.79		
19.4	28.2		Cum	2	8.80	0.15	0.15	0.15	0.60	1.58		
28.2	33.5		Cum	2	5.30	0.15	0.15	0.15	0.60	0.95		
33.5	42.5		Cum	2	9.00	0.15	0.15	0.15	0.60	1.62		
42.5	54.9		Cum	2	12.40	0.15	0.15	0.15	0.60	2.23		
54.9	65.7		Cum	2	10.80	0.15	0.15	0.15	0.60	1.94		
65.7	74.1		Cum	2	8.40	0.15	0.15	0.15	0.60	1.51		
74.1	85		Cum	2	10.90	0.15	0.15	0.15	0.60	1.96		
85	92.8		Cum	2	7.80	0.15	0.15	0.15	0.60	1.40		
		Joseph House Road (W0884)										
		LHS										
		East to West										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	36.4		Cum	2	6.40	0.15	0.15	0.15	0.60	1.15		
36.4	48.8		Cum	2	12.40	0.15	0.15	0.15	0.60	2.23		
		RHS										
		West to East										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	27.6		Cum	2	12.60	0.15	0.15	0.15	0.60	2.27		
		1st Main Road (W1307)										
		LHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	22.7		Cum	2	7.70	0.15	0.15	0.15	0.60	1.39		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	17.6		Cum	2	2.60	0.15	0.15	0.15	0.60	0.47		
17.6	23.4	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
23.4	30		Cum	2	6.60	0.15	0.15	0.15	0.60	1.19		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	55.2		Cum	2	10.20	0.15	0.15	0.15	0.60	1.84		
55.2	60.3	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
60.3	75		Cum	2	14.70	0.15	0.15	0.15	0.60	2.65		
75	86.3		Cum	2	11.30	0.15	0.15	0.15	0.60	2.03		
86.3	91.5	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
91.5	105		Cum	2	13.50	0.15	0.15	0.15	0.60	2.43		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	131.5		Cum	2	11.50	0.15	0.15	0.15	0.60	2.07		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	19.2		Cum	2	4.20	0.15	0.15	0.15	0.60	0.76		
19.2	25.5		Cum	2	6.30	0.15	0.15	0.15	0.60	1.13		
25.5	30		Cum	2	4.50	0.15	0.15	0.15	0.60	0.81		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	125.9		Cum	2	5.90	0.15	0.15	0.15	0.60	1.06		
		Cross Road 1 (W0870)										

Scanned by CamScanner

		East to West										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	26.1		Cum	2	11.10	0.15	0.15	0.15	0.60	2.00		
		Cross Road 2 (W0862)										
		East to West										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	33.8		Cum	2	3.80	0.15	0.15	0.15	0.60	0.68		
		Cross Road 3										
		East to West										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	37.5		Cum	2	7.50	0.15	0.15	0.15	0.60	1.35		
		Cross Road (W1297)										
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	106.7		Cum	2	1.70	0.15	0.15	0.15	0.60	0.31		
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	107.2		Cum	2	2.20	0.15	0.15	0.15	0.60	0.40		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	29.8		Cum	2	14.80	0.15	0.15	0.15	0.60	2.66		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	61.8		Cum	2	1.80	0.15	0.15	0.15	0.60	0.32		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	66.9		Cum	2	6.90	0.15	0.15	0.15	0.60	1.24		
		Dead END										

Scanned by CamScanner

0	15											
15	16.8		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
			Cum	2	1.80	0.15	0.15	0.15	0.60	0.32		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0	15											
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	63.1		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
			Cum	2	3.10	0.15	0.15	0.15	0.60	0.56		
		LHS										
		South to North										
0	15											
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	66.3		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
			Cum	2	6.30	0.15	0.15	0.15	0.60	1.13		
		Dead END										
0	5.8		Cum	2	5.80	0.15	0.15	0.15	0.60	1.04		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	45.8		Cum	2	0.80	0.15	0.15	0.15	0.60	0.14		
45.8	59.2		Cum	2	13.40	0.15	0.15	0.15	0.60	2.41		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	27		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		
27	41.8		Cum	2	14.80	0.15	0.15	0.15	0.60	2.66		
41.8	55		Cum	2	13.20	0.15	0.15	0.15	0.60	2.38		
55	60.2		Cum	2	5.20	0.15	0.15	0.15	0.60	0.94		
		Dead END										
0	7.3		Cum	2	7.30	0.15	0.15	0.15	0.60	1.31		
		1st Main Road (W0612)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	36.6		Cum	2	6.60	0.15	0.15	0.15	0.60	1.19		
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	53.3		Cum	2	8.30	0.15	0.15	0.15	0.60	1.49		
53.3	61.1	Road Break	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
61.1	70.7		Cum	2	9.60	0.15	0.15	0.15	0.60	1.73		
70.7	85		Cum	2	14.30	0.15	0.15	0.15	0.60	2.57		
85	100		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
100	115		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
115	125.8		Cum	2	10.80	0.15	0.15	0.15	0.60	1.94		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	18.4		Cum	2	3.40	0.15	0.15	0.15	0.60	0.61		
18.4	30		Cum	2	11.60	0.15	0.15	0.15	0.60	2.09		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	49.1		Cum	2	4.10	0.15	0.15	0.15	0.60	0.74		
49.1	55		Cum	2	5.90	0.15	0.15	0.15	0.60	1.06		

Scanned by CamScanner

55	64.8		Cum	2	9.80	0.15	0.15	0.15	0.60	1.76		
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	74.2		Cum	2	14.20	0.15	0.15	0.15	0.60	2.56		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	20.2		Cum	2	5.20	0.15	0.15	0.15	0.60	0.94		
20.2	33	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
33	45		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	68.4		Cum	2	8.40	0.15	0.15	0.15	0.60	1.51		
68.4	74.6		Cum	2	6.20	0.15	0.15	0.15	0.60	1.12		
74.6	85		Cum	2	10.40	0.15	0.15	0.15	0.60	1.87		
85	100		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
100	115		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
115	128.5		Cum	2	13.50	0.15	0.15	0.15	0.60	2.43		
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	17.6		Cum	2	2.60	0.15	0.15	0.15	0.60	0.47		
17.6	21.8		Cum	2	4.20	0.15	0.15	0.15	0.60	0.76		
21.8	26.5		Cum	2	4.70	0.15	0.15	0.15	0.60	0.85		
26.5	36.4		Cum	2	9.90	0.15	0.15	0.15	0.60	1.78		
36.4	46.8		Cum	2	10.40	0.15	0.15	0.15	0.60	1.87		
46.8	57.2		Cum	2	10.40	0.15	0.15	0.15	0.60	1.87		
57.2	70		Cum	2	12.80	0.15	0.15	0.15	0.60	2.30		
70	78.4		Cum	2	8.40	0.15	0.15	0.15	0.60	1.51		
78.4	82.5	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
82.5	91		Cum	2	8.50	0.15	0.15	0.15	0.60	1.53		
91	95.3		Cum	2	4.30	0.15	0.15	0.15	0.60	0.77		
95.3	104.2		Cum	2	8.90	0.15	0.15	0.15	0.60	1.60		
104.2	113.4		Cum	2	9.20	0.15	0.15	0.15	0.60	1.66		
113.4	128.2		Cum	2	14.80	0.15	0.15	0.15	0.60	2.66		
		Connecting Road 1 (W0608)										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	23.8		Cum	2	8.80	0.15	0.15	0.15	0.60	1.58		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	25.4		Cum	2	10.40	0.15	0.15	0.15	0.60	1.87		
		Dead END (W0965)										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	17.7		Cum	2	2.70	0.15	0.15	0.15	0.60	0.49		
		Connecting Road 2										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	21.6		Cum	2	6.60	0.15	0.15	0.15	0.60	1.19		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	23.9		Cum	2	8.90	0.15	0.15	0.15	0.60	1.60		
		1st Main, 1st A Cross (W0975)										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Work Order Reports Settings

Scanned by CamScanner

15	20.5		Cum	2	5.50	0.15	0.15	0.15	0.60	0.99		
20.5	30.3		Cum	2	9.80	0.15	0.15	0.15	0.60	1.76		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	74.4		Cum	2	14.40	0.15	0.15	0.15	0.60	2.59		
0	10.7		Cum	2	10.70	0.15	0.15	0.15	0.60	1.93		
10.7	25		Cum	2	14.30	0.15	0.15	0.15	0.60	2.57		
25	32.5		Cum	2	7.50	0.15	0.15	0.15	0.60	1.35		
32.5	45		Cum	2	12.50	0.15	0.15	0.15	0.60	2.25		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	90		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
90	105		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
105	120		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
120	121.2		Cum	2	1.20	0.15	0.15	0.15	0.60	0.22		
		LHS										
		South to North										
0	14.2		Cum	2	14.20	0.15	0.15	0.15	0.60	2.56		
14.2	25		Cum	2	10.80	0.15	0.15	0.15	0.60	1.94		
25	40		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
40	65		Cum	2	25.00	0.15	0.15	0.15	0.60	4.50		
65	76.6		Cum	2	11.60	0.15	0.15	0.15	0.60	2.09		
		2nd A Main Road (W0616)										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	26.5		Cum	2	11.50	0.15	0.15	0.15	0.60	2.07		
26.5	35.7		Cum	2	9.20	0.15	0.15	0.15	0.60	1.66		
35.7	46.4		Cum	2	10.70	0.15	0.15	0.15	0.60	1.93		
46.4	58		Cum	2	11.60	0.15	0.15	0.15	0.60	2.09		
58	70.6		Cum	2	12.60	0.15	0.15	0.15	0.60	2.27		
70.6	83.3		Cum	2	12.70	0.15	0.15	0.15	0.60	2.29		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	27.2		Cum	2	12.20	0.15	0.15	0.15	0.60	2.20		
27.2	36.9		Cum	2	9.70	0.15	0.15	0.15	0.60	1.75		
36.9	44.4		Cum	2	7.50	0.15	0.15	0.15	0.60	1.35		
44.4	50		Cum	2	5.60	0.15	0.15	0.15	0.60	1.01		
50	65		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
65	75		Cum	2	10.00	0.15	0.15	0.15	0.60	1.80		
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	25.1		Cum	2	10.10	0.15	0.15	0.15	0.60	1.82		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	60		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
60	75		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
75	85.6		Cum	2	10.60	0.15	0.15	0.15	0.60	1.91		
		Dead END (W0965)										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		

Work Order -> View Masters Reports Settings

Scanned by CamScanner

30	35.7		Cum	2	5.70	0.15	0.15	0.15	0.60	1.03		
		Dasarahalli Main Road (M0022)										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	59.1		Cum	2	14.10	0.15	0.15	0.15	0.60	2.54		
		20th R Cross Road (W0961)										
		RHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	45		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
45	47.5		Cum	2	2.50	0.15	0.15	0.15	0.60	0.45		
47.5	53	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
53	65		Cum	2	12.00	0.15	0.15	0.15	0.60	2.16		
65	80		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
80	95		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
95	99.7		Cum	2	4.70	0.15	0.15	0.15	0.60	0.85		
99.7	112		Cum	2	12.30	0.15	0.15	0.15	0.60	2.21		
112	125		Cum	2	13.00	0.15	0.15	0.15	0.60	2.34		
125	140		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
140	155		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
155	159.9		Cum	2	4.90	0.15	0.15	0.15	0.60	0.88		
		LHS										
0	15		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
15	30		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
30	40.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
40.5	55		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
55	65.5		Cum	2	10.50	0.15	0.15	0.15	0.60	1.89		
65.5	70.7	Culvert	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
70.7	85		Cum	2	14.30	0.15	0.15	0.15	0.60	2.57		
85	100		Cum	2	15.00	0.15	0.15	0.15	0.60	2.70		
100	111.8		Cum	2	11.80	0.15	0.15	0.15	0.60	2.12		
111.8	116.9	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
116.9	130		Cum	2	13.10	0.15	0.15	0.15	0.60	2.36		
130	144.5		Cum	2	14.50	0.15	0.15	0.15	0.60	2.61		
144.5	148.7	No Work	Cum	2	0.00	0.15	0.15	0.15	0.60	0.00		
148.7	164.3		Cum	2	15.60	0.15	0.15	0.15	0.60	2.81		
		2nd Cross (W0983) Dead End										
0	13.2		Cum	2	13.20	0.15	0.15	0.15	0.60	2.38		
		Dasarahalli Circle										
0	15		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
15	30		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
30	45		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
45	60		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
60	75		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
75	90		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
90	105		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
105	120		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
120	135		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
135	150		Cum	2	15.00	0.20	0.20	0.20	0.90	5.40		
150	159		Cum	2	9.00	0.20	0.20	0.20	0.90	3.24		
									Sub Total	**1048.57**		
		Culvert										
		Bottom Raft										
		Kuvempu Layout										
		2nd Main Road (W0616)	Cum	1	5.75	1.40	1.40	1.40	0.20	1.61		
		1st Main 1st Cross Road (W0973)	Cum	1	8.20	1.40	1.40	1.40	0.20	2.30		
		21st Cross Road (W0969)	Cum	1	6.20	1.40	1.40	1.40	0.20	1.74		
			Cum	1	10.40	1.40	1.40	1.40	0.20	2.91		
		Dead End Road (W0965)	Cum	1	8.10	1.40	1.40	1.40	0.20	2.27		
		21st Cross Road (W0969)	Cum	1	7.40	1.40	1.40	1.40	0.20	2.07		
		Dasarahalli Main Road (M0022)	Cum	1	7.00	1.40	1.40	1.40	0.20	1.96		
		1st Main Road (W0612)	Cum	1	7.70	1.40	1.40	1.40	0.20	2.16		

Masters Reports Settings
Work Order -> View

Scanned by CamScanner

			Cum	1	4.70	1.40	1.40	1.40	0.20	1.32		
			Cum	1	9.50	1.40	1.40	1.40	0.20	2.66		
		20th R Cross Road (W0961)	Cum	1	7.00	1.40	1.40	1.40	0.20	1.96		
		18th A Cross Road (W0618)	Cum	1	6.30	1.40	1.40	1.40	0.20	1.76		
		1st Main Road (W0612)	Cum	1	5.50	1.40	1.40	1.40	0.20	1.54		
		Mariyanna Palya										
		Joseph House Road (W0884)	Cum	1	5.60	1.70	1.70	1.70	0.20	1.90		
		Moto Works Oppo. (W1299)	Cum	1	6.10	1.70	1.70	1.70	0.20	2.07		
			Cum	1	5.80	1.70	1.70	1.70	0.20	1.97		
			Cum	1	5.10	1.70	1.70	1.70	0.20	1.73		
			Cum	1	5.20	1.70	1.70	1.70	0.20	1.77		
		Side Wall										
		Kuvempu Layout										
		2nd Main Road (W0616)	Cum	2	5.75	0.23	0.23	0.23	0.50	1.32		
			Cum	2	8.20	0.23	0.23	0.23	0.50	1.89		
			Cum	2	6.20	0.23	0.23	0.23	0.50	1.43		
			Cum	2	10.40	0.23	0.23	0.23	0.50	2.39		
		Dead End Road (W0965)	Cum	2	8.10	0.23	0.23	0.23	0.50	1.86		
		21st Cross Road (W0969)	Cum	2	7.40	0.23	0.23	0.23	0.50	1.70		
		Dasarahalli Main Road (M0022)	Cum	2	7.00	0.23	0.23	0.23	0.50	1.61		
		1st Main Road (W0612)	Cum	2	7.70	0.23	0.23	0.23	0.50	1.77		
			Cum	2	4.70	0.23	0.23	0.23	0.50	1.08		
			Cum	2	9.50	0.23	0.23	0.23	0.50	2.19		
		20th R Cross Road (W0961)	Cum	2	7.00	0.23	0.23	0.23	0.50	1.61		
		18th A Cross Road (W0618)	Cum	2	6.30	0.23	0.23	0.23	0.50	1.45		
		1st Main Road (W0612)	Cum	2	5.50	0.23	0.23	0.23	0.50	1.27		
		Mariyanna Palya										
		Joseph House Road (W0884)	Cum	2	5.60	0.23	0.23	0.23	0.50	1.29		
		Moto Works Oppo. (W1299)	Cum	2	6.10	0.23	0.23	0.23	0.50	1.40		
			Cum	2	5.80	0.23	0.23	0.23	0.50	1.33		
			Cum	2	5.10	0.23	0.23	0.23	0.50	1.17		
			Cum	2	5.20	0.23	0.23	0.23	0.50	1.20		
									Sub Total	**63.66**		
		Bed Concrete										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0	15		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
15	30		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
30	37.5	Culvert	Cum	0	0.00	0.75	0.75	0.75	0.10	0.00		
37.5	50		Cum	1	12.50	0.75	0.75	0.75	0.10	0.94		
50	65		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
65	80		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
80	94.8		Cum	1	14.80	0.75	0.75	0.75	0.10	1.11		
94.8	103.8	Culvert	Cum	0	0.00	0.75	0.75	0.00	0.10	0.00		
103.8	115		Cum	1	11.20	0.75	0.75	0.75	0.10	0.84		
115	128.1		Cum	1	13.10	0.75	0.75	0.75	0.10	0.98		
128.1	135	Culvert	Cum	0	0.00	0.75	0.75	0.75	0.10	0.00		
135	147.3		Cum	1	12.30	0.75	0.75	0.75	0.10	0.92		
147.3	152.5		Cum	1	5.20	0.75	0.75	0.75	0.10	0.39		
152.5	162		Cum	1	9.50	0.75	0.75	0.75	0.10	0.71		
162	177		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
177	191.5		Cum	1	14.50	0.75	0.75	0.75	0.10	1.09		
191.5	200		Cum	1	8.50	0.75	0.75	0.75	0.10	0.64		
200	215		Cum	1	15.00	0.75	0.75	0.75	0.10	1.13		
215	228		Cum	1	13.00	0.75	0.75	0.75	0.10	0.98		
228	240		Cum	1	12.00	0.75	0.75	0.75	0.10	0.90		
240	244.5		Cum	1	4.50	0.75	0.75	0.75	0.10	0.34		
									Sub Total	**16.58**		
								Total Executed Quantity		**1128.81**	**8000.00**	**9030511.00**
								Tender Quantity		**1147.54**		

Work Order - > View
Masters Reports Settings

Scanned by CamScanner

Item no.06		Providing T.M.T bars Fe 500 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. and as per the directions of the Engineer-in-charge of the work										
		For Drain	Tonne		1048.57			0.075		78.64		
		For Culvert	Tonne		63.66			0.095		6.05		
									Total Executed Qty	**84.69**		
									Tender Quantity	**84.27**		
									Quantity upto 125%	**84.69**	**91000.00**	**7706837.00**
Item no.07		Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. and as per the directions of the Engineer-in-charge of the work										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		LHS										
		South to North										
0	2.5		Sqm	1	2.50	0.75	0.75	0.75		1.88		
2.5	15		Sqm	1	12.50	0.75	0.75	0.75		9.38		
15	18.4		Sqm	1	3.40	0.75	0.75	0.75		2.55		
18.4	24.4	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
24.4	35		Sqm	1	10.60	0.75	0.75	0.75		7.95		
35	50		Sqm	1	15.00	0.75	0.75	0.75		11.25		
50	64.1		Sqm	1	14.10	0.75	0.75	0.75		10.58		
64.1	75		Sqm	1	10.90	0.75	0.75	0.75		8.18		
75	87.8	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
87.8	91.8		Sqm	1	4.00	0.75	0.75	0.75		3.00		
		RHS										
		North to South										
0	15	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
15	19.4	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
19.4	28.2		Sqm	1	8.80	0.75	0.75	0.75		6.60		
28.2	33.5	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
33.5	42.5		Sqm	1	9.00	0.75	0.75	0.75		6.75		
42.5	54.9	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
54.9	65.7		Sqm	1	10.80	0.75	0.75	0.75		8.10		
65.7	74.1	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
74.1	85		Sqm	1	10.90	0.75	0.75	0.75		8.18		
85	92.8		Sqm	1	7.80	0.75	0.75	0.75		5.85		
		Joseph House Road (W0884)										
		LHS										
		East to West										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	36.4		Sqm	1	6.40	0.75	0.75	0.75		4.80		
36.4	48.8	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
		RHS										
		West to East										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	27.6		Sqm	1	12.60	0.75	0.75	0.75		9.45		
		1st Main Road (W1307)										
		LHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	22.7		Sqm	1	7.70	0.75	0.75	0.75		5.78		
		Moto Works Oppo. (W1299)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	17.6		Sqm	1	2.60	0.75	0.75	0.75		1.95		
17.6	23.4	Culvert	Sqm	1	0.00	0.75	0.75	0.75		0.00		
23.4	30		Sqm	1	6.60	0.75	0.75	0.75		4.95		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	55.2		Sqm	1	10.20	0.75	0.75	0.75		7.65		
55.2	60.3	Culvert	Sqm	1	0.00	0.75	0.75	0.75		8.00		

Scanned by CamScanner

60.3	75		Sqm	1	14.70	0.75	0.75	0.75		11.03		
75	86.3	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
86.3	91.5	Culvert	Sqm	1	0.00	0.75	0.75	0.75		0.00		
91.5	105		Sqm	1	13.50	0.75	0.75	0.75		10.13		
105	120		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120	131.5		Sqm	1	11.50	0.75	0.75	0.75		8.63		
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	19.2		Sqm	1	4.20	0.75	0.75	0.75		3.15		
19.2	25.5	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
25.5	30		Sqm	1	4.50	0.75	0.75	0.75		3.38		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	90		Sqm	1	15.00	0.75	0.75	0.75		11.25		
90	105		Sqm	1	15.00	0.75	0.75	0.75		11.25		
105	120		Sqm	1	15.00	0.75	0.75	0.75		11.25		
120	125.9		Sqm	1	5.90	0.75	0.75	0.75		4.43		
		Cross Road 1 (W0870)										
		East to West										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	26.1		Sqm	1	11.10	0.75	0.75	0.75		8.33		
		Cross Road 2 (W0862)										
		East to West										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	33.8		Sqm	1	3.80	0.75	0.75	0.75		2.85		
		Cross Road 3										
		East to West										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	37.5		Sqm	1	7.50	0.75	0.75	0.75		5.63		
		Cross Road (W1297)										
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90	105		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105	106.7		Sqm	1	1.70	0.90	0.90	0.90		1.53		
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90	105		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105	107.2		Sqm	1	2.20	0.90	0.90	0.90		1.98		
		Kuvempu Layout										
		2nd Main, 2nd Cross (W0616)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
		LHS										
		South to North										

Work Order -> View Reports Settings

Scanned by CamScanner

0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	29.8		Sqm	1	14.80	0.75	0.75	0.75		11.10		
		1st Main, 3rd Cross (W0989)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	61.8		Sqm	1	1.80	0.75	0.75	0.75		1.35		
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	66.9		Sqm	1	6.90	0.75	0.75	0.75		5.18		
		Dead END										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	16.8		Sqm	1	1.80	0.75	0.75	0.75		1.35		
		1st Main, 2nd Cross (W0983)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	63.1		Sqm	1	3.10	0.75	0.75	0.75		2.33		
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	66.3		Sqm	1	6.30	0.75	0.75	0.75		4.73		
		Dead END										
0	5.8		Sqm	1	5.80	0.75	0.75	0.75		4.35		
		1st Main, 1st Cross (W0973)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	45.8		Sqm	1	0.80	0.75	0.75	0.75		0.60		
45.8	59.2		Sqm	1	13.40	0.75	0.75	0.75		10.05		
		LHS										
		South to North										
0	15	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
15	27	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
27	41.8		Sqm	1	14.80	0.75	0.75	0.75		11.10		
41.8	55	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
55	60.2	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
		Dead END										
0	7.3		Sqm	1	7.30	0.75	0.75	0.75		5.48		
		1st Main Road (W0612)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		

Work Order ->View Reports Settings

Scanned by CamScanner

30	36.6		Sqm	1	6.60	0.75	0.75	0.75		4.95		
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	53.3		Sqm	1	8.30	0.90	0.90	0.90		7.47		
53.3	61.1	Road Break	Sqm	1	0.00	0.90	0.90	0.90		0.00		
61.1	70.7		Sqm	1	0.00	0.90	0.90	0.90		0.00		
70.7	85		Sqm	1	14.30	0.90	0.90	0.90		12.87		
85	100		Sqm	1	15.00	0.90	0.90	0.90		13.50		
100	115		Sqm	1	15.00	0.90	0.90	0.90		13.50		
115	125.8		Sqm	1	10.80	0.90	0.90	0.90		9.72		
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	18.4		Sqm	1	3.40	0.90	0.90	0.90		3.06		
18.4	30	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
30	45	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
45	49.1	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
49.1	55		Sqm	1	5.90	0.90	0.90	0.90		5.31		
55	64.8		Sqm	1	9.80	0.90	0.90	0.90		8.82		
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	74.2		Sqm	1	14.20	0.90	0.90	0.90		12.78		
		21st Cross Road (W0969)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	20.2		Sqm	1	5.20	0.90	0.90	0.90		4.68		
20.2	33	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
33	45		Sqm	1	12.00	0.90	0.90	0.90		10.80		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	68.4		Sqm	1	8.40	0.90	0.90	0.90		7.56		
68.4	74.6		Sqm	1	6.20	0.90	0.90	0.90		5.58		
74.6	85		Sqm	1	10.40	0.90	0.90	0.90		9.36		
85	100		Sqm	1	15.00	0.90	0.90	0.90		13.50		
100	115		Sqm	1	15.00	0.90	0.90	0.90		13.50		
115	128.5		Sqm	1	13.50	0.90	0.90	0.90		12.15		
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	17.6		Sqm	1	2.60	0.90	0.90	0.90		2.34		
17.6	21.8	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
21.8	26.5		Sqm	1	4.70	0.90	0.90	0.90		4.23		
26.5	36.4	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
36.4	46.8		Sqm	1	10.40	0.90	0.90	0.90		9.36		
46.8	57.2		Sqm	1	10.40	0.90	0.90	0.90		9.36		
57.2	70		Sqm	1	12.80	0.90	0.90	0.90		11.52		
70	78.4		Sqm	1	8.40	0.90	0.90	0.90		7.56		
78.4	82.5	No Work	Sqm	1	0.00	0.90	0.90	0.90		0.00		
82.5	91	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
91	95.3		Sqm	1	4.30	0.90	0.90	0.90		3.87		
95.3	104.2	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
104.2	113.4		Sqm	1	9.20	0.90	0.90	0.90		8.28		
113.4	128.2	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		Connecting Road 1 (W0608)										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	23.8		Sqm	1	8.80	0.75	0.75	0.75		6.60		
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		

Scanned by CamScanner

15	25.4		Sqm	1	10.40	0.75	0.75	0.75		7.80		
		Dead END (W0965)										
0	15											
15	17.7		Sqm	1	15.00	0.75	0.75	0.75		11.25		
			Sqm	1	2.70	0.75	0.75	0.75		2.03		
		Connecting Road 2										
		RHS										
0	15											
15	21.6		Sqm	1	15.00	0.75	0.75	0.75		11.25		
			Sqm	1	6.60	0.75	0.75	0.75		4.95		
			Sqm									
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	23.9		Sqm	1	8.90	0.75	0.75	0.75		6.68		
			Sqm									
		1st Main, 1st A Cross (W0975)										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	20.5		Sqm	1	5.50	0.90	0.90	0.90		4.95		
20.5	30.3		Sqm	1	9.80	0.90	0.90	0.90		8.82		
		2nd Main Road (W0616)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	74.4		Sqm	1	14.40	0.75	0.75	0.75		10.80		
0	10.7		Sqm	1	10.70	0.90	0.90	0.90		9.63		
10.7	25	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
25	32.5	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
32.5	45		Sqm	1	12.50	0.90	0.90	0.90		11.25		
45	60		Sqm	1	15.00	0.90	0.90	0.90		13.50		
60	75		Sqm	1	15.00	0.90	0.90	0.90		13.50		
75	90		Sqm	1	15.00	0.90	0.90	0.90		13.50		
90	105		Sqm	1	15.00	0.90	0.90	0.90		13.50		
105	120		Sqm	1	15.00	0.90	0.90	0.90		13.50		
120	121.2		Sqm	1	1.20	0.90	0.90	0.90		1.08		
		LHS										
		South to North										
0	14.2		Sqm	1	14.20	0.75	0.75	0.75		10.65		
14.2	25	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
25	40	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
40	65	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
65	76.6	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
		2nd A Main Road (W0616)										
		RHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	26.5		Sqm	1	11.50	0.90	0.90	0.90		10.35		
26.5	35.7	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
35.7	46.4	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
46.4	58		Sqm	1	11.60	0.90	0.90	0.90		10.44		
58	70.6		Sqm	1	12.60	0.90	0.90	0.90		11.34		
70.6	83.3	BS Slab	Sqm	1	0.00	0.90	0.90	0.90		0.00		
		18th A Cross Road (W0618)										
		LHS										
		South to North										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	27.2		Sqm	1	12.20	0.75	0.75	0.75		9.15		
27.2	36.9	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
36.9	44.4		Sqm	1	7.50	0.75	0.75	0.75		5.63		
44.4	50	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
50	65	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
65	75	BS Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		

Scanned by CamScanner

0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	25.1		Sqm	1	10.10	0.90	0.90	0.90		9.09		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		RHS										
		North to South										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	60		Sqm	1	15.00	0.75	0.75	0.75		11.25		
60	75		Sqm	1	15.00	0.75	0.75	0.75		11.25		
75	85.6		Sqm	1	10.60	0.75	0.75	0.75		7.95		
		Dead END (W0965)										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	35.7		Sqm	1	5.70	0.75	0.75	0.75		4.28		
		Dasarahalli Main Road (M0022)										
		RHS										
0	15		Sqm	1	15.00	0.90	0.90	0.90		13.50		
15	30		Sqm	1	15.00	0.90	0.90	0.90		13.50		
30	45		Sqm	1	15.00	0.90	0.90	0.90		13.50		
45	59.1		Sqm	1	14.10	0.90	0.90	0.90		12.69		
		20th R Cross Road (W0961)										
		RHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	45		Sqm	1	15.00	0.75	0.75	0.75		11.25		
45	47.5		Sqm	1	2.50	0.75	0.75	0.75		1.88		
47.5	53	Culvert	Sqm	1	0.00	0.75	0.75	0.75		0.00		
53	65		Sqm	1	12.00	0.75	0.75	0.75		9.00		
65	80		Sqm	1	15.00	0.75	0.75	0.75		11.25		
80	95		Sqm	1	15.00	0.75	0.75	0.75		11.25		
95	99.7		Sqm	1	4.70	0.75	0.75	0.75		3.53		
99.7	112	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
112	125		Sqm	1	13.00	0.75	0.75	0.75		9.75		
125	140		Sqm	1	15.00	0.75	0.75	0.75		11.25		
140	155		Sqm	1	15.00	0.75	0.75	0.75		11.25		
155	159.9		Sqm	1	4.90	0.75	0.75	0.75		3.68		
		LHS										
0	15		Sqm	1	15.00	0.75	0.75	0.75		11.25		
15	30		Sqm	1	15.00	0.75	0.75	0.75		11.25		
30	40.5		Sqm	1	10.50	0.75	0.75	0.75		7.88		
40.5	55	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
55	65.5	B S Slab	Sqm	1	0.00	0.75	0.75	0.75		0.00		
65.5	70.7	Culvert	Sqm	1	0.00	0.75	0.75	0.75		0.00		
70.7	85		Sqm	1	14.30	0.75	0.75	0.75		10.73		
85	100		Sqm	1	15.00	0.75	0.75	0.75		11.25		
100	111.8		Sqm	1	11.80	0.75	0.75	0.75		8.85		
111.8	116.9	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
116.9	130		Sqm	1	13.10	0.75	0.75	0.75		9.83		
130	144.5		Sqm	1	14.50	0.75	0.75	0.75		10.88		
144.5	148.7	No Work	Sqm	1	0.00	0.75	0.75	0.75		0.00		
148.7	164.3		Sqm	1	15.60	0.75	0.75	0.75		11.70		
		2nd Cross (W0983) Dead End										
0	13.2		Sqm	1	13.20	0.75	0.75	0.75		9.90		
		Dasarahalli Circle										
0	15		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15	30		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30	45		Sqm	1	15.00	1.20	1.20	1.20		18.00		
45	60		Sqm	1	15.00	1.20	1.20	1.20		18.00		
60	75		Sqm	1	15.00	1.20	1.20	1.20		18.00		

Scanned by CamScanner

75	90		Sqm	1	15.00	1.20	1.20	1.20		18.00		
90	105		Sqm	1	15.00	1.20	1.20	1.20		18.00		
105	120		Sqm	1	15.00	1.20	1.20	1.20		18.00		
120	135		Sqm	1	15.00	1.20	1.20	1.20		18.00		
135	150		Sqm	1	15.00	1.20	1.20	1.20		18.00		
150	159		Sqm	1	9.00	1.20	1.20	1.20		10.80		
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0	15		Sqm	1	15.00	1.20	1.20	1.20		18.00		
15	30		Sqm	1	15.00	1.20	1.20	1.20		18.00		
30	37.5	Culvert	Sqm	0	0.00	1.20	1.20	1.20		0.00		
37.5	50		Sqm	1	12.50	1.20	1.20	1.20		15.00		
50	65		Sqm	1	15.00	1.20	1.20	1.20		18.00		
65	80		Sqm	1	15.00	1.20	1.20	1.20		18.00		
80	94.8		Sqm	1	14.80	1.20	1.20	1.20		17.76		
94.8	103.8	Culvert	Sqm	0	0.00	1.20	1.20	1.20		0.00		
103.8	115		Sqm	1	11.20	1.20	1.20	1.20		13.44		
115	128.1		Sqm	1	13.10	1.20	1.20	1.20		15.72		
128.1	135	Culvert	Sqm	0	0.00	1.20	1.20	1.20		0.00		
135	147.3	BS Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
147.3	152.5		Sqm	1	5.20	1.20	1.20	1.20		6.24		
152.5	162		Sqm	1	9.50	1.20	1.20	1.20		11.40		
162	177		Sqm	1	15.00	1.20	1.20	1.20		18.00		
177	191.5		Sqm	1	14.50	1.20	1.20	1.20		17.40		
191.5	200	Desilt Only	Sqm	1	0.00	1.20	1.20	1.20		0.00		
200	215	Desilt Only	Sqm	1	0.00	1.20	1.20	1.20		0.00		
215	228	Desilt Only	Sqm	1	0.00	1.20	1.20	1.20		0.00		
228	240	BS Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
240	244.5	BS Slab	Sqm	1	0.00	1.20	1.20	1.20		0.00		
									Total Executed Quantity	**2395.29**	**1950.00**	**4670816.00**
									Tender Quantity	**2662.35**		
Item no.08		Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift, transportation etc ,complete. and as per the directions of the Engineer-in-charge of the work										
		Kuvempu Layout										
		2nd Main Road (W0616)	Sqm	1	5.75	1.20	1.20	1.20		6.90		
		1st Main 1st Cross Road (W0973)	Sqm	1	8.20	1.20	1.20	1.20		9.84		
		21st Cross Road (W0969)	Sqm	1	6.20	1.20	1.20	1.20		7.44		
			Sqm	1	10.40	1.20	1.20	1.20		12.48		
		Dead End Road (W0965)	Sqm	1	8.10	1.20	1.20	1.20		9.72		
		21st Cross Road (W0969)	Sqm	1	7.40	1.20	1.20	1.20		8.88		
		Dasarahalli Main Road (M0022)	Sqm	1	7.00	1.20	1.20	1.20		8.40		
		1st Main Road (W0612)	Sqm	1	7.70	1.20	1.20	1.20		9.24		
			Sqm	1	4.70	1.20	1.20	1.20		5.64		
			Sqm	1	9.50	1.20	1.20	1.20		11.40		
		20th R Cross Road (W0961)	Sqm	1	7.00	1.20	1.20	1.20		8.40		
		18th A Cross Road (W0618)	Sqm	1	6.30	1.20	1.20	1.20		7.56		
		1st Main Road (W0612)	Sqm	1	5.50	1.20	1.20	1.20		6.60		
		Mariyanna Palya										
		Joseph House Road (W0884)	Sqm	1	5.60	1.50	1.50	1.50		8.40		
		Moto Works Oppo. (W1299)	Sqm	1	6.10	1.50	1.50	1.50		9.15		
			Sqm	1	5.80	1.50	1.50	1.50		8.70		
			Sqm	1	5.10	1.50	1.50	1.50		7.65		
			Sqm	1	5.20	1.50	1.50	1.50		7.80		
									Total Executed Quantity	**154.20**	**6000.00**	**925200.00**
									Tender Quantity	**202.92**		
Item no.09		Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications and directions of the Engineer in charge.										
		Mariyanna Palya										
		St. Anthony Church Road (I0794)										
0	15		Sqm	2	15.00				0.20	6.00		
15	30		Sqm	2	15.00				0.20	6.00		
30	37.5	Culvert	Sqm	0	0.00				0.20	0.00		

Scanned by CamScanner

37.5	50		Sqm	2	12.50				0.20	5.00		
50	65		Sqm	2	15.00				0.20	6.00		
65	80		Sqm	2	15.00				0.20	6.00		
80	94.8		Sqm	2	14.80				0.20	5.92		
94.8	103.8	Culvert	Sqm	0	0.00				0.20	0.00		
103.8	115		Sqm	2	11.20				0.20	4.48		
115	128.1		Sqm	2	13.10				0.20	5.24		
128.1	135	Culvert	Sqm	0	0.00				0.20	0.00		
135	147.3	0.00	Sqm	2	12.30				0.20	4.92		
147.3	152.5		Sqm	2	5.20				0.20	2.08		
152.5	162		Sqm	2	9.50				0.20	3.80		
162	177		Sqm	2	15.00				0.20	6.00		
177	191.5		Sqm	2	14.50				0.20	5.80		
191.5	200	0.00	Sqm	2	0.00				0.20	0.00		
200	215	0.00	Sqm	2	0.00				0.20	0.00		
215	228	0.00	Sqm	2	0.00				0.20	0.00		
228	240	0.00	Sqm	2	0.00				0.20	0.00		
240	244.5	0.00	Sqm	2	0.00				0.20	0.00		
									Total Executed Quantity	**67.24**	**1100.00**	**73964.00**
									Tender Quantity	**100.80**		
Item no.10		Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. and as per the directions of the Engineer-in-charge of the work										
		Mariyanna Palya										
		1st Main Road (W1307)										
		RHS										
0	15		m	1	15.00					15.00		
15	22.7		m	1	7.70					7.70		
		Moto Works Oppo. (W1299)										
		LHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	60		m	1	15.00					15.00		
60	75		m	1	15.00					15.00		
75	90		m	1	15.00					15.00		
90	105		m	1	15.00					15.00		
105	120		m	1	15.00					15.00		
120	125.9		m	1	5.90					5.90		
		RHS										
0	15		m	1	15.00					15.00		
15	17.6		m	1	2.60					2.60		
17.6	23.4	Culvert	m	1	0.00					0.00		
23.4	35		m	1	11.60					11.60		
35	50		m	1	15.00					15.00		
50	55.2		m	1	5.20					5.20		
55.2	60.3	Culvert	m	1	0.00					0.00		
60.3	74		m	1	13.70					13.70		
74	77.3	Ramp	m	1	0.00					0.00		
77.3	86.3		m	1	9.00					9.00		
86.3	91.5	Culvert	m	1	0.00					0.00		
91.5	105		m	1	13.50					13.50		
105	117.2		m	1	12.20					12.20		
117.2	120.4	Ramp	m	1	0.00					0.00		
120.4	131.5		m	1	11.10					11.10		
		Kuvempu Layout										
		(W0616)										
		LHS										
0	15		m	1	15.00					15.00		
15	29.8		m	1	14.80					14.80		
		RHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
		1st main 2nd Cross Road (W0983)										

Scanned by CamScanner

		LHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	63.1		m	1	18.10					18.10		
		RHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	60		m	1	15.00					15.00		
60	66.3		m	1	6.30					6.30		
		1st main 1st Cross Road (W0973)										
		RHS										
0	15		m	1	15.00					15.00		
15	24.6		m	1	9.60					9.60		
24.6	27.8	Ramp	m	1	0.00					0.00		
27.8	45		m	1	17.20					17.20		
45	58.2		m	1	13.20					13.20		
		LHS										
0	15	Ramp	m	1	0.00					0.00		
15	25.6	Ramp	m	1	0.00					0.00		
25.6	41.4		m	1	15.80					15.80		
41.4	60.2		m	1	18.80					18.80		
		1st main Road (W0612)										
		RHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	40.2		m	1	10.20					10.20		
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	54.3		m	1	9.30					9.30		
54.3	62.1	Road Break	m	0	0.00					0.00		
62.1	77.1		m	1	15.00					15.00		
77.1	92.1		m	1	15.00					15.00		
92.1	107.1		m	1	15.00					15.00		
107.1	122.1		m	1	15.00					15.00		
122.1	126.8		m	1	4.70					4.70		
		1st main Road (W0612)										
		LHS										
0	15	No work	m	1	0.00					0.00		
15	30	No work	m	1	0.00					0.00		
30	45	No work	m	1	0.00					0.00		
45	50	No work	m	1	0.00					0.00		
50	65		m	1	15.00					15.00		
65	80		m	1	15.00					15.00		
80	95		m	1	15.00					15.00		
95	110		m	1	15.00					15.00		
110	125		m	1	15.00					15.00		
125	128.4		m	1	3.40					3.40		
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45.4		m	1	15.40					15.40		
45.4	50.3	No Work	m	1	0.00					0.00		
50.3	65.3		m	1	15.00					15.00		
65.3	74.8		m	1	9.50					9.50		
		1st Main 3rd Cross Road (W0989)										
		LHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		

Scanned by CamScanner

45	61.8		m	1	16.80					16.80		
		2nd Main Road (W0616)										
		LHS										
0	15		m	1	15.00					15.00		
15	21.2		m	1	6.20					6.20		
		RHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	60		m	1	15.00					15.00		
60	74		m	1	14.00					14.00		
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	60		m	1	15.00					15.00		
60	75		m	1	15.00					15.00		
75	90		m	1	15.00					15.00		
90	105		m	1	15.00					15.00		
105	120.8		m	1	15.80					15.80		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		LHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	45		m	1	15.00					15.00		
45	60		m	1	15.00					15.00		
60	75		m	1	15.00					15.00		
75	85.6		m	1	10.60					10.60		
		21th Cross Road (W0969)										
		RHS										
0	15		m	1	15.00					15.00		
15	20.2		m	1	5.20					5.20		
20.2	33	No Work	m	0	0.00					0.00		
33	48		m	1	15.00					15.00		
48	63		m	1	15.00					15.00		
63	68.4		m	1	5.40					5.40		
68.4	74.6	No Work	m	0	0.00					0.00		
74.6	89.6		m	1	15.00					15.00		
89.6	104.6		m	1	15.00					15.00		
104.6	119.6		m	1	15.00					15.00		
119.6	129.5		m	1	9.90					9.90		
		LHS										
0	15		m	1	15.00					15.00		
15	30		m	1	15.00					15.00		
30	46.8		m	1	16.80					16.80		
46.8	57.2	old Culvert	m	0	0.00					0.00		
57.2	72.2		m	1	15.00					15.00		
72.2	87.2		m	1	15.00					15.00		
87.2	102.2		m	1	15.00					15.00		
102.2	117.2		m	1	15.00					15.00		
117.2	128.2		m	1	11.00					11.00		
		Connecting Road-1 (W0608)										
		LHS										
0	15		m	1	15.00					15.00		
15	25.4		m	1	10.40					10.40		
		RHS										
0	15		m	1	15.00					15.00		
15	23.8		m	1	8.80					8.80		
		Dead End Road (W0965)										
		LHS										

Scanned by CamScanner

0	15		m	1	15.00					15.00		
15	17		m	1	2.00					2.00		
		RHS										
0	15		m	1	15.00					15.00		
15	23.1		m	1	8.10					8.10		
23.1	35.7	Ramp	m	1	0.00					0.00		
		Connecting Road -2										
		LHS										
0	15		m	1	15.00					15.00		
15	20.5		m	1	5.50					5.50		
		RHS										
0	15		m	1	15.00					15.00		
15	23.9		m	1	8.90					8.90		
		1st A Cross Road (W0975)										
		LHS										
0	15		m	1	15.00					15.00		
15	30.3		m	1	15.30					15.30		
		2nd Main Road (W0616)										
0	15		m	1	15.00					15.00		
15	24.8		m	1	9.80					9.80		
		18th A Cross Road (W0618)										
		LHS										
0	15		m	1	15.00					15.00		
15	25		m	1	10.00					10.00		
25	34.8	Ramp	m	1	0.00					0.00		
34.8	49.8		m	1	15.00					15.00		
49.8	54		m	1	4.20					4.20		
54	69	Ramp	m	1	0.00					0.00		
69	72.3	Ramp	m	1	0.00					0.00		
		2nd A Cross Road (W0616)										
		LHS										
0	7.4	Ramp	m	1	0.00					0.00		
7.4	25.1		m	1	17.70					17.70		
25.1	40.5	Ramp	m	1	0.00					0.00		
40.5	55.5		m	1	15.00					15.00		
55.5	69.9		m	1	14.40					14.40		
69.9	83.1	No Work	m	1	0.00					0.00		
		2nd Main Road (W0616)										
		LHS										
0	8		m	1	8.00					8.00		
8	9.8	No Work	m	1	1.80					1.80		
9.8	24.8		m	1	15.00					15.00		
24.8	36.1		m	1	11.30					11.30		
		Mariyannana Palya										
		1st Main Road (W0973)										
		LHS										
0	15		m	1	15.00					15.00		
15	29.8		m	1	14.80					14.80		
29.8	37.4	Culvert	m	1	7.60					7.60		
37.4	52.4		m	1	15.00					15.00		
52.4	67.4		m	1	15.00					15.00		
67.4	82.4		m	1	15.00					15.00		
82.4	94.8		m	1	12.40					12.40		
94.8	103.8	Culvert	m	1	0.00					0.00		
103.8	118.8		m	1	15.00					15.00		
118.8	128		m	1	9.20					9.20		
128	135	Culvert	m	1	0.00					0.00		
135	147.4		m	1	12.40					12.40		
147.4	152.6	No Work	m	1	0.00					0.00		
152.6	161.5		m	1	8.90					8.90		

Scanned by CamScanner

161.5	177	No Work	m	1	0.00					0.00			
177	191.7		m	1	14.70					14.70			
		20th R Cross Road (W0961)											
		RHS											
0	15		m	1	15.00					15.00			
15	30		m	1	15.00					15.00			
30	45		m	1	15.00					15.00			
45	47.5		m	1	2.50					2.50			
47.5	53	Culvert	m	1	0.00					0.00			
53	65		m	1	12.00					12.00			
65	80		m	1	15.00					15.00			
80	95		m	1	15.00					15.00			
95	99.7		m	1	4.70					4.70			
99.7	112	B S Slab	m	1	12.30					12.30			
112	125		m	1	13.00					13.00			
125	140		m	1	15.00					15.00			
140	155		m	1	15.00					15.00			
155	159.9		m	1	4.90					4.90			
		LHS											
0	15		m	1	15.00					15.00			
15	30		m	1	15.00					15.00			
30	40.5		m	1	10.50					10.50			
40.5	55	B S Slab	m	1	14.50					14.50			
55	65.5	B S Slab	m	1	10.50					10.50			
65.5	70.7	Culvert	m	1	0.00					0.00			
70.7	85		m	1	14.30					14.30			
85	100		m	1	15.00					15.00			
100	111.8		m	1	11.80					11.80			
111.8	116.9	No Work	m	1	0.00					0.00			
116.9	130		m	1	13.10					13.10			
130	144.5		m	1	14.50					14.50			
144.5	148.7	No Work	m	1	0.00					0.00			
148.7	164.3		m	1	15.60					15.60			
			m						**Total Length**	**2210.90**			
			Nos						**Length/0.45**	**4914.00**			
									Total Executed Quantity	**4914.00**	**440.00**	**2162160.00**	
									Tender Quantity	**5656.00**			

Item no.11		Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour Complete as per specifications and directions of the Engineer in charge.											
		Mariyanna Palya											
		1st Main Road (W1307)											
		RHS											
0	15		Sqm	1	15.00				0.40	6.00			
15	22.7		Sqm	1	7.70				0.40	3.08			
		Moto Works Oppo. (W1299)											
		LHS											
0	15		Sqm	1	15.00				0.40	6.00			
15	30		Sqm	1	15.00				0.40	6.00			
30	45		Sqm	1	15.00				0.40	6.00			
45	60		Sqm	1	15.00				0.40	6.00			
60	75		Sqm	1	15.00				0.40	6.00			
75	90		Sqm	1	15.00				0.40	6.00			
90	105		Sqm	1	15.00				0.40	6.00			
105	120		Sqm	1	15.00				0.40	6.00			
120	125.9		Sqm	1	5.90				0.40	2.36			
		RHS											
0	15		Sqm	1	15.00				0.40	6.00			
15	17.6		Sqm	1	2.60				0.40	1.04			
17.6	23.4	Culvert	Sqm	1	0.00				0.40	0.00			
23.4	35		Sqm	1	11.60				0.40	4.64			
35	50		Sqm	1	15.00				0.40	6.00			
50	55.2		Sqm	1	5.20				0.40	2.08			
55.2	60.3	Culvert	Sqm	1	0.00				0.40	0.00			
60.3	74		Sqm	1	13.70				0.40	5.48			
74	77.3	Ramp	Sqm	1	0.00				0.40	0.00			
77.3	86.3		Sqm	1	9.00				0.40	3.60			
86.3	91.5	Culvert	Sqm	1	0.00				0.40	0.00			

Scanned by CamScanner

91.5	105											
105	117.2		Sqm	1	13.50				0.40	5.40		
117.2	120.4	Ramp	Sqm	1	12.20				0.40	4.88		
120.4	131.5		Sqm	1	0.00				0.40	0.00		
			Sqm	1	11.10				0.40	4.44		
		Kuvempu Layout										
		2nd Main road 2nd Cross Road (W0616)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	29.8		Sqm	1	14.80				0.40	5.92		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
		1st main 2nd Cross Road (W0983)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	63.1		Sqm	1	18.10				0.40	7.24		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	60		Sqm	1	15.00				0.40	6.00		
60	66.3		Sqm	1	6.30				0.40	2.52		
		1st main 1st Cross Road (W0973)										
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	24.6		Sqm	1	9.60				0.40	3.84		
24.6	27.8	Ramp	Sqm	1	0.00				0.40	0.00		
27.8	45		Sqm	1	17.20				0.40	6.88		
45	58.2		Sqm	1	13.20				0.40	5.28		
		LHS										
0	15	Ramp	Sqm	1	0.00				0.40	0.00		
15	25.6	Ramp	Sqm	1	0.00				0.40	0.00		
25.6	41.4		Sqm	1	15.80				0.40	6.32		
41.4	60.2		Sqm	1	18.80				0.40	7.52		
		1st main Road (W0612)										
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	40.2		Sqm	1	10.20				0.40	4.08		
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	54.3		Sqm	1	9.30				0.40	3.72		
54.3	62.1	Road Break										
62.1	77.1		Sqm	1	15.00				0.40	6.00		
77.1	92.1		Sqm	1	15.00				0.40	6.00		
92.1	107.1		Sqm	1	15.00				0.40	6.00		
107.1	122.1		Sqm	1	15.00				0.40	6.00		
122.1	126.8		Sqm	1	4.70				0.40	1.88		
		1st main Road (W0612)										
		LHS										
0	15	No work	Sqm	1	0.00				0.40	0.00		
15	30	No work	Sqm	1	0.00				0.40	0.00		
30	45	No work	Sqm	1	0.00				0.40	0.00		
45	50	No work	Sqm	1	0.00				0.40	0.00		
50	65		Sqm	1	15.00				0.40	6.00		
65	80		Sqm	1	15.00				0.40	6.00		
80	95		Sqm	1	15.00				0.40	6.00		
95	110		Sqm	1	15.00				0.40	6.00		

Scanned by CamScanner

110	125		Sqm	1	15.00				0.40	6.00		
125	128.4		Sqm	1	3.40				0.40	1.36		
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45.4		Sqm	1	15.40				0.40	6.16		
45.4	50.3	No Work	Sqm	1	0.00				0.40	0.00		
50.3	65.3		Sqm	1	15.00				0.40	6.00		
65.3	74.8		Sqm	1	9.50				0.40	3.80		
		1st Main 3rd Cross Road (W0989)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	61.8		Sqm	1	16.80				0.40	6.72		
		2nd Main Road (W0616)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	21.2		Sqm	1	6.20				0.40	2.48		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	60		Sqm	1	15.00				0.40	6.00		
60	74		Sqm	1	14.00				0.40	5.60		
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	60		Sqm	1	15.00				0.40	6.00		
60	75		Sqm	1	15.00				0.40	6.00		
75	90		Sqm	1	15.00				0.40	6.00		
90	105		Sqm	1	15.00				0.40	6.00		
105	120.8		Sqm	1	15.80				0.40	6.32		
		Munikempanna Layout										
		1st Cross Road (W0973)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	60		Sqm	1	15.00				0.40	6.00		
60	75		Sqm	1	15.00				0.40	6.00		
75	85.6		Sqm	1	10.60				0.40	4.24		
		21th Cross Road (W0969)										
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	20.2		Sqm	1	5.20				0.40	2.08		
20.2	33	No Work										
33	48		Sqm	1	15.00				0.40	6.00		
48	63		Sqm	1	15.00				0.40	6.00		
63	68.4		Sqm	1	5.40				0.40	2.16		
68.4	74.6	No Work										
74.6	89.6		Sqm	1	15.00				0.40	6.00		
89.6	104.6		Sqm	1	15.00				0.40	6.00		
104.6	119.6		Sqm	1	15.00				0.40	6.00		
119.6	129.5		Sqm	1	9.90				0.40	3.96		
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	46.8		Sqm	1	16.80				0.40	6.72		
46.8	57.2	old Culvert										
57.2	72.2		Sqm	1	15.00				0.40	6.00		
72.2	87.2		Sqm	1	15.00				0.40	6.00		
87.2	102.2		Sqm	1	15.00				0.40	6.00		
102.2	117.2		Sqm	1	15.00				0.40	6.00		
117.2	128.2		Sqm	1	11.00				0.40	4.40		

Scanned by CamScanner

		Connecting Road-1 (W0608)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	25.4		Sqm	1	10.40				0.40	4.16		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	23.8		Sqm	1	8.80				0.40	3.52		
		Dead End Road (W0965)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	17		Sqm	1	2.00				0.40	0.80		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	23.1		Sqm	1	8.10				0.40	3.24		
23.1	35.7	Ramp	Sqm	1	0.00				0.40	0.00		
		Connecting Road -2										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	20.5		Sqm	1	5.50				0.40	2.20		
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	23.9		Sqm	1	8.90				0.40	3.56		
		1st A Cross Road (W0975)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30.3		Sqm	1	15.30				0.40	6.12		
		2nd Main Road (W0616)										
0	15		Sqm	1	15.00				0.40	6.00		
15	24.8		Sqm	1	9.80				0.40	3.92		
		18th A Cross Road (W0618)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	25		Sqm	1	10.00				0.40	4.00		
25	34.8	Ramp	Sqm	1	0.00				0.40	0.00		
34.8	49.8		Sqm	1	15.00				0.40	6.00		
49.8	54		Sqm	1	4.20				0.40	1.68		
54	69	Ramp	Sqm	1	0.00				0.40	0.00		
69	72.3	Ramp	Sqm	1	0.00				0.40	0.00		
		2nd A Cross Road (W0616)										
		LHS										
0	7.4	Ramp	Sqm	1	0.00				0.40	0.00		
7.4	25.1		Sqm	1	17.70				0.40	7.08		
25.1	40.5	Ramp	Sqm	1	0.00				0.40	0.00		
40.5	55.5		Sqm	1	15.00				0.40	6.00		
55.5	69.9		Sqm	1	14.40				0.40	5.76		
69.9	83.1	No Work	Sqm	1	0.00				0.40	0.00		
		2nd Main Road (W0616)										
		LHS										
0	8		Sqm	1	8.00				0.40	3.20		
8	9.8	No Work	Sqm	1	1.80				0.40	0.72		
9.8	24.8		Sqm	1	15.00				0.40	6.00		
24.8	36.1		Sqm	1	11.30				0.40	4.52		
		Mariyannana Palya										
		1st Main Road (W0973)										
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	29.8		Sqm	1	14.80				0.40	5.92		
29.8	37.4	Culvert	Sqm	1	7.60				0.40	3.04		
37.4	52.4		Sqm	1	15.00				0.40	6.00		
52.4	67.4		Sqm	1	15.00				0.40	6.00		
67.4	82.4		Sqm	1	15.00				0.40	6.00		

Scanned by CamScanner

82.4	94.8		Sqm	1	12.40				0.40	4.96		
94.8	103.8	Culvert	Sqm	1	0.00				0.40	0.00		
103.8	118.8		Sqm	1	15.00				0.40	6.00		
118.8	128		Sqm	1	9.20				0.40	3.68		
128	135	Culvert	Sqm	1	0.00				0.40	0.00		
135	147.4		Sqm	1	12.40				0.40	4.96		
147.4	152.6	No Work	Sqm	1	0.00				0.40	0.00		
152.6	161.5		Sqm	1	8.90				0.40	3.56		
161.5	177	No Work	Sqm	1	0.00				0.40	0.00		
177	191.7		Sqm	1	14.70				0.40	5.88		
		20th R Cross Road (W0961)										
		RHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	45		Sqm	1	15.00				0.40	6.00		
45	47.5		Sqm	1	2.50				0.40	1.00		
47.5	53	Culvert	Sqm	1	0.00				0.40	0.00		
53	65		Sqm	1	12.00				0.40	4.80		
65	80		Sqm	1	15.00				0.40	6.00		
80	95		Sqm	1	15.00				0.40	6.00		
95	99.7		Sqm	1	4.70				0.40	1.88		
99.7	112	B S Slab	Sqm	1	12.30				0.40	4.92		
112	125		Sqm	1	13.00				0.40	5.20		
125	140		Sqm	1	15.00				0.40	6.00		
140	155		Sqm	1	15.00				0.40	6.00		
155	159.9		Sqm	1	4.90				0.40	1.96		
		LHS										
0	15		Sqm	1	15.00				0.40	6.00		
15	30		Sqm	1	15.00				0.40	6.00		
30	40.5		Sqm	1	10.50				0.40	4.20		
40.5	55	B S Slab	Sqm	1	14.50				0.40	5.80		
55	65.5	B S Slab	Sqm	1	10.50				0.40	4.20		
65.5	70.7	Culvert	Sqm	1	0.00				0.40	0.00		
70.7	85		Sqm	1	14.30				0.40	5.72		
85	100		Sqm	1	15.00				0.40	6.00		
100	111.8		Sqm	1	11.80				0.40	4.72		
111.8	116.9	No Work	Sqm	1	0.00				0.40	0.00		
116.9	130		Sqm	1	13.10				0.40	5.24		
130	144.5		Sqm	1	14.50				0.40	5.80		
144.5	148.7	No Work	Sqm	1	0.00				0.40	0.00		
148.7	164.3		Sqm	1	15.60				0.40	6.24		
								Total Executed Quantity		**884.36**	**85.00**	**75171.00**
								Tender Quantity		**1018.00**		

Item no.12	Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications and directions of the Engineer in charge.

		For Asphalt Road										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Cum	1	12.40	7.65	6.80	7.23	0.35	31.36		
12.4	23.1		Cum	1	10.70	6.80	6.80	6.80	0.35	25.47		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Cum	1	15.00	4.90	5.20	5.05	0.35	26.51		
15	29.8		Cum	1	14.80	5.20	5.60	5.40	0.35	27.97		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.35	33.08		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.35	32.81		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.35	33.34		
45	62.5		Cum	1	17.50	6.40	5.45	5.93	0.35	36.29		
		1st Main Road 1st Cross Road (W0973)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.35	33.08		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.35	32.81		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.35	33.34		
45	58.2		Cum	1	13.20	6.40	5.45	5.93	0.35	27.37		

Scanned by CamScanner

		1st Main Road (W0612)											
0	15		Cum	1	15.00	5.25	5.35	5.30	0.35	27.83			
15	30		Cum	1	15.00	5.35	6.60	5.98	0.35	31.37			
30	45		Cum	1	15.00	6.60	6.20	6.40	0.35	33.60			
45	60		Cum	1	15.00	6.20	6.05	6.13	0.35	32.16			
60	75		Cum	1	15.00	6.05	5.70	5.88	0.35	30.84			
75	90		Cum	1	15.00	5.70	5.90	5.80	0.35	30.45			
90	95.6		Cum	1	5.60	6.00	7.50	6.75	0.35	13.23			
95.6	105		Cum	1	9.40	7.50	7.30	7.40	0.35	24.35			
105	120		Cum	1	15.00	7.30	7.30	7.30	0.35	38.33			
120	124		Cum	1	4.00	7.30	8.20	7.75	0.35	10.85			
124	126.4		Cum	1	2.40	8.20	12.20	10.20	0.35	8.57			
126.4	135		Cum	1	8.60	12.20	12.30	12.25	0.35	36.87			
135	146.2		Cum	1	11.20	11.10	8.20	9.65	0.35	37.83			
146.2	160		Cum	1	13.80	8.20	8.70	8.45	0.35	40.81			
160	165.2		Cum	1	5.20	8.70	5.80	7.25	0.35	13.20			
165.2	180		Cum	1	14.80	5.80	6.15	5.98	0.35	30.95			
180	195		Cum	1	15.00	6.15	6.20	6.18	0.35	32.42			
195	201.4		Cum	1	6.40	6.20	6.50	6.35	0.35	14.22			
201.4	205.1		Cum	1	3.70	6.50	3.70	5.10	0.35	6.60			
205.1	207.5		Cum	1	2.40	3.70	1.60	2.65	0.35	2.23			
		1st Main 3rd Cross (W0989)											
0	15		Cum	1	15.00	5.65	5.60	5.63	0.35	29.53			
15	30		Cum	1	15.00	5.60	5.65	5.63	0.35	29.53			
30	45		Cum	1	15.00	5.65	5.45	5.55	0.35	29.14			
45	61.2		Cum	1	16.20	5.45	5.20	5.33	0.35	30.19			
		2nd Main Road (W0616)											
0	15		Cum	1	15.00	7.10	7.10	7.10	0.35	37.28			
15	16.7		Cum	1	1.70	7.10	7.10	7.10	0.35	4.22			
16.7	18	No Work	Cum	1	0.00	0.00	0.00	0.00	0.35	0.00			
18	30		Cum	1	12.00	5.20	5.40	5.30	0.35	22.26			
30	45		Cum	1	15.00	5.40	5.60	5.50	0.35	28.88			
45	60		Cum	1	15.00	5.60	5.50	5.55	0.35	29.14			
60	75		Cum	1	15.00	5.50	5.30	5.40	0.35	28.35			
75	90		Cum	1	15.00	5.30	5.65	5.48	0.35	28.74			
90	105		Cum	1	15.00	5.65	7.00	6.33	0.35	33.21			
105	120		Cum	1	15.00	7.00	6.70	6.85	0.35	35.96			
120	135		Cum	1	15.00	6.70	6.70	6.70	0.35	35.18			
135	150		Cum	1	15.00	6.70	6.70	6.70	0.35	35.18			
150	164		Cum	1	14.00	6.40	5.20	5.80	0.35	28.42			
164	180		Cum	1	16.00	5.20	6.20	5.70	0.35	31.92			
180	195		Cum	1	15.00	6.20	5.40	5.80	0.35	30.45			
195	210		Cum	1	15.00	5.40	6.70	6.05	0.35	31.76			
210	218		Cum	1	8.00	6.70	6.40	6.55	0.35	18.34			
218	219.5	No Work	Cum	1	0.00	0.00	0.00	0.00	0.35	0.00			
219.5	230		Cum	1	10.50	5.80	6.00	5.90	0.35	21.68			
230	245		Cum	1	15.00	6.00	5.00	5.50	0.35	28.88			
245	260		Cum	1	15.00	5.00	6.20	5.60	0.35	29.40			
260	275		Cum	1	15.00	6.20	6.00	6.10	0.35	32.03			
275	285.5		Cum	1	10.50	6.00	6.00	6.00	0.35	22.05			
		Munikempanna Layout											
		1st Cross Road (W0973)											
0	15		Cum	1	15.00	5.00	5.30	5.15	0.35	27.04			
15	30		Cum	1	15.00	5.30	5.80	5.55	0.35	29.14			
30	45		Cum	1	15.00	5.80	5.55	5.68	0.35	29.79			
45	60		Cum	1	15.00	5.55	5.80	5.68	0.35	29.79			
60	74.1		Cum	1	14.10	5.60	2.80	4.20	0.35	20.73			
74.1	85.8		Cum	1	11.70	2.80	2.50	2.65	0.35	10.85			
		21th Cross Road (W0969)											
0	15		Cum	1	15.00	7.90	6.20	7.05	0.35	37.01			
15	20.2		Cum	1	5.20	6.05	5.50	5.78	0.35	10.51			
20.2	33		Cum	1	12.80	5.60	6.00	5.80	0.35	25.98			
33	45		Cum	1	12.00	6.00	6.80	6.40	0.35	26.88			
45	60		Cum	1	15.00	5.60	6.60	6.10	0.35	32.03			
60	75		Cum	1	15.00	6.60	6.70	6.65	0.35	34.91			
75	90		Cum	1	15.00	6.70	6.65	6.68	0.35	35.04			
90	105		Cum	1	15.00	6.65	6.70	6.68	0.35	35.04			
105	120		Cum	1	15.00	6.70	6.70	6.70	0.35	35.18			

Scanned by CamScanner

120	130		Cum	1	10.00	6.70	6.70	6.70	0.35	23.45		
		Connecting Road-1 (W0608)										
0	3.9		Cum	1	3.90	7.20	6.95	7.08	0.35	9.66		
3.9	15		Cum	1	11.10	9.00	8.00	8.50	0.35	33.02		
15	23.8		Cum	1	8.80	8.00	7.60	7.80	0.35	24.02		
		Dead End (W0965)										
0	15		Cum	1	15.00	7.80	6.50	7.15	0.35	37.54		
15	23.8		Cum	1	8.80	6.70	5.50	6.10	0.35	18.79		
23.8	24.9		Cum	1	1.10	5.60	6.50	6.05	0.35	2.33		
24.9	36.9		Cum	1	12.00	6.50	6.50	6.50	0.35	27.30		
		Connecting Road-2										
0	15		Cum	1	15.00	5.90	5.90	5.90	0.35	30.98		
15	24		Cum	1	9.00	5.90	5.90	5.90	0.35	18.59		
		1st A Cross Road (W0975)										
0	15		Cum	1	15.00	7.70	7.90	7.80	0.35	40.95		
15	31.3		Cum	1	16.30	7.90	8.00	7.95	0.35	45.35		
		18th A Cross Road (W0618)										
0	15		Cum	1	15.00	5.80	5.60	5.70	0.35	29.93		
15	30		Cum	1	15.00	5.60	5.60	5.60	0.35	29.40		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.35	29.14		
45	60		Cum	1	15.00	5.50	4.90	5.20	0.35	27.30		
60	74.2		Cum	1	14.20	5.60	4.90	5.25	0.35	26.09		
		For CC Road Kaveri Layout Krishna Nivas House (W1309) South to North										
0	15		Cum	1	15.00	4.70	5.20	4.95	0.45	33.41		
15	30		Cum	1	15.00	5.20	5.20	5.20	0.45	35.10		
30	45		Cum	1	15.00	5.20	5.15	5.18	0.45	34.93		
45	60		Cum	1	15.00	5.15	5.25	5.20	0.45	35.10		
60	75		Cum	1	15.00	5.25	5.00	5.13	0.45	34.59		
75	90		Cum	1	15.00	5.00	5.35	5.18	0.45	34.93		
90	91.2		Cum	1	1.20	5.35	5.35	5.35	0.45	2.89		
		Joseph House Road (W0884) East to West										
0	11.6		Cum	1	11.60	5.85	5.85	5.85	0.45	30.54		
11.6	25		Cum	1	13.40	5.00	5.25	5.13	0.45	30.90		
25	40		Cum	1	15.00	5.25	5.00	5.13	0.45	34.59		
40	45.8		Cum	1	5.80	5.00	5.00	5.00	0.45	13.05		
		Moto Works Oppo. (W1299) North to South										
0	15		Cum	1	15.00	4.45	4.85	4.65	0.45	31.39		
15	30		Cum	1	15.00	4.85	5.60	5.23	0.45	35.27		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.45	37.46		
45	60		Cum	1	15.00	5.50	5.00	5.25	0.45	35.44		
60	75		Cum	1	15.00	5.00	5.50	5.25	0.45	35.44		
75	90		Cum	1	15.00	5.50	5.10	5.30	0.45	35.78		
90	105		Cum	1	15.00	5.10	5.30	5.20	0.45	35.10		
105	120		Cum	1	15.00	5.30	5.75	5.53	0.45	37.29		
120	132		Cum	1	12.00	5.75	7.15	6.45	0.45	34.83		
		Cross Road 1 (W0870) West to East										
0	15		Cum	1	15.00	4.55	4.60	4.58	0.45	30.88		
15	25.6		Cum	1	10.60	4.60	5.35	4.98	0.45	23.73		
		Cross Road 2 (W0862) West to East										
0	15		Cum	1	15.00	5.35	5.20	5.28	0.45	35.61		
15	30		Cum	1	15.00	5.20	5.55	5.38	0.45	36.28		
30	33		Cum	1	3.00	5.55	5.50	5.53	0.45	7.46		
		Cross Road (W1297) South to North										

Scanned by CamScanner

0	15		Cum	1	15.00	5.40	5.10	5.25	0.45	35.44		
15	30		Cum	1	15.00	5.10	4.70	4.90	0.45	33.08		
30	45		Cum	1	15.00	4.70	4.60	4.65	0.45	31.39		
45	60		Cum	1	15.00	4.60	4.50	4.55	0.45	30.71		
60	75		Cum	1	15.00	4.50	4.30	4.40	0.45	29.70		
75	90		Cum	1	15.00	4.30	4.00	4.15	0.45	28.01		
90	105		Cum	1	15.00	4.00	4.00	4.00	0.45	27.00		
		Kuvempu Layout										
		2nd Main 1st Cross Road (W0977)										
0	11.3		Cum	1	11.30	6.80	6.65	6.73	0.45	34.20		
11.3	21.7		Cum	1	10.40	6.65	5.50	6.08	0.45	28.43		
21.7	25.4		Cum	1	3.70	5.20	5.80	5.50	0.45	9.16		
25.4	35.1		Cum	1	9.70	5.30	6.25	5.78	0.45	25.21		
35.1	48.5		Cum	1	13.40	6.25	6.70	6.48	0.45	39.04		
									Total Executed Quantity	**3578.93**		
									Tender Quantity	**3314.53**		
									Quantity upto 125%	**3578.93**	**30.00**	**107368.00**
Item no.13		Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications and directions of the Engineer in charge.										
		For Asphalt Road										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Sqm	1	12.40	7.65	6.80	7.23		89.59		
12.4	23.1		Sqm	1	10.70	6.80	6.80	6.80		72.76		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Sqm	1	15.00	4.90	5.20	5.05		75.75		
15	29.8		Sqm	1	14.80	5.20	5.60	5.40		79.92		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	62.5		Sqm	1	17.50	6.40	5.45	5.93		103.69		
		1st Main Road 1st Cross Road (W0973)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	58.2		Sqm	1	13.20	6.40	5.45	5.93		78.21		
		1st Main Road (W0612)										
0	15		Sqm	1	15.00	5.25	5.35	5.30		79.50		
15	30		Sqm	1	15.00	5.35	6.60	5.98		89.63		
30	45		Sqm	1	15.00	6.60	6.20	6.40		96.00		
45	60		Sqm	1	15.00	6.20	6.05	6.13		91.88		
60	75		Sqm	1	15.00	6.05	5.70	5.88		88.13		
75	90		Sqm	1	15.00	5.70	5.90	5.80		87.00		
90	95.6		Sqm	1	5.60	6.00	7.50	6.75		37.80		
95.6	105		Sqm	1	9.40	7.50	7.30	7.40		69.56		
105	120		Sqm	1	15.00	7.30	7.30	7.30		109.50		
120	124		Sqm	1	4.00	7.30	8.20	7.75		31.00		
124	126.4		Sqm	1	2.40	8.20	12.20	10.20		24.48		
126.4	135		Sqm	1	8.60	12.20	12.30	12.25		105.35		
135	146.2		Sqm	1	11.20	11.10	8.20	9.65		108.08		
146.2	160		Sqm	1	13.80	8.20	8.70	8.45		116.61		
160	165.2		Sqm	1	5.20	8.70	5.80	7.25		37.70		
165.2	180		Sqm	1	14.80	5.80	6.15	5.98		88.43		
180	195		Sqm	1	15.00	6.15	6.20	6.18		92.63		
195	201.4		Sqm	1	6.40	6.20	6.50	6.35		40.64		
201.4	205.1		Sqm	1	3.70	6.50	3.70	5.10		18.87		
205.1	207.5		Sqm	1	2.40	3.70	1.60	2.65		6.36		
		1st Main 3rd Cross (W0989)										
0	15		Sqm	1	15.00	5.65	5.60	5.63		84.38		
15	30		Sqm	1	15.00	5.60	5.65	5.63		84.38		

Scanned by CamScanner

30	45		Sqm	1	15.00	5.65	5.45	5.55		83.25	
45	61.2		Sqm	1	16.20	5.45	5.20	5.33		86.27	
		2nd Main Road (W0616)									
0	15		Sqm	1	15.00	7.10	7.10	7.10		106.50	
15	16.7		Sqm	1	1.70	7.10	7.10	7.10		12.07	
16.7	18	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00	
18	30		Sqm	1	12.00	5.20	5.40	5.30		63.60	
30	45		Sqm	1	15.00	5.40	5.60	5.50		82.50	
45	60		Sqm	1	15.00	5.60	5.50	5.55		83.25	
60	75		Sqm	1	15.00	5.50	5.30	5.40		81.00	
75	90		Sqm	1	15.00	5.30	5.65	5.48		82.13	
90	105		Sqm	1	15.00	5.65	7.00	6.33		94.88	
105	120		Sqm	1	15.00	7.00	6.70	6.85		102.75	
120	135		Sqm	1	15.00	6.70	6.70	6.70		100.50	
135	150		Sqm	1	15.00	6.70	6.70	6.70		100.50	
150	164		Sqm	1	14.00	6.40	5.20	5.80		81.20	
164	180		Sqm	1	16.00	5.20	6.20	5.70		91.20	
180	195		Sqm	1	15.00	6.20	5.40	5.80		87.00	
195	210		Sqm	1	15.00	5.40	6.70	6.05		90.75	
210	218		Sqm	1	8.00	6.70	6.40	6.55		52.40	
218	219.5	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00	
219.5	230		Sqm	1	10.50	5.80	6.00	5.90		61.95	
230	245		Sqm	1	15.00	6.00	5.00	5.50		82.50	
245	260		Sqm	1	15.00	5.00	6.20	5.60		84.00	
260	275		Sqm	1	15.00	6.20	6.00	6.10		91.50	
275	285.5		Sqm	1	10.50	6.00	6.00	6.00		63.00	
		Munikempanna Layout									
		1st Cross Road (W0973)									
0	15		Sqm	1	15.00	5.00	5.30	5.15		77.25	
15	30		Sqm	1	15.00	5.30	5.80	5.55		83.25	
30	45		Sqm	1	15.00	5.80	5.55	5.68		85.13	
45	60		Sqm	1	15.00	5.55	5.80	5.68		85.13	
60	74.1		Sqm	1	14.10	5.60	2.80	4.20		59.22	
74.1	85.8		Sqm	1	11.70	2.80	2.50	2.65		31.01	
		21th Cross Road (W0969)									
0	15		Sqm	1	15.00	7.90	6.20	7.05		105.75	
15	20.2		Sqm	1	5.20	6.05	5.50	5.78		30.03	
20.2	33		Sqm	1	12.80	5.60	6.00	5.80		74.24	
33	45		Sqm	1	12.00	6.00	6.80	6.40		76.80	
45	60		Sqm	1	15.00	5.60	6.60	6.10		91.50	
60	75		Sqm	1	15.00	6.60	6.70	6.65		99.75	
75	90		Sqm	1	15.00	6.70	6.65	6.68		100.13	
90	105		Sqm	1	15.00	6.65	6.70	6.68		100.13	
105	120		Sqm	1	15.00	6.70	6.70	6.70		100.50	
120	130		Sqm	1	10.00	6.70	6.70	6.70		67.00	
		Connecting Road-1 (W0608)									
0	3.9		Sqm	1	3.90	7.20	6.95	7.08		27.59	
3.9	15		Sqm	1	11.10	9.00	8.00	8.50		94.35	
15	23.8		Sqm	1	8.80	8.00	7.60	7.80		68.64	
		Dead End (W0965)									
0	15		Sqm	1	15.00	7.80	6.50	7.15		107.25	
15	23.8		Sqm	1	8.80	6.70	5.50	6.10		53.68	
23.8	24.9		Sqm	1	1.10	5.60	6.50	6.05		6.65	
24.9	36.9		Sqm	1	12.00	6.50	6.50	6.50		78.00	
		Connecting Road-2									
0	15		Sqm	1	15.00	5.90	5.90	5.90		88.50	
15	24		Sqm	1	9.00	5.90	5.90	5.90		53.10	
		1st A Cross Road (W0975)									
0	15		Sqm	1	15.00	7.70	7.90	7.80		117.00	
15	31.3		Sqm	1	16.30	7.90	8.00	7.95		129.59	
		18th A Cross Road (W0618)									
0	15		Sqm	1	15.00	5.80	5.60	5.70		85.50	
15	30		Sqm	1	15.00	5.60	5.60	5.60		84.00	
30	45		Sqm	1	15.00	5.60	5.50	5.55		83.25	
45	60		Sqm	1	15.00	5.50	4.90	5.20		78.00	

Scanned by CamScanner

60	74.2		Sqm	1	14.20	5.60	4.90	5.25		74.55		
		For CC Road										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		South to North										
0	15		Sqm	1	15.00	4.70	5.20	4.95		74.25		
15	30		Sqm	1	15.00	5.20	5.20	5.20		78.00		
30	45		Sqm	1	15.00	5.20	5.15	5.18		77.63		
45	60		Sqm	1	15.00	5.15	5.25	5.20		78.00		
60	75		Sqm	1	15.00	5.25	5.00	5.13		76.88		
75	90		Sqm	1	15.00	5.00	5.35	5.18		77.63		
90	91.2		Sqm	1	1.20	5.35	5.35	5.35		6.42		
		Joseph House Road (W0884)										
		East to West										
0	11.6		Sqm	1	11.60	5.85	5.85	5.85		67.86		
11.6	25		Sqm	1	13.40	5.00	5.25	5.13		68.68		
25	40		Sqm	1	15.00	5.25	5.00	5.13		76.88		
40	45.8		Sqm	1	5.80	5.00	5.00	5.00		29.00		
		Moto Works Oppo. (W1299)										
		North to South										
0	15		Sqm	1	15.00	4.45	4.85	4.65		69.75		
15	30		Sqm	1	15.00	4.85	5.60	5.23		78.38		
30	45		Sqm	1	15.00	5.60	5.50	5.55		83.25		
45	60		Sqm	1	15.00	5.50	5.00	5.25		78.75		
60	75		Sqm	1	15.00	5.00	5.50	5.25		78.75		
75	90		Sqm	1	15.00	5.50	5.10	5.30		79.50		
90	105		Sqm	1	15.00	5.10	5.30	5.20		78.00		
105	120		Sqm	1	15.00	5.30	5.75	5.53		82.88		
120	132		Sqm	1	12.00	5.75	7.15	6.45		77.40		
		Cross Road 1 (W0870)										
		West to East										
0	15		Sqm	1	15.00	4.55	4.60	4.58		68.63		
15	25.6		Sqm	1	10.60	4.60	5.35	4.98		52.74		
		Cross Road 2 (W0862)										
		West to East										
0	15		Sqm	1	15.00	5.35	5.20	5.28		79.13		
15	30		Sqm	1	15.00	5.20	5.55	5.38		80.63		
30	33		Sqm	1	3.00	5.55	5.50	5.53		16.58		
		Cross Road (W1297)										
		South to North										
0	15		Sqm	1	15.00	5.40	5.10	5.25		78.75		
15	30		Sqm	1	15.00	5.10	4.70	4.90		73.50		
30	45		Sqm	1	15.00	4.70	4.60	4.65		69.75		
45	60		Sqm	1	15.00	4.60	4.50	4.55		68.25		
60	75		Sqm	1	15.00	4.50	4.30	4.40		66.00		
75	90		Sqm	1	15.00	4.30	4.00	4.15		62.25		
90	105		Sqm	1	15.00	4.00	4.00	4.00		60.00		
		Kuvempu Layout										
		2nd Main 1st Cross Road (W0977)										
0	11.3		Sqm	1	11.30	6.80	6.65	6.73		75.99		
11.3	21.7		Sqm	1	10.40	6.65	5.50	6.08		63.18		
21.7	25.4		Sqm	1	3.70	5.20	5.80	5.50		20.35		
25.4	35.1		Sqm	1	9.70	5.30	6.25	5.78		56.02		
35.1	48.5		Sqm	1	13.40	6.25	6.70	6.48		86.77		
									Total Executed Quantity	**9512.28**		
									Tender Quantity	**8954.75**		
									Quantity upto 125%	**9512.28**	**7.00**	**66586.00**
Item no.14		Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications and directions of the Engineer in charge.										
		For Asphalt Road										
		Kuvempu Layout										

Scanned by CamScanner

		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Cum	1	12.40	7.65	6.80	7.23	0.15	13.44		
12.4	23.1		Cum	1	10.70	6.80	6.80	6.80	0.15	10.91		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Cum	1	15.00	4.90	5.20	5.05	0.15	11.36		
15	29.8		Cum	1	14.80	5.20	5.60	5.40	0.15	11.99		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.15	14.18		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.15	14.06		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.15	14.29		
45	62.5		Cum	1	17.50	6.40	5.45	5.93	0.15	15.55		
		1st Main Road 1st Cross Road (W0973)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.15	14.18		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.15	14.06		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.15	14.29		
45	58.2		Cum	1	13.20	6.40	5.45	5.93	0.15	11.73		
		1st Main Road (W0612)										
0	15		Cum	1	15.00	5.25	5.35	5.30	0.15	11.93		
15	30		Cum	1	15.00	5.35	6.60	5.98	0.15	13.44		
30	45		Cum	1	15.00	6.60	6.20	6.40	0.15	14.40		
45	60		Cum	1	15.00	6.20	6.05	6.13	0.15	13.78		
60	75		Cum	1	15.00	6.05	5.70	5.88	0.15	13.22		
75	90		Cum	1	15.00	5.70	5.90	5.80	0.15	13.05		
90	95.6		Cum	1	5.60	6.00	7.50	6.75	0.15	5.67		
95.6	105		Cum	1	9.40	7.50	7.30	7.40	0.15	10.43		
105	120		Cum	1	15.00	7.30	7.30	7.30	0.15	16.43		
120	124		Cum	1	4.00	7.30	8.20	7.75	0.15	4.65		
124	126.4		Cum	1	2.40	8.20	12.20	10.20	0.15	3.67		
126.4	135		Cum	1	8.60	12.20	12.30	12.25	0.15	15.80		
135	146.2		Cum	1	11.20	11.10	8.20	9.65	0.15	16.21		
146.2	160		Cum	1	13.80	8.20	8.70	8.45	0.15	17.49		
160	165.2		Cum	1	5.20	8.70	5.80	7.25	0.15	5.65		
165.2	180		Cum	1	14.80	5.80	6.15	5.98	0.15	13.26		
180	195		Cum	1	15.00	6.15	6.20	6.18	0.15	13.89		
195	201.4		Cum	1	6.40	6.20	6.50	6.35	0.15	6.10		
201.4	205.1		Cum	1	3.70	6.50	3.70	5.10	0.15	2.83		
205.1	207.5		Cum	1	2.40	3.70	1.60	2.65	0.15	0.95		
		1st Main 3rd Cross (W0989)										
0	15		Cum	1	15.00	5.65	5.60	5.63	0.15	12.66		
15	30		Cum	1	15.00	5.60	5.65	5.63	0.15	12.66		
30	45		Cum	1	15.00	5.65	5.45	5.55	0.15	12.49		
45	61.2		Cum	1	16.20	5.45	5.20	5.33	0.15	12.94		
		2nd Main Road (W0616)										
0	15		Cum	1	15.00	7.10	7.10	7.10	0.15	15.98		
15	16.7		Cum	1	1.70	7.10	7.10	7.10	0.15	1.81		
16.7	18	No Work	Cum	1	0.00	0.00	0.00	0.00	0.15	0.00		
18	30		Cum	1	12.00	5.20	5.40	5.30	0.15	9.54		
30	45		Cum	1	15.00	5.40	5.60	5.50	0.15	12.38		
45	60		Cum	1	15.00	5.60	5.50	5.55	0.15	12.49		
60	75		Cum	1	15.00	5.50	5.30	5.40	0.15	12.15		
75	90		Cum	1	15.00	5.30	5.65	5.48	0.15	12.32		
90	105		Cum	1	15.00	5.65	7.00	6.33	0.15	14.23		
105	120		Cum	1	15.00	7.00	6.70	6.85	0.15	15.41		
120	135		Cum	1	15.00	6.70	6.70	6.70	0.15	15.08		
135	150		Cum	1	15.00	6.70	6.70	6.70	0.15	15.08		
150	164		Cum	1	14.00	6.40	5.20	5.80	0.15	12.18		
164	180		Cum	1	16.00	5.20	6.20	5.70	0.15	13.68		
180	195		Cum	1	15.00	6.20	5.40	5.80	0.15	13.05		
195	210		Cum	1	15.00	5.40	6.70	6.05	0.15	13.61		
210	218		Cum	1	8.00	6.70	6.40	6.55	0.15	7.86		
218	219.5	No Work	Cum	1	0.00	0.00	0.00	0.00	0.15	0.00		
219.5	230		Cum	1	10.50	5.80	6.00	5.90	0.15	9.29		
230	245		Cum	1	15.00	6.00	5.00	5.50	0.15	12.38		

Scanned by CamScanner

245	260		Cum	1	15.00	5.00	6.20	5.60	0.15	12.60		
260	275		Cum	1	15.00	6.20	6.00	6.10	0.15	13.73		
275	285.5		Cum	1	10.50	6.00	6.00	6.00	0.15	9.45		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0	15		Cum	1	15.00	5.00	5.30	5.15	0.15	11.59		
15	30		Cum	1	15.00	5.30	5.80	5.55	0.15	12.49		
30	45		Cum	1	15.00	5.80	5.55	5.68	0.15	12.77		
45	60		Cum	1	15.00	5.55	5.80	5.68	0.15	12.77		
60	74.1		Cum	1	14.10	5.60	2.80	4.20	0.15	8.88		
74.1	85.8		Cum	1	11.70	2.80	2.50	2.65	0.15	4.65		
		21th Cross Road (W0969)										
0	15		Cum	1	15.00	7.90	6.20	7.05	0.15	15.86		
15	20.2		Cum	1	5.20	6.05	5.50	5.78	0.15	4.50		
20.2	33		Cum	1	12.80	5.60	6.00	5.80	0.15	11.14		
33	45		Cum	1	12.00	6.00	6.80	6.40	0.15	11.52		
45	60		Cum	1	15.00	5.60	6.60	6.10	0.15	13.73		
60	75		Cum	1	15.00	6.60	6.70	6.65	0.15	14.96		
75	90		Cum	1	15.00	6.70	6.65	6.68	0.15	15.02		
90	105		Cum	1	15.00	6.65	6.70	6.68	0.15	15.02		
105	120		Cum	1	15.00	6.70	6.70	6.70	0.15	15.08		
120	130		Cum	1	10.00	6.70	6.70	6.70	0.15	10.05		
		Connecting Road-1 (W0608)										
0	3.9		Cum	1	3.90	7.20	6.95	7.08	0.15	4.14		
3.9	15		Cum	1	11.10	9.00	8.00	8.50	0.15	14.15		
15	23.8		Cum	1	8.80	8.00	7.60	7.80	0.15	10.30		
		Dead End (W0965)										
0	15		Cum	1	15.00	7.80	6.50	7.15	0.15	16.09		
15	23.8		Cum	1	8.80	6.70	5.50	6.10	0.15	8.05		
23.8	24.9		Cum	1	1.10	5.60	6.50	6.05	0.15	1.00		
24.9	36.9		Cum	1	12.00	6.50	6.50	6.50	0.15	11.70		
		Connecting Road-2										
0	15		Cum	1	15.00	5.90	5.90	5.90	0.15	13.28		
15	24		Cum	1	9.00	5.90	5.90	5.90	0.15	7.97		
		1st A Cross Road (W0975)										
0	15		Cum	1	15.00	7.70	7.90	7.80	0.15	17.55		
15	31.3		Cum	1	16.30	7.90	8.00	7.95	0.15	19.44		
		18th A Cross Road (W0618)										
0	15		Cum	1	15.00	5.80	5.60	5.70	0.15	12.83		
15	30		Cum	1	15.00	5.60	5.60	5.60	0.15	12.60		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.15	12.49		
45	60		Cum	1	15.00	5.50	4.90	5.20	0.15	11.70		
60	74.2		Cum	1	14.20	5.60	4.90	5.25	0.15	11.18		
		For CC Road										
		Kaveri Layout										
		Krishna Nivas House (W1309)										
		South to North										
0	15		Cum	1	15.00	4.70	5.20	4.95	0.15	11.14		
15	30		Cum	1	15.00	5.20	5.20	5.20	0.15	11.70		
30	45		Cum	1	15.00	5.20	5.15	5.18	0.15	11.64		
45	60		Cum	1	15.00	5.15	5.25	5.20	0.15	11.70		
60	75		Cum	1	15.00	5.25	5.00	5.13	0.15	11.53		
75	90		Cum	1	15.00	5.00	5.35	5.18	0.15	11.64		
90	91.2		Cum	1	1.20	5.35	5.35	5.35	0.15	0.96		
		Joseph House Road (W0884)										
		East to West										
0	11.6		Cum	1	11.60	5.85	5.85	5.85	0.15	10.18		
11.6	25		Cum	1	13.40	5.00	5.25	5.13	0.15	10.30		
25	40		Cum	1	15.00	5.25	5.00	5.13	0.15	11.53		
40	45.8		Cum	1	5.80	5.00	5.00	5.00	0.15	4.35		
		Moto Works Oppo. (W1299)										
		North to South										

Scanned by CamScanner

0	15		Cum	1	15.00	4.45	4.85	4.65	0.15	10.46		
15	30		Cum	1	15.00	4.85	5.60	5.23	0.15	11.76		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.15	12.49		
45	60		Cum	1	15.00	5.50	5.00	5.25	0.15	11.81		
60	75		Cum	1	15.00	5.00	5.50	5.25	0.15	11.81		
75	90		Cum	1	15.00	5.50	5.10	5.30	0.15	11.93		
90	105		Cum	1	15.00	5.10	5.30	5.20	0.15	11.70		
105	120		Cum	1	15.00	5.30	5.75	5.53	0.15	12.43		
120	132		Cum	1	12.00	5.75	7.15	6.45	0.15	11.61		
		Cross Road 1 (W0870)										
		West to East										
0	15		Cum	1	15.00	4.55	4.60	4.58	0.15	10.29		
15	25.6		Cum	1	10.60	4.60	5.35	4.98	0.15	7.91		
		Cross Road 2 (W0862)										
		West to East										
0	15		Cum	1	15.00	5.35	5.20	5.28	0.15	11.87		
15	30		Cum	1	15.00	5.20	5.55	5.38	0.15	12.09		
30	33		Cum	1	3.00	5.55	5.50	5.53	0.15	2.49		
		Cross Road (W1297)										
		South to North										
0	15		Cum	1	15.00	5.40	5.10	5.25	0.15	11.81		
15	30		Cum	1	15.00	5.10	4.70	4.90	0.15	11.03		
30	45		Cum	1	15.00	4.70	4.60	4.65	0.15	10.46		
45	60		Cum	1	15.00	4.60	4.50	4.55	0.15	10.24		
60	75		Cum	1	15.00	4.50	4.30	4.40	0.15	9.90		
75	90		Cum	1	15.00	4.30	4.00	4.15	0.15	9.34		
90	105		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
.												
		Kuvempu Layout										
		2nd Main 1st Cross Road (W0977)										
0	11.3		Cum	1	11.30	6.80	6.65	6.73	0.15	11.40		
11.3	21.7		Cum	1	10.40	6.65	5.50	6.08	0.15	9.48		
21.7	25.4		Cum	1	3.70	5.20	5.80	5.50	0.15	3.05		
25.4	35.1		Cum	1	9.70	5.30	6.25	5.78	0.15	8.40		
35.1	48.5		Cum	1	13.40	6.25	6.70	6.48	0.15	13.01		
									Total Executed Quantity	**1426.84**		
									Tender Quantity	**1343.21**		
									Quantity upto 125%	**1426.84**	**2000.00**	**2853683.00**

Item no.15 Providing, laying, spreading and compacting cushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed materials by tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications and directions of the Engineer in charge.

		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Cum	1	12.40	7.65	6.80	7.23	0.20	17.92		
12.4	23.1		Cum	1	10.70	6.80	6.80	6.80	0.20	14.55		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Cum	1	15.00	4.90	5.20	5.05	0.20	15.15		
15	29.8		Cum	1	14.80	5.20	5.60	5.40	0.20	15.98		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.20	18.90		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.20	18.75		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.20	19.05		
45	62.5		Cum	1	17.50	6.40	5.45	5.93	0.20	20.74		
		1st Main Road 1st Cross Road (W0973)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.20	18.90		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.20	18.75		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.20	19.05		
45	58.2		Cum	1	13.20	6.40	5.45	5.93	0.20	15.64		
		1st Main Road (W0612)										

Scanned by CamScanner

0	15		Cum	1	15.00	5.25	5.35	5.30	0.20	15.90		
15	30		Cum	1	15.00	5.35	6.60	5.98	0.20	17.93		
30	45		Cum	1	15.00	6.60	6.20	6.40	0.20	19.20		
45	60		Cum	1	15.00	6.20	6.05	6.13	0.20	18.38		
60	75		Cum	1	15.00	6.05	5.70	5.88	0.20	17.63		
75	90		Cum	1	15.00	5.70	5.90	5.80	0.20	17.40		
90	95.6		Cum	1	5.60	6.00	7.50	6.75	0.20	7.56		
95.6	105		Cum	1	9.40	7.50	7.30	7.40	0.20	13.91		
105	120		Cum	1	15.00	7.30	7.30	7.30	0.20	21.90		
120	124		Cum	1	4.00	7.30	8.20	7.75	0.20	6.20		
124	126.4		Cum	1	2.40	8.20	12.20	10.20	0.20	4.90		
126.4	135		Cum	1	8.60	12.20	12.30	12.25	0.20	21.07		
135	146.2		Cum	1	11.20	11.10	8.20	9.65	0.20	21.62		
146.2	160		Cum	1	13.80	8.20	8.70	8.45	0.20	23.32		
160	165.2		Cum	1	5.20	8.70	5.80	7.25	0.20	7.54		
165.2	180		Cum	1	14.80	5.80	6.15	5.98	0.20	17.69		
180	195		Cum	1	15.00	6.15	6.20	6.18	0.20	18.53		
195	201.4		Cum	1	6.40	6.20	6.50	6.35	0.20	8.13		
201.4	205.1		Cum	1	3.70	6.50	3.70	5.10	0.20	3.77		
205.1	207.5		Cum	1	2.40	3.70	1.60	2.65	0.20	1.27		
		1st Main 3rd Cross (W0989)										
0	15		Cum	1	15.00	5.65	5.60	5.63	0.20	16.88		
15	30		Cum	1	15.00	5.60	5.65	5.63	0.20	16.88		
30	45		Cum	1	15.00	5.65	5.45	5.55	0.20	16.65		
45	61.2		Cum	1	16.20	5.45	5.20	5.33	0.20	17.25		
		2nd Main Road (W0616)										
0	15		Cum	1	15.00	7.10	7.10	7.10	0.20	21.30		
15	16.7		Cum	1	1.70	7.10	7.10	7.10	0.20	2.41		
16.7	18	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
18	30		Cum	1	12.00	5.20	5.40	5.30	0.20	12.72		
30	45		Cum	1	15.00	5.40	5.60	5.50	0.20	16.50		
45	60		Cum	1	15.00	5.60	5.50	5.55	0.20	16.65		
60	75		Cum	1	15.00	5.50	5.30	5.40	0.20	16.20		
75	90		Cum	1	15.00	5.30	5.65	5.48	0.20	16.43		
90	105		Cum	1	15.00	5.65	7.00	6.33	0.20	18.98		
105	120		Cum	1	15.00	7.00	6.70	6.85	0.20	20.55		
120	135		Cum	1	15.00	6.70	6.70	6.70	0.20	20.10		
135	150		Cum	1	15.00	6.70	6.70	6.70	0.20	20.10		
150	164		Cum	1	14.00	6.40	5.20	5.80	0.20	16.24		
164	180		Cum	1	16.00	5.20	6.20	5.70	0.20	18.24		
180	195		Cum	1	15.00	6.20	5.40	5.80	0.20	17.40		
195	210		Cum	1	15.00	5.40	6.70	6.05	0.20	18.15		
210	218		Cum	1	8.00	6.70	6.40	6.55	0.20	10.48		
218	219.5	No Work	Cum	1	0.00	0.00	0.00	0.00	0.20	0.00		
219.5	230		Cum	1	10.50	5.80	6.00	5.90	0.20	12.39		
230	245		Cum	1	15.00	6.00	5.00	5.50	0.20	16.50		
245	260		Cum	1	15.00	5.00	6.20	5.60	0.20	16.80		
260	275		Cum	1	15.00	6.20	6.00	6.10	0.20	18.30		
275	285.5		Cum	1	10.50	6.00	6.00	6.00	0.20	12.60		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0	15		Cum	1	15.00	5.00	5.30	5.15	0.20	15.45		
15	30		Cum	1	15.00	5.30	5.80	5.55	0.20	16.65		
30	45		Cum	1	15.00	5.80	5.55	5.68	0.20	17.03		
45	60		Cum	1	15.00	5.55	5.80	5.68	0.20	17.03		
60	74.1		Cum	1	14.10	5.60	2.80	4.20	0.20	11.84		
74.1	85.8		Cum	1	11.70	2.80	2.50	2.65	0.20	6.20		
		21th Cross Road (W0969)										
0	15		Cum	1	15.00	7.90	6.20	7.05	0.20	21.15		
15	20.2		Cum	1	5.20	6.05	5.50	5.78	0.20	6.01		
20.2	33		Cum	1	12.80	5.60	6.00	5.80	0.20	14.85		
33	45		Cum	1	12.00	6.00	6.80	6.40	0.20	15.36		
45	60		Cum	1	15.00	5.60	6.60	6.10	0.20	18.30		
60	75		Cum	1	15.00	6.60	6.70	6.65	0.20	19.95		
75	90		Cum	1	15.00	6.70	6.65	6.68	0.20	20.03		
90	105		Cum	1	15.00	6.65	6.70	6.68	0.20	20.03		
105	120		Cum	1	15.00	6.70	6.70	6.70	0.20	20.10		
120	130		Cum	1	10.00	6.70	6.70	6.70	0.20	13.40		

Scanned by CamScanner

		Connecting Road-1 (W0608)										
0	3.9		Cum	1	3.90	7.20	6.95	7.08	0.20	5.52		
3.9	15		Cum	1	11.10	9.00	8.00	8.50	0.20	18.87		
15	23.8		Cum	1	8.80	8.00	7.60	7.80	0.20	13.73		
		Dead End (W0965)										
0	15		Cum	1	15.00	7.80	6.50	7.15	0.20	21.45		
15	23.8		Cum	1	8.80	6.70	5.50	6.10	0.20	10.74		
23.8	24.9		Cum	1	1.10	5.60	6.50	6.05	0.20	1.33		
24.9	36.9		Cum	1	12.00	6.50	6.50	6.50	0.20	15.60		
		Connecting Road-2										
0	15		Cum	1	15.00	5.90	5.90	5.90	0.20	17.70		
15	24		Cum	1	9.00	5.90	5.90	5.90	0.20	10.62		
		1st A Cross Road (W0975)										
0	15		Cum	1	15.00	7.70	7.90	7.80	0.20	23.40		
15	31.3		Cum	1	16.30	7.90	8.00	7.95	0.20	25.92		
		18th A Cross Road (W0618)										
0	15		Cum	1	15.00	5.80	5.60	5.70	0.20	17.10		
15	30		Cum	1	15.00	5.60	5.60	5.60	0.20	16.80		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.20	16.65		
45	60		Cum	1	15.00	5.50	4.90	5.20	0.20	15.60		
60	74.2		Cum	1	14.20	5.60	4.90	5.25	0.20	14.91		
									Total Executed Quantity	**1403.19**	**2100.00**	**2946691.00**
									Tender Quantity	**1430.21**		

Item no.16 Providing and applying primer coat with S.S. bitumen emulsion on prepared surface of granular base such as WMM including cleaning of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications and directions of the Engineer in charge.

		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Sqm	1	12.40	7.65	6.80	7.23		89.59		
12.4	23.1		Sqm	1	10.70	6.80	6.80	6.80		72.76		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Sqm	1	15.00	4.90	5.20	5.05		75.75		
15	29.8		Sqm	1	14.80	5.20	5.60	5.40		79.92		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	62.5		Sqm	1	17.50	6.40	5.45	5.93		103.69		
		1st Main Road 1st Cross Road (W0973)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	58.2		Sqm	1	13.20	6.40	5.45	5.93		78.21		
		1st Main Road (W0612)										
0	15		Sqm	1	15.00	5.25	5.35	5.30		79.50		
15	30		Sqm	1	15.00	5.35	6.60	5.98		89.63		
30	45		Sqm	1	15.00	6.60	6.20	6.40		96.00		
45	60		Sqm	1	15.00	6.20	6.05	6.13		91.88		
60	75		Sqm	1	15.00	6.05	5.70	5.88		88.13		
75	90		Sqm	1	15.00	5.70	5.90	5.80		87.00		
90	95.6		Sqm	1	5.60	6.00	7.50	6.75		37.80		
95.6	105		Sqm	1	9.40	7.50	7.30	7.40		69.56		
105	120		Sqm	1	15.00	7.30	7.30	7.30		109.50		
120	124		Sqm	1	4.00	7.30	8.20	7.75		31.00		
124	126.4		Sqm	1	2.40	8.20	12.20	10.20		24.48		
126.4	135		Sqm	1	8.60	12.20	12.30	12.25		105.35		
135	146.2		Sqm	1	11.20	11.10	8.20	9.65		108.08		
146.2	160		Sqm	1	13.80	8.20	8.70	8.45		116.61		
160	165.2		Sqm	1	5.20	8.70	5.80	7.25		37.70		
165.2	180		Sqm	1	14.80	5.80	6.15	5.98		88.43		

Scanned by CamScanner

180	195		Sqm	1	15.00	6.15	6.20	6.18		92.63		
195	201.4		Sqm	1	6.40	6.20	6.50	6.35		40.64		
201.4	205.1		Sqm	1	3.70	6.50	3.70	5.10		18.87		
205.1	207.5		Sqm	1	2.40	3.70	1.60	2.65		6.36		
		1st Main 3rd Cross (W0989)										
0	15		Sqm	1	15.00	5.65	5.60	5.63		84.38		
15	30		Sqm	1	15.00	5.60	5.65	5.63		84.38		
30	45		Sqm	1	15.00	5.65	5.45	5.55		83.25		
45	61.2		Sqm	1	16.20	5.45	5.20	5.33		86.27		
		2nd Main Road (W0616)										
0	15		Sqm	1	15.00	7.10	7.10	7.10		106.50		
15	16.7		Sqm	1	1.70	7.10	7.10	7.10		12.07		
16.7	18	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
18	30		Sqm	1	12.00	5.20	5.40	5.30		63.60		
30	45		Sqm	1	15.00	5.40	5.60	5.50		82.50		
45	60		Sqm	1	15.00	5.60	5.50	5.55		83.25		
60	75		Sqm	1	15.00	5.50	5.30	5.40		81.00		
75	90		Sqm	1	15.00	5.30	5.65	5.48		82.13		
90	105		Sqm	1	15.00	5.65	7.00	6.33		94.88		
105	120		Sqm	1	15.00	7.00	6.70	6.85		102.75		
120	135		Sqm	1	15.00	6.70	6.70	6.70		100.50		
135	150		Sqm	1	15.00	6.70	6.70	6.70		100.50		
150	164		Sqm	1	14.00	6.40	5.20	5.80		81.20		
164	180		Sqm	1	16.00	5.20	6.20	5.70		91.20		
180	195		Sqm	1	15.00	6.20	5.40	5.80		87.00		
195	210		Sqm	1	15.00	5.40	6.70	6.05		90.75		
210	218		Sqm	1	8.00	6.70	6.40	6.55		52.40		
218	219.5	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
219.5	230		Sqm	1	10.50	5.80	6.00	5.90		61.95		
230	245		Sqm	1	15.00	6.00	5.00	5.50		82.50		
245	260		Sqm	1	15.00	5.00	6.20	5.60		84.00		
260	275		Sqm	1	15.00	6.20	6.00	6.10		91.50		
275	285.5		Sqm	1	10.50	6.00	6.00	6.00		63.00		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0	15		Sqm	1	15.00	5.00	5.30	5.15		77.25		
15	30		Sqm	1	15.00	5.30	5.80	5.55		83.25		
30	45		Sqm	1	15.00	5.80	5.55	5.68		85.13		
45	60		Sqm	1	15.00	5.55	5.80	5.68		85.13		
60	74.1		Sqm	1	14.10	5.60	2.80	4.20		59.22		
74.1	85.8		Sqm	1	11.70	2.80	2.50	2.65		31.01		
		21th Cross Road (W0969)										
0	15		Sqm	1	15.00	7.90	6.20	7.05		105.75		
15	20.2		Sqm	1	5.20	6.05	5.50	5.78		30.03		
20.2	33		Sqm	1	12.80	5.60	6.00	5.80		74.24		
33	45		Sqm	1	12.00	6.00	6.80	6.40		76.80		
45	60		Sqm	1	15.00	5.60	6.60	6.10		91.50		
60	75		Sqm	1	15.00	6.60	6.70	6.65		99.75		
75	90		Sqm	1	15.00	6.70	6.65	6.68		100.13		
90	105		Sqm	1	15.00	6.65	6.70	6.68		100.13		
105	120		Sqm	1	15.00	6.70	6.70	6.70		100.50		
120	130		Sqm	1	10.00	6.70	6.70	6.70		67.00		
		Connecting Road-1 (W0608)										
0	3.9		Sqm	1	3.90	7.20	6.95	7.08		27.59		
3.9	15		Sqm	1	11.10	9.00	8.00	8.50		94.35		
15	23.8		Sqm	1	8.80	8.00	7.60	7.80		68.64		
		Dead End (W0965)										
0	15		Sqm	1	15.00	7.80	6.50	7.15		107.25		
15	23.8		Sqm	1	8.80	6.70	5.50	6.10		53.68		
23.8	24.9		Sqm	1	1.10	5.60	6.50	6.05		6.65		
24.9	36.9		Sqm	1	12.00	6.50	6.50	6.50		78.00		
		Connecting Road-2										
0	15		Sqm	1	15.00	5.90	5.90	5.90		88.50		
15	24		Sqm	1	9.00	5.90	5.90	5.90		53.10		
		1st A Cross Road (W0975)										

Scanned by CamScanner

0	15		Sqm	1	15.00	7.70	7.90	7.80		117.00		
15	31.3		Sqm	1	16.30	7.90	8.00	7.95		129.59		
		18th A Cross Road (W0618)										
0	15		Sqm	1	15.00	5.80	5.60	5.70		85.50		
15	30		Sqm	1	15.00	5.60	5.60	5.60		84.00		
30	45		Sqm	1	15.00	5.60	5.50	5.55		83.25		
45	60		Sqm	1	15.00	5.50	4.90	5.20		78.00		
60	74.2		Sqm	1	14.20	5.60	4.90	5.25		74.55		
									Total Executed Quantity	**7015.93**	**35.00**	**245558.00**
									Tender Quantity	**7151.05**		

Item no.17 Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base / binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by smooth wheeled, vibratory & tandem rollers to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specifications and directions of the Engineer in charge.

		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Cum	1	12.40	7.65	6.80	7.23	0.05	4.48		
12.4	23.1		Cum	1	10.70	6.80	6.80	6.80	0.05	3.64		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Cum	1	15.00	4.90	5.20	5.05	0.05	3.79		
15	29.8		Cum	1	14.80	5.20	5.60	5.40	0.05	4.00		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.05	4.73		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.05	4.69		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.05	4.76		
45	62.5		Cum	1	17.50	6.40	5.45	5.93	0.05	5.18		
		1st Main Road 1st Cross Road (W0973)										
0	15		Cum	1	15.00	6.40	6.20	6.30	0.05	4.73		
15	30		Cum	1	15.00	6.20	6.30	6.25	0.05	4.69		
30	45		Cum	1	15.00	6.30	6.40	6.35	0.05	4.76		
45	58.2		Cum	1	13.20	6.40	5.45	5.93	0.05	3.91		
		1st Main Road (W0612)										
0	15		Cum	1	15.00	5.25	5.35	5.30	0.05	3.98		
15	30		Cum	1	15.00	5.35	6.60	5.98	0.05	4.48		
30	45		Cum	1	15.00	6.60	6.20	6.40	0.05	4.80		
45	60		Cum	1	15.00	6.20	6.05	6.13	0.05	4.59		
60	75		Cum	1	15.00	6.05	5.70	5.88	0.05	4.41		
75	90		Cum	1	15.00	5.70	5.90	5.80	0.05	4.35		
90	95.6		Cum	1	5.60	6.00	7.50	6.75	0.05	1.89		
95.6	105		Cum	1	9.40	7.50	7.30	7.40	0.05	3.48		
105	120		Cum	1	15.00	7.30	7.30	7.30	0.05	5.48		
120	124		Cum	1	4.00	7.30	8.20	7.75	0.05	1.55		
124	126.4		Cum	1	2.40	8.20	12.20	10.20	0.05	1.22		
126.4	135		Cum	1	8.60	12.20	12.30	12.25	0.05	5.27		
135	146.2		Cum	1	11.20	11.10	8.20	9.65	0.05	5.40		
146.2	160		Cum	1	13.80	8.20	8.70	8.45	0.05	5.83		
160	165.2		Cum	1	5.20	8.70	5.80	7.25	0.05	1.89		
165.2	180		Cum	1	14.80	5.80	6.15	5.98	0.05	4.42		
180	195		Cum	1	15.00	6.15	6.20	6.18	0.05	4.63		
195	201.4		Cum	1	6.40	6.20	6.50	6.35	0.05	2.03		
201.4	205.1		Cum	1	3.70	6.50	3.70	5.10	0.05	0.94		
205.1	207.5		Cum	1	2.40	3.70	1.60	2.65	0.05	0.32		
		1st Main 3rd Cross (W0989)										
0	15		Cum	1	15.00	5.65	5.60	5.63	0.05	4.22		
15	30		Cum	1	15.00	5.60	5.65	5.63	0.05	4.22		
30	45		Cum	1	15.00	5.65	5.45	5.55	0.05	4.16		
45	61.2		Cum	1	16.20	5.45	5.20	5.33	0.05	4.31		
		2nd Main Road (W0616)										
0	15		Cum	1	15.00	7.10	7.10	7.10	0.05	5.33		
15	16.7		Cum	1	1.70	7.10	7.10	7.10	0.05	0.60		

Scanned by CamScanner

16.7	18	No Work	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
18	30		Cum	1	12.00	5.20	5.40	5.30	0.05	3.18		
30	45		Cum	1	15.00	5.40	5.60	5.50	0.05	4.13		
45	60		Cum	1	15.00	5.60	5.50	5.55	0.05	4.16		
60	75		Cum	1	15.00	5.50	5.30	5.40	0.05	4.05		
75	90		Cum	1	15.00	5.30	5.65	5.48	0.05	4.11		
90	105		Cum	1	15.00	5.65	7.00	6.33	0.05	4.74		
105	120		Cum	1	15.00	7.00	6.70	6.85	0.05	5.14		
120	135		Cum	1	15.00	6.70	6.70	6.70	0.05	5.03		
135	150		Cum	1	15.00	6.70	6.70	6.70	0.05	5.03		
150	164		Cum	1	14.00	6.40	5.20	5.80	0.05	4.06		
164	180		Cum	1	16.00	5.20	6.20	5.70	0.05	4.56		
180	195		Cum	1	15.00	6.20	5.40	5.80	0.05	4.35		
195	210		Cum	1	15.00	5.40	6.70	6.05	0.05	4.54		
210	218		Cum	1	8.00	6.70	6.40	6.55	0.05	2.62		
218	219.5	No Work	Cum	1	0.00	0.00	0.00	0.00	0.05	0.00		
219.5	230		Cum	1	10.50	5.80	6.00	5.90	0.05	3.10		
230	245		Cum	1	15.00	6.00	5.00	5.50	0.05	4.13		
245	260		Cum	1	15.00	5.00	6.20	5.60	0.05	4.20		
260	275		Cum	1	15.00	6.20	6.00	6.10	0.05	4.58		
275	285.5		Cum	1	10.50	6.00	6.00	6.00	0.05	3.15		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0	15		Cum	1	15.00	5.00	5.30	5.15	0.05	3.86		
15	30		Cum	1	15.00	5.30	5.80	5.55	0.05	4.16		
30	45		Cum	1	15.00	5.80	5.55	5.68	0.05	4.26		
45	60		Cum	1	15.00	5.55	5.80	5.68	0.05	4.26		
60	74.1		Cum	1	14.10	5.60	2.80	4.20	0.05	2.96		
74.1	85.8		Cum	1	11.70	2.80	2.50	2.65	0.05	1.55		
		21th Cross Road (W0969)										
0	15		Cum	1	15.00	7.90	6.20	7.05	0.05	5.29		
15	20.2		Cum	1	5.20	6.05	5.50	5.78	0.05	1.50		
20.2	33		Cum	1	12.80	5.60	6.00	5.80	0.05	3.71		
33	45		Cum	1	12.00	6.00	6.80	6.40	0.05	3.84		
45	60		Cum	1	15.00	5.60	6.60	6.10	0.05	4.58		
60	75		Cum	1	15.00	6.60	6.70	6.65	0.05	4.99		
75	90		Cum	1	15.00	6.70	6.65	6.68	0.05	5.01		
90	105		Cum	1	15.00	6.65	6.70	6.68	0.05	5.01		
105	120		Cum	1	15.00	6.70	6.70	6.70	0.05	5.03		
120	130		Cum	1	10.00	6.70	6.70	6.70	0.05	3.35		
		Connecting Road-1 (W0608)										
0	3.9		Cum	1	3.90	7.20	6.95	7.08	0.05	1.38		
3.9	15		Cum	1	11.10	9.00	8.00	8.50	0.05	4.72		
15	23.8		Cum	1	8.80	8.00	7.60	7.80	0.05	3.43		
		Dead End (W0965)										
0	15		Cum	1	15.00	7.80	6.50	7.15	0.05	5.36		
15	23.8		Cum	1	8.80	6.70	5.50	6.10	0.05	2.68		
23.8	24.9		Cum	1	1.10	5.60	6.50	6.05	0.05	0.33		
24.9	36.9		Cum	1	12.00	6.50	6.50	6.50	0.05	3.90		
		Connecting Road-2										
0	15		Cum	1	15.00	5.90	5.90	5.90	0.05	4.43		
15	24		Cum	1	9.00	5.90	5.90	5.90	0.05	2.66		
		1st A Cross Road (W0975)										
0	15		Cum	1	15.00	7.70	7.90	7.80	0.05	5.85		
15	31.3		Cum	1	16.30	7.90	8.00	7.95	0.05	6.48		
		18th A Cross Road (W0618)										
0	15		Cum	1	15.00	5.80	5.60	5.70	0.05	4.28		
15	30		Cum	1	15.00	5.60	5.60	5.60	0.05	4.20		
30	45		Cum	1	15.00	5.60	5.50	5.55	0.05	4.16		
45	60		Cum	1	15.00	5.50	4.90	5.20	0.05	3.90		
60	74.2		Cum	1	14.20	5.60	4.90	5.25	0.05	3.73		
								Total Executed Quantity		**350.80**	**8000.00**	**2806372.00**
								Tender Quantity		**357.55**		

Scanned by CamScanner

Item no.18		Providing and applying tack coat using 80/100 grade bitumen(VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM complete as per specifications and directions of the Engineer in charge.										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0	12.4		Sqm	1	12.40	7.65	6.80	7.23		89.59		
12.4	23.1		Sqm	1	10.70	6.80	6.80	6.80		72.76		
		2nd Main Road 2nd Cross Road (W0616)										
0	15		Sqm	1	15.00	4.90	5.20	5.05		75.75		
15	29.8		Sqm	1	14.80	5.20	5.60	5.40		79.92		
		1st Main Road 2nd Cross Road (W0983)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	62.5		Sqm	1	17.50	6.40	5.45	5.93		103.69		
		1st Main Road 1st Cross Road (W0973)										
0	15		Sqm	1	15.00	6.40	6.20	6.30		94.50		
15	30		Sqm	1	15.00	6.20	6.30	6.25		93.75		
30	45		Sqm	1	15.00	6.30	6.40	6.35		95.25		
45	58.2		Sqm	1	13.20	6.40	5.45	5.93		78.21		
		1st Main Road (W0612)										
0	15		Sqm	1	15.00	5.25	5.35	5.30		79.50		
15	30		Sqm	1	15.00	5.35	6.60	5.98		89.63		
30	45		Sqm	1	15.00	6.60	6.20	6.40		96.00		
45	60		Sqm	1	15.00	6.20	6.05	6.13		91.88		
60	75		Sqm	1	15.00	6.05	5.70	5.88		88.13		
75	90		Sqm	1	15.00	5.70	5.90	5.80		87.00		
90	95.6		Sqm	1	5.60	6.00	7.50	6.75		37.80		
95.6	105		Sqm	1	9.40	7.50	7.30	7.40		69.56		
105	120		Sqm	1	15.00	7.30	7.30	7.30		109.50		
120	124		Sqm	1	4.00	7.30	8.20	7.75		31.00		
124	126.4		Sqm	1	2.40	8.20	12.20	10.20		24.48		
126.4	135		Sqm	1	8.60	12.20	12.30	12.25		105.35		
135	146.2		Sqm	1	11.20	11.10	8.20	9.65		108.08		
146.2	160		Sqm	1	13.80	8.20	8.70	8.45		116.61		
160	165.2		Sqm	1	5.20	8.70	5.80	7.25		37.70		
165.2	180		Sqm	1	14.80	5.80	6.15	5.98		88.43		
180	195		Sqm	1	15.00	6.15	6.20	6.18		92.63		
195	201.4		Sqm	1	6.40	6.20	6.50	6.35		40.64		
201.4	205.1		Sqm	1	3.70	6.50	3.70	5.10		18.87		
205.1	207.5		Sqm	1	2.40	3.70	1.60	2.65		6.36		
		1st Main 3rd Cross (W0989)										
0	15		Sqm	1	15.00	5.65	5.60	5.63		84.38		
15	30		Sqm	1	15.00	5.60	5.65	5.63		84.38		
30	45		Sqm	1	15.00	5.65	5.45	5.55		83.25		
45	61.2		Sqm	1	16.20	5.45	5.20	5.33		86.27		
		2nd Main Road (W0616)										
0	15		Sqm	1	15.00	7.10	7.10	7.10		106.50		
15	16.7		Sqm	1	1.70	7.10	7.10	7.10		12.07		
16.7	18	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
18	30		Sqm	1	12.00	5.20	5.40	5.30		63.60		
30	45		Sqm	1	15.00	5.40	5.60	5.50		82.50		
45	60		Sqm	1	15.00	5.60	5.50	5.55		83.25		
60	75		Sqm	1	15.00	5.50	5.30	5.40		81.00		
75	90		Sqm	1	15.00	5.30	5.65	5.48		82.13		
90	105		Sqm	1	15.00	5.65	7.00	6.33		94.88		
105	120		Sqm	1	15.00	7.00	6.70	6.85		102.75		
120	135		Sqm	1	15.00	6.70	6.70	6.70		100.50		
135	150		Sqm	1	15.00	6.70	6.70	6.70		100.50		
150	164		Sqm	1	14.00	6.40	5.20	5.80		81.20		
164	180		Sqm	1	16.00	5.20	6.20	5.70		91.20		
180	195		Sqm	1	15.00	6.20	5.40	5.80		87.00		

Scanned by CamScanner

195	210		Sqm	1	15.00	5.40	6.70	6.05		90.75		
210	218		Sqm	1	8.00	6.70	6.40	6.55		52.40		
218	219.5	No Work	Sqm	1	0.00	0.00	0.00	0.00		0.00		
219.5	230		Sqm	1	10.50	5.80	6.00	5.90		61.95		
230	245		Sqm	1	15.00	6.00	5.00	5.50		82.50		
245	260		Sqm	1	15.00	5.00	6.20	5.60		84.00		
260	275		Sqm	1	15.00	6.20	6.00	6.10		91.50		
275	285.5		Sqm	1	10.50	6.00	6.00	6.00		63.00		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0	15		Sqm	1	15.00	5.00	5.30	5.15		77.25		
15	30		Sqm	1	15.00	5.30	5.80	5.55		83.25		
30	45		Sqm	1	15.00	5.80	5.55	5.68		85.13		
45	60		Sqm	1	15.00	5.55	5.80	5.68		85.13		
60	74.1		Sqm	1	14.10	5.60	2.80	4.20		59.22		
74.1	85.8		Sqm	1	11.70	2.80	2.50	2.65		31.01		
		21th Cross Road (W0969)										
0	15		Sqm	1	15.00	7.90	6.20	7.05		105.75		
15	20.2		Sqm	1	5.20	6.05	5.50	5.78		30.03		
20.2	33		Sqm	1	12.80	5.60	6.00	5.80		74.24		
33	45		Sqm	1	12.00	6.00	6.80	6.40		76.80		
45	60		Sqm	1	15.00	5.60	6.60	6.10		91.50		
60	75		Sqm	1	15.00	6.60	6.70	6.65		99.75		
75	90		Sqm	1	15.00	6.70	6.65	6.68		100.13		
90	105		Sqm	1	15.00	6.65	6.70	6.68		100.13		
105	120		Sqm	1	15.00	6.70	6.70	6.70		100.50		
120	130		Sqm	1	10.00	6.70	6.70	6.70		67.00		
		Connecting Road-1 (W0608)										
0	3.9		Sqm	1	3.90	7.20	6.95	7.08		27.59		
3.9	15		Sqm	1	11.10	9.00	8.00	8.50		94.35		
15	23.8		Sqm	1	8.80	8.00	7.60	7.80		68.64		
		Dead End (W0965)										
0	15		Sqm	1	15.00	7.80	6.50	7.15		107.25		
15	23.8		Sqm	1	8.80	6.70	5.50	6.10		53.68		
23.8	24.9		Sqm	1	1.10	5.60	6.50	6.05		6.65		
24.9	36.9		Sqm	1	12.00	6.50	6.50	6.50		78.00		
		Connecting Road-2										
0	15		Sqm	1	15.00	5.90	5.90	5.90		88.50		
15	24		Sqm	1	9.00	5.90	5.90	5.90		53.10		
		1st A Cross Road (W0975)										
0	15		Sqm	1	15.00	7.70	7.90	7.80		117.00		
15	31.3		Sqm	1	16.30	7.90	8.00	7.95		129.59		
		18th A Cross Road (W0618)										
0	15		Sqm	1	15.00	5.80	5.60	5.70		85.50		
15	30		Sqm	1	15.00	5.60	5.60	5.60		84.00		
30	45		Sqm	1	15.00	5.60	5.50	5.55		83.25		
45	60		Sqm	1	15.00	5.50	4.90	5.20		78.00		
60	74.2		Sqm	1	14.20	5.60	4.90	5.25		74.55		
									Total Executed Quantity	**7015.93**	**15.00**	**105239.00**
									Tender Quantity	**7151.05**		
Item no.19		Providing and laying bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction in all respects complete as per specifications and directions of the Engineer in charge.										
		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0.00	12.40		Cum	1	12.40	7.65	6.80	7.23	0.04	3.58		
12.40	23.10		Cum	1	10.70	6.80	6.80	6.80	0.04	2.91		
		(W0616)										
0.00	15.00		Cum	1	15.00	4.90	5.20	5.05	0.04	3.03		
15.00	29.80		Cum	1	14.80	5.20	5.60	5.40	0.04	3.20		
		(W0983)										

Scanned by CamScanner

0.00	15.00		Cum	1	15.00	6.40	6.20	6.30	0.04	3.78		
15.00	30.00		Cum	1	15.00	6.20	6.30	6.25	0.04	3.75		
30.00	45.00		Cum	1	15.00	6.30	6.40	6.35	0.04	3.81		
45.00	62.50		Cum	1	17.50	6.40	5.45	5.93	0.04	4.15		
		(W0973)										
0.00	15.00		Cum	1	15.00	6.40	6.20	6.30	0.04	3.78		
15.00	30.00		Cum	1	15.00	6.20	6.30	6.25	0.04	3.75		
30.00	45.00		Cum	1	15.00	6.30	6.40	6.35	0.04	3.81		
45.00	58.20		Cum	1	13.20	6.40	5.45	5.93	0.04	3.13		
		1st Main Road (W0612)										
0.00	15.00		Cum	1	15.00	5.25	5.35	5.30	0.04	3.18		
15.00	30.00		Cum	1	15.00	5.35	6.60	5.98	0.04	3.59		
30.00	45.00		Cum	1	15.00	6.60	6.20	6.40	0.04	3.84		
45.00	60.00		Cum	1	15.00	6.20	6.05	6.13	0.04	3.68		
60.00	75.00		Cum	1	15.00	6.05	5.70	5.88	0.04	3.53		
75.00	90.00		Cum	1	15.00	5.70	5.90	5.80	0.04	3.48		
90.00	95.60		Cum	1	5.60	6.00	7.50	6.75	0.04	1.51		
95.60	105.00		Cum	1	9.40	7.50	7.30	7.40	0.04	2.78		
105.00	120.00		Cum	1	15.00	7.30	7.30	7.30	0.04	4.38		
120.00	124.00		Cum	1	4.00	7.30	8.20	7.75	0.04	1.24		
124.00	126.40		Cum	1	2.40	8.20	12.20	10.20	0.04	0.98		
126.40	135.00		Cum	1	8.60	12.20	12.30	12.25	0.04	4.21		
135.00	146.20		Cum	1	11.20	11.10	8.20	9.65	0.04	4.32		
146.20	160.00		Cum	1	13.80	8.20	8.70	8.45	0.04	4.66		
160.00	165.20		Cum	1	5.20	8.70	5.80	7.25	0.04	1.51		
165.20	180.00		Cum	1	14.80	5.80	6.15	5.98	0.04	3.54		
180.00	195.00		Cum	1	15.00	6.15	6.20	6.18	0.04	3.71		
195.00	201.40		Cum	1	6.40	6.20	6.50	6.35	0.04	1.63		
201.40	205.10		Cum	1	3.70	6.50	3.70	5.10	0.04	0.75		
205.10	207.50		Cum	1	2.40	3.70	1.60	2.65	0.04	0.25		
		1st Main 3rd Cross (W0989)										
0.00	15.00		Cum	1	15.00	5.65	5.60	5.63	0.04	3.38		
15.00	30.00		Cum	1	15.00	5.60	5.65	5.63	0.04	3.38		
30.00	45.00		Cum	1	15.00	5.65	5.45	5.55	0.04	3.33		
45.00	61.20		Cum	1	16.20	5.45	5.20	5.33	0.04	3.45		
		2nd Main Road (W0616)										
0.00	15.00		Cum	1	15.00	7.10	7.10	7.10	0.04	4.26		
15.00	16.70		Cum	1	1.70	7.10	7.10	7.10	0.04	0.48		
16.70	18.00	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
18.00	30.00		Cum	1	12.00	5.20	5.40	5.30	0.04	2.54		
30.00	45.00		Cum	1	15.00	5.40	5.60	5.50	0.04	3.30		
45.00	60.00		Cum	1	15.00	5.60	5.50	5.55	0.04	3.33		
60.00	75.00		Cum	1	15.00	5.50	5.30	5.40	0.04	3.24		
75.00	90.00		Cum	1	15.00	5.30	5.65	5.48	0.04	3.29		
90.00	105.00		Cum	1	15.00	5.65	7.00	6.33	0.04	3.80		
105.00	120.00		Cum	1	15.00	7.00	6.70	6.85	0.04	4.11		
120.00	135.00		Cum	1	15.00	6.70	6.70	6.70	0.04	4.02		
135.00	150.00		Cum	1	15.00	6.70	6.70	6.70	0.04	4.02		
150.00	164.00		Cum	1	14.00	6.40	5.20	5.80	0.04	3.25		
164.00	180.00		Cum	1	16.00	5.20	6.20	5.70	0.04	3.65		
180.00	195.00		Cum	1	15.00	6.20	5.40	5.80	0.04	3.48		
195.00	210.00		Cum	1	15.00	5.40	6.70	6.05	0.04	3.63		
210.00	218.00		Cum	1	8.00	6.70	6.40	6.55	0.04	2.10		
218.00	219.50	No Work	Cum	1	0.00	0.00	0.00	0.00	0.04	0.00		
219.50	230.00		Cum	1	10.50	5.80	6.00	5.90	0.04	2.48		
230.00	245.00		Cum	1	15.00	6.00	5.00	5.50	0.04	3.30		
245.00	260.00		Cum	1	15.00	5.00	6.20	5.60	0.04	3.36		
260.00	275.00		Cum	1	15.00	6.20	6.00	6.10	0.04	3.66		
275.00	285.50		Cum	1	10.50	6.00	6.00	6.00	0.04	2.52		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0.00	15.00		Cum	1	15.00	5.00	5.30	5.15	0.04	3.09		
15.00	30.00		Cum	1	15.00	5.30	5.80	5.55	0.04	3.33		
30.00	45.00		Cum	1	15.00	5.80	5.55	5.68	0.04	3.41		
45.00	60.00		Cum	1	15.00	5.55	5.80	5.68	0.04	3.41		
60.00	74.10		Cum	1	14.10	5.60	2.80	4.20	0.04	2.37		
74.10	85.80		Cum	1	11.70	2.80	2.50	2.65	0.04	1.24		

Scanned by CamScanner

		21th Cross Road (W0969)											
0.00	15.00		Cum	1	15.00	7.90	6.20	7.05	0.04	4.23		
15.00	20.20		Cum	1	5.20	6.05	5.50	5.78	0.04	1.20		
20.20	33.00		Cum	1	12.80	5.60	6.00	5.80	0.04	2.97		
33.00	45.00		Cum	1	12.00	6.00	6.80	6.40	0.04	3.07		
45.00	60.00		Cum	1	15.00	5.60	6.60	6.10	0.04	3.66		
60.00	75.00		Cum	1	15.00	6.60	6.70	6.65	0.04	3.99		
75.00	90.00		Cum	1	15.00	6.70	6.65	6.68	0.04	4.01		
90.00	105.00		Cum	1	15.00	6.65	6.70	6.68	0.04	4.01		
105.00	120.00		Cum	1	15.00	6.70	6.70	6.70	0.04	4.02		
120.00	130.00		Cum	1	10.00	6.70	6.70	6.70	0.04	2.68		
		Connecting Road-1 (W0608)										
0.00	3.90		Cum	1	3.90	7.20	6.95	7.08	0.04	1.10		
3.90	15.00		Cum	1	11.10	9.00	8.00	8.50	0.04	3.77		
15.00	23.80		Cum	1	8.80	8.00	7.60	7.80	0.04	2.75		
		Dead End (W0965)										
0.00	15.00		Cum	1	15.00	7.80	6.50	7.15	0.04	4.29		
15.00	23.80		Cum	1	8.80	6.70	5.50	6.10	0.04	2.15		
23.80	24.90		Cum	1	1.10	5.60	6.50	6.05	0.04	0.27		
24.90	36.90		Cum	1	12.00	6.50	6.50	6.50	0.04	3.12		
		Connecting Road-2										
0.00	15.00		Cum	1	15.00	5.90	5.90	5.90	0.04	3.54		
15.00	24.00		Cum	1	9.00	5.90	5.90	5.90	0.04	2.12		
		1st A Cross Road (W0975)										
0.00	15.00		Cum	1	15.00	7.70	7.90	7.80	0.04	4.68		
15.00	31.30		Cum	1	16.30	7.90	8.00	7.95	0.04	5.18		
		18th A Cross Road (W0618)	Extra		NEW							
0.00	15.00		Cum	1	15.00	5.80	5.60	5.70	0.04	3.42		
15.00	30.00		Cum	1	15.00	5.60	5.60	5.60	0.04	3.36		
30.00	45.00		Cum	1	15.00	5.60	5.50	5.55	0.04	3.33		
45.00	60.00		Cum	1	15.00	5.50	4.90	5.20	0.04	3.12		
60.00	74.20		Cum	1	14.20	5.60	4.90	5.25	0.04	2.98		
									Total Executed Quantity	**280.64**	**10000.00**	**2806372.00**
									Tender Quantity	**286.04**		

Item no.20 Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface/ Concrete Surface: Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35 standards specified. The finished surface to be level, uniform and free from streaks and holes complete as per specifications and directions of the Engineer in charge.

		Kuvempu Layout										
		2nd Main Road 1st Cross Road (W0977)										
0.00	23.10		Sqm	2	23.10	0.10	0.10	0.10		4.62		
		(W0616)										
0.00	29.80		Sqm	2	29.80	0.10	0.10	0.10		5.96		
		(W0983)										
0.00	62.50		Sqm	2	62.50	0.10	0.10	0.10		12.50		
		(W0973)										
0.00	58.20		Sqm	2	58.20	0.10	0.10	0.10		11.64		
		1st Main Road (W0612)										
0.00	207.50		Sqm	2	207.50	0.10	0.10	0.10		41.50		
		1st Main 3rd Cross (W0989)										
0.00	61.20		Sqm	2	61.20	0.10	0.10	0.10		12.24		
		2nd Main Road (W0616)										
0.00	282.70		Sqm	2	282.70	0.10	0.10	0.10		56.54		
		Munikempanna Layout										
		1st Cross Road (W0973)										
0.00	85.80		Sqm	2	85.80	0.10	0.10	0.10		17.16		
		21th Cross Road (W0969)										
0.00	130.00		Sqm	2	130.00	0.10	0.10	0.10		26.00		

Scanned by CamScanner

		Connecting Road-1 (W0608)										
0.00	23.80		Sqm	2	23.80	0.10	0.10	0.10		4.76		
		Dead End (W0965)										
0.00	36.90		Sqm	2	36.90	0.10	0.10	0.10		7.38		
		Connecting Road-2										
0.00	24.00		Sqm	2	24.00	0.10	0.10	0.10		4.80		
		1st A Cross Road (W0975)										
0.00	31.30		Cum	2	31.30	0.10	0.10	0.10		6.26		
		18th A Cross Road (W0618)										
0.00	74.20		Cum	2	74.20	0.10	0.10	0.10		14.84		
									Total Executed Quantity	**226.20**		
									Tender Quantity	**221.80**		
									Quantity upto 125%	**226.20**	**460.00**	**104052.00**

Item no.21 Providing and Constructing dry lean cement concrete mix CC1:5:10 Base with OPC 25mm and down size graded granite metal coarse aggregate at 0.86cum and fine aggregates @ 0.58cum over a prepared sub-base coarse and fine aggregate conforming to IS: 383-2016, aggregate cement ratio not to exceed 15:1. Aggregate gradation after blending to be as per Table 600-1, optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 tonnes vibratory roller, finishing and curing complete as per specifications and directions of the Engineer in charge.

		Kaveri Layout										
		Krishna Nivas House (W1309)										
		South to North										
0	15		Cum	1	15	4.7	5.2	4.95	0.15	11.14		
15	30		Cum	1	15	5.2	5.2	5.2	0.15	11.70		
30	45		Cum	1	15	5.2	5.15	5.175	0.15	11.64		
45	60		Cum	1	15	5.15	5.25	5.2	0.15	11.70		
60	75		Cum	1	15	5.25	5	5.125	0.15	11.53		
75	90		Cum	1	15	5	5.35	5.175	0.15	11.64		
90	91.2		Cum	1	1.2	5.35	5.35	5.35	0.15	0.96		
		Joseph House Road (W0884)										
		East to West										
0	11.6		Cum	1	11.6	5.85	5.85	5.85	0.15	10.18		
11.6	25		Cum	1	13.4	5	5.25	5.125	0.15	10.30		
25	40		Cum	1	15	5.25	5	5.125	0.15	11.53		
40	45.8		Cum	1	5.8	5	5	5	0.15	4.35		
		Moto Works Oppo. (W1299)										
		North to South										
0	15		Cum	1	15	4.45	4.85	4.65	0.15	10.46		
15	30		Cum	1	15	4.85	5.6	5.225	0.15	11.76		
30	45		Cum	1	15	5.6	5.5	5.55	0.15	12.49		
45	60		Cum	1	15	5.5	5	5.25	0.15	11.81		
60	75		Cum	1	15	5	5.5	5.25	0.15	11.81		
75	90		Cum	1	15	5.5	5.1	5.3	0.15	11.93		
90	105		Cum	1	15	5.1	5.3	5.2	0.15	11.70		
105	120		Cum	1	15	5.3	5.75	5.525	0.15	12.43		
120	132		Cum	1	12	5.75	7.15	6.45	0.15	11.61		
		Cross Road 1 (W0870)										
		West to East										
0	15		Cum	1	15	4.55	4.6	4.575	0.15	10.29		
15	25.6		Cum	1	10.6	4.6	5.35	4.975	0.15	7.91		
		Cross Road 2 (W0862)										
		West to East										
0	15		Cum	1	15	5.35	5.2	5.275	0.15	11.87		
15	30		Cum	1	15	5.2	5.55	5.375	0.15	12.09		
30	33		Cum	1	3	5.55	5.5	5.525	0.15	2.49		
		Cross Road (W1297)										
		South to North										
0	15		Cum	1	15	5.4	5.1	5.25	0.15	11.81		
15	30		Cum	1	15	5.1	4.7	4.9	0.15	11.03		
30	45		Cum	1	15	4.7	4.6	4.65	0.15	10.46		
45	60		Cum	1	15	4.6	4.5	4.55	0.15	10.24		
60	75		Cum	1	15	4.5	4.3	4.4	0.15	9.90		

Scanned by CamScanner

75	90												
90	105		Cum	1	15	4.3	4	4.15	0.15	9.34			
			Cum	1	15	4	4	4	0.15	9.00			
		Kuvempu Layout											
		2nd Main 1st Cross Road (W0977)											
0	11.3												
11.3	21.7		Cum	1	11.3	6.8	6.65	6.725	0.15	11.40			
21.7	25.4		Cum	1	10.4	6.65	5.5	6.075	0.15	9.48			
25.4	35.1		Cum	1	3.7	5.2	5.8	5.5	0.15	3.05			
35.1	48.5		Cum	1	9.7	5.3	6.25	5.775	0.15	8.40			
			Cum	1	13.4	6.25	6.7	6.475	0.15	13.01			
									Total Executed Quantity	**374.45**			
									Tender Quantity	**270.56**			
									Quantity upto 125%	**338.20**	**5000.00**	**1691000.00**	
									Quantity Above 125%	**36.25**	**4400.08**	**159511.00**	
Item no.22		Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire chargedof machines,all lead and lift charges etc., complete as per specifications. -and as per the directions of the Engineer-in-charge of the work												
		Kaveri Layout											
		Krishna Nivas House (W1309)											
		South to North											
0	15		Cum	1	15.00	4.70	5.20	4.95	0.15	11.14			
15	30		Cum	1	15.00	5.20	5.20	5.20	0.15	11.70			
30	45		Cum	1	15.00	5.20	5.15	5.18	0.15	11.64			
45	60		Cum	1	15.00	5.15	5.25	5.20	0.15	11.70			
60	75		Cum	1	15.00	5.25	5.00	5.13	0.15	11.53			
75	90		Cum	1	15.00	5.00	5.35	5.18	0.15	11.64			
90	91.2		Cum	1	1.20	5.35	5.35	5.35	0.15	0.96			
		Joseph House Road (W0884)											
		East to West											
0	11.6		Cum	1	11.60	5.85	5.85	5.85	0.15	10.18			
11.6	25		Cum	1	13.40	5.00	5.25	5.13	0.15	10.30			
25	40		Cum	1	15.00	5.25	5.00	5.13	0.15	11.53			
40	45.8		Cum	1	5.80	5.00	5.00	5.00	0.15	4.35			
		Moto Works Oppo. (W1299)											
		North to South											
0	15		Cum	1	15.00	4.45	4.85	4.65	0.15	10.46			
15	30		Cum	1	15.00	4.85	5.60	5.23	0.15	11.76			
30	45		Cum	1	15.00	5.60	5.50	5.55	0.15	12.49			
45	60		Cum	1	15.00	5.50	5.00	5.25	0.15	11.81			
60	75		Cum	1	15.00	5.00	5.50	5.25	0.15	11.81			
75	90		Cum	1	15.00	5.50	5.10	5.30	0.15	11.93			
90	105		Cum	1	15.00	5.10	5.30	5.20	0.15	11.70			
105	120		Cum	1	15.00	5.30	5.75	5.53	0.15	12.43			
120	132		Cum	1	12.00	5.75	7.15	6.45	0.15	11.61			
		Cross Road 1 (W0870)											
		West to East											
0	15		Cum	1	15.00	4.55	4.60	4.58	0.15	10.29			
15	25.6		Cum	1	10.60	4.60	5.35	4.98	0.15	7.91			
		Cross Road 2 (W0862)											
		West to East											
0	15		Cum	1	15.00	5.35	5.20	5.28	0.15	11.87			
15	30		Cum	1	15.00	5.20	5.55	5.38	0.15	12.09			
30	33		Cum	1	3.00	5.55	5.50	5.53	0.15	2.49			
		Cross Road (W1297)											
		South to North											
0	15		Cum	1	15.00	5.40	5.10	5.25	0.15	11.81			
15	30		Cum	1	15.00	5.10	4.70	4.90	0.15	11.03			
30	45		Cum	1	15.00	4.70	4.60	4.65	0.15	10.46			
45	60		Cum	1	15.00	4.60	4.50	4.55	0.15	10.24			
60	75		Cum	1	15.00	4.50	4.30	4.40	0.15	9.90			
75	90		Cum	1	15.00	4.30	4.00	4.15	0.15	9.34			

Scanned by CamScanner

90	105		Cum	1	15.00	4.00	4.00	4.00	0.15	9.00		
		Kuvempu Layout										
		2nd Main 1st Cross Road (W0977)										
0	11.3		Cum	1	11.30	6.80	6.65	6.73	0.15	11.40		
11.3	21.7		Cum	1	10.40	6.65	5.50	6.08	0.15	9.48		
21.7	25.4		Cum	1	3.70	5.20	5.80	5.50	0.15	3.05		
25.4	35.1		Cum	1	9.70	5.30	6.25	5.78	0.15	8.40		
35.1	48.5		Cum	1	13.40	6.25	6.70	6.48	0.15	13.01		
										Total Executed Quantity	374.45	
										Tender Quantity	270.56	
										Quantity upto 125%	338.20	6800.00	2299760.00
										Quantity Above 125%	36.25	6266.43	227169.00
												Sub Total	45674647.00
												For 12% Applicable GST	5480958.00
												Total Amount	51155605.00

Assistant Engineer
BBMP

Assistant Executive Engineer
BBMP

Executive Engineer
BBMP

Technical Sanction
Accorded For Rs. 51155605.00
Head of A/C..P.3873.....
CER NO :...22..... Dt:31.03.2022

Scanned by CamScanner